



VOL. XXXII.

CLEVELAND, SEPTEMBER 7, 1905.

No. 10.

## The Manufacture of Chain Cables.

L. B. POWELL.

One of the most important branches of modern chain manufacture is the production of the heavy cable chains

must be met by the chain manufacturer in order to have the chain accepted by the government inspectors who pass on all



MAKING  $1\frac{1}{8}$  STUD LINK CABLE CHAIN AT THE RATE OF TWELVE FATHOMS PER DAY OR ONE LINK EVERY THREE MINUTES.

used as anchor chains on vessels, and it is the only branch of this manufacture in which the government has so far interested itself as to prepare certain requirements which

of the material used at the various ship yards. There have been several different sets of requirements compiled which govern the quality of the chain, according to whether the

chain is for government use, in which case the requirements are quite high, or whether the chain is to be used only on vessels built for and by private concerns, in which case the requirements are easily complied with by the chain manufacturer.

Chain made for private vessels have only to comply with the table of tests and dimensions adopted by the American Ship Masters' Association, compiled principally for the purpose of securing uniform dimensions of link in order that the chain will fit any standard make of windlass. The weight per fathom does not have to be considered; neither does the quality of the iron used, save that of course a fairly good fibrous iron should be used of sufficient ductility and strength as to give satisfactory service. When the manufacturer has gauged the links and subjected the chain to the required proof strain, that is all that is expected.

It is quite another thing to make chain for government use and comply with the rigid requirements of material, weight and test, as called for in making chain for lighthouse vessels, for example. The following extract from the lighthouse board requirements for chain will give an idea of what must be secured in the way of iron:

"The bars must be of homogenous iron and must not contain more than five one-hundredths of 1 percent of carbon nor less than eight one-hundredths nor more than fourteen one-hundredths of 1 percent of phosphorus, nor shall the sum of the carbon and phosphorus be more than fifteen one-hundredths of 1 percent. The iron must not contain more than one-hundredth of 1 percent of sulphur nor more than ten one-hundredths of 1 percent of either silicon or manganese.

"This iron in finished bars must have a tensile strength of not less than 48,000 lbs. per square inch nor more than 52,000 lbs. per square inch, an elastic limit of about 60 percent of the breaking strain, an elongation of at least 30 percent in a length of 8 in. and a contraction of area of at least 40 percent.

"Bolts cut from 1 percent of these bars must stand bending cold until the sides are brought parallel and separated from each other not more than one-half inch without showing signs of rupture. Bolts must also stand bending at red heat until sides are close together without any sign of fracture at the bend. Such bolts as may be nicked and broken cold by slow bending must show fibrous. One percent of these bolts will be made into test specimens of three links and this triplet must stand a pull of at least 39,000 lbs. to the square inch of the sectional area of the link in a 1½ in. chain.

"From each chain of 120 fathoms, samples, not exceeding three in number of three links each, will be taken from any part of any shot. These samples will be pulled to destruction at the works or at the nearest standard testing machine under the supervision of an agent of the lighthouse board."

From this it will be seen that not only must a special high grade of iron be secured that will pass the chemical and physical tests of the lighthouse requirements, but also after each 120 fathom shot is made up complete, at least nine links will be cut out to be pulled to destruction and these sample links will, of course, have to be replaced at the manufacturer's expense before the chain is accepted. The breaking strain required by the lighthouse vessel requirements is considerably higher than that required by the American Ship Masters' Association and even higher than that required by Lloyd's Register of Shipping and therefore calls for a chain of high tensile strength and elasticity.

It is evident from the use to which cable chains are placed that the material used in their manufacture must possess peculiar qualities other than superior strength. In addition to possessing good welding qualities the iron must also possess a great deal of ductility and elasticity—the ability to yield

slightly to a sudden strain and when that strain is removed, to resume its former condition. A chain made from iron possessing high tensile strength only would be unsuited for cable chain for the reason that while it would resist to a high degree the strain placed upon it, it would in a short time be pulled stiff and thus be worthless for anchor chain use, while a cable chain possessing high tensile strength and elasticity also will give slightly under the sudden strains incidental to its use, but when the strain is removed, will be able to resume its former condition and thus fulfill in a satisfactory manner the use to which it is intended.

In selecting the material from which cable chain is to be made it is advisable to subject samples thereof to tests in order to determine whether or not the quality of the material is as desired.

Most iron, unless especially rolled from selected material, is liable to be either "red short" or "cold short," and it is well to test samples of iron for both. "Red short" iron is iron that will crack when worked at a heat, and is caused from too much sulphur in the ore. In order to test for "red short" iron it is usual to heat the sample bar at the end, open the end and bend the horns back upon themselves. If this can be accomplished without sign of crack or flaw the iron is free from too much sulphur. In order to test for "cold short" iron the sample bar should be bent double on itself while cold, and if this is accomplished without sign of crack or flaw, the iron is free from too much phosphorus, which causes the iron to be "cold short." Another and probably the best way to test for "cold short" iron is to nick the sample bar with a chisel and bend it back upon itself. This will fracture the iron and show the fibre, which in good iron will be long and tough and of a dark grey color. Iron which may show traces of being "cold short" may still be acceptably used for the manufacture of chain cables for the reason that the iron is always at a red heat while the chain is in the process of manufacture, but for the purpose of insuring the most satisfactory quality of product, it is better to use an iron that passes both tests satisfactorily.

Leaving the subject of material, which is of the highest importance on account of the valuable lives and property dependent thereon, we come to the subject of forming this material, link by link, into the long cable chain.

The mention of chain occurs in history as far back as our records go and even in the Bible mention was made of chain, although there is nothing shown in the old records to enable us to determine the shape of the links or the material from which they were made. From the nature of the product and its many uses it is safe to argue that chain is an ancient institution dating back to the first use of iron in any shape.

While modern methods and machinery have so developed the industry that the old and the new processes of manufacture have little in common, yet the main feature of each process still remains the raising of the material to a welding heat and effecting a homogeneous union by pounding the ends together.

All chain used for ship cables is strictly hand made chain, sometimes called "off the rod" chain, from the fact that the material is cut off of the long rod, bent into shape and welded by blows of hand hammers and sometimes called "dolly" chain, from the fact that after the weld has been accomplished by means of blows of the hand hammers, the weld is smoothed under a "dolly" in order to reduce the swell of the weld to the same size as the balance of the link and also to remove the marks left by the hammer blows. For the purpose of illustrating in detail the successive steps incidental to the manufacture of ship cable chain, taking each operation step by step from the cutting of the long bar into pieces to the finishing touches placed on the completed

chain, we reproduce herewith a photograph showing the manner in which  $1\frac{3}{4}$  in. stud link cable chain is made. The chain-maker can be seen holding the link of chain in his tongs, while his two helpers are smoothing up the weld by means of hammer blows on the head of the dolly. The chain-maker and his helpers can, in the usual eight-hour day, turn out about twelve fathoms per day, equal to about 1,800 pounds and at the rate of one link welded every three minutes.

From the long bar of iron pieces are cut on a power shear to a predetermined length so that each piece is the proper length to make one link of the chain. These pieces are placed in the fire at the opening shown at the right side of the fire, where an inclined rack is shown, on which the pieces are laid so that they are being slowly heated by the waste heat of the fire. The lowest piece on this rack is withdrawn from the front of the fire with large tongs and placed down in the glowing bed of the fire, where it is quickly brought to a red heat. When this heat is reached, the piece is withdrawn, while another piece of iron is taken from the rack and placed in the fire in its stead. The first piece is now placed in the link bending machine which stands near the fire and by means of a long arm operated by the helpers the piece is bent around a link former or mandrel into a U shape. This U-shape link is now placed back in the fire for reheating and in the meantime another piece is bent into U shape, these operations being successive and timed with exact precision. Owing to the fact that iron at a high temperature scales rapidly when brought into contact with the air, it is customary to take some steps to prevent this scale forming on the part of the link that is being welded. For this purpose, when the iron having reached a white heat, is withdrawn from the fire, the open ends are first dipped in a pan of sand conveniently near, hooked through the last link welded and placed on the face of the anvil. The helpers now pound one end of the link with their hammers until it has been tapered down to an angle of 60 percent with the diameter of the bar, and when one end is thus drawn down or "scarfed," as it is called, the link is turned over and the other end scarfed in a like manner. The union of the sand and scale form a sort of liquid slag which is expelled by the blows of the hammers, leaving the scarfs clean and free to weld. On the side of the anvil towards the chain-maker is the beck-horn which has its face hollowed out to receive the link, and on the opposite side of the anvil, through which the beck-horn projects, is attached a dolly, which is hinged to the projecting end of the beck-horn in such a manner that when the dolly is lowered the groove in the under part of its head will meet the groove in the beck-horn.

After the ends of the link have been scarfed out, during which time the dolly is swung back out of the way, the link is placed against the beck-horn while the ends of the link are pounded towards each other in such a way that the ends, being scarfed in opposite directions, will meet and form the continuity of the link. The link is then placed flat on the face of the anvil and the scarfed ends pounded tightly together and the link then placed back in the fire for the final and welding heat. When this has been reached, the link is again withdrawn, the end to be welded placed flat on the face of the anvil while the helpers with their hammers pound the scarfed ends together, thus welding the ends of the link at the point of contact. The link is then placed in the groove of the beck-horn, the hinged dolly lowered to rest on the top of the welded portion, while the helpers pound the top of the dolly with their hammers as the chain-maker moves the link backwards and forwards on the beck-horn, at times turning the link entirely over so that all portions of the weld secure a thorough working necessary to insure a perfect weld.

The link is then placed on the face of the anvil while a

cast iron stud is inserted in the center of the link, the link being narrowed by hammer blows to grip and hold the stud in place. These studs have their ends hollowed out to correspond with the rounded surface of the link and are used for the purpose of increasing the strength of the link and for preventing the link narrowing when subjected to a strain, as would a similar unstudded chain. The placing of the stud in the center of the link increases the strength of the chain one-third and the proof and breaking tests of stud link cable chain are one-third higher than chain of the same size, made close link and without studs.

After a shot of chain has reached the proper length it is fitted with end links and then subjected to the required proof strain, during which the links are gauged to see that they are of proper dimensions to fit in the windlass for which they are made. After the testing the chain is dipped in a vat of blacking in order to protect it from rust while in transit and is then ready for shipment.

The fires in which the links are heated are of an ordinary brick type and the fuel used is a 24-hour coke, which is crushed to certain sizes according to the size of chain to be made. Artificial draft or blast is forced into the fire in order to maintain the high temperature required, this blast entering the fire from one side and being brought up into the body of the fire through a water cooled tuyere, which consists of a conical-cast iron piece with a hole through its center through which the air passes. The air passage is encircled by a chamber containing flowing water which prevents the tuyere being burnt out by the intense heat of the fire. The blast entering the fire naturally results in part of the

TABLE OF TESTS AND DIMENSIONS OF LINKS OF STUD LINK CABLE CHAIN.

Size of Chain Inches.	Requirements of American Ship Masters' Association.				Requirements of Lloyd's Register of Shipping.		
	Dimensions of Links.		Weight per fath- om, lbs.	Proof Test in Tons.	Length in Fathoms.	Proof Test in Tons.	Breaking Test in Tons.
	Outside Length Inches	Outside Width Inches					
1 3/4	5	3 1/4	49	13 1/4	165	13 1/4	20 1/4
1 1/2	5 1/2	3 3/4	61	18	165	18	27 1/2
1 1/4	6 1/4	4 1/8	74	22 1/2	195	22 1/2	34 1/4
1 3/16	7 1/8	4 1/2	90	25 1/2	210	25 1/2	42 1/4
1 1/8	7 3/4	4 3/4	97	31	210	31	46 1/2
1 3/8	8 1/4	5 1/8	110	34	210	34	51
1 1/2	8 3/4	5 3/8	113	37 1/2	210	37 1/2	55 1/2
1 3/4	9 1/4	5 3/4	127	40 1/2	210	40 1/2	58 7/10
1 7/8	9 3/4	5 7/8	150	47 1/2	240	47 1/2	66 5/10
1 3/4	10	6 1/4	173	55 1/2	240	55 1/2	77 1/2
1 3/8	10 1/2	6 3/4	203	63 3/10	240	63 1/2	88 5/10
1 15/16	10 3/4	7	215	67 1/2	270	67 1/2	94 1/2
2	11 1/8	7 1/4	233	72	270	72	100 8/10
2 1/8	12	7 3/4	276	81 1/4	270	81 1/4	113 1/4
2 1/4	13	8 1/4	300	91	270	91 1/4	127 1/2

flames and heat being forced out the front of the fire against the workmen and in order to counteract this, it is necessary to provide large fans which are suspended over the workmen and operated from the shafting of the shop.

As the strength of a chain is that of its weakest link, so is the strength of a link that of its weakest point, which is invariably in the weld. Notwithstanding the care taken in forming a weld it cannot be relied upon until given the test of continued usage and it is an acknowledged fact that by being welded the chain link loses 50 percent of its theoretical strength—in other words, a chain link being formed by the union of its two sides should possess twice the strength of one side, but this is not the case, as repeated tests have shown that the strength of a welded link is only that of the single bar of material, instead of that of double the bar, as might be expected. A test made of a great number of welded stud links shows that over 75 percent of the breaks occurred at or near the weld, which proves conclusively that the welds were not homogeneous. This weakness is due in part to the repeated working of the material at the welded juncture de-



LAUNCH OF BATTLESHIP KANSAS AT THE YARD OF THE NEW YORK SHIP BUILDING CO., CAMDEN, N. J.

[For description see *Marine Review*, August 17.]

stroying the fibre of the iron and in part to the fact that the iron was either just a little too high or a little too low in temperature to afford the opportunity of securing a perfect and homogeneous union at that point.

Government inspection of vessels, both while building and after in use, does much to reduce to a minimum the chances of accidents occurring through defective chains and as often the safety of a huge vessel, with its precious cargo of human lives, is dependent upon the quality of material and weld of the anchor chain, such inspections cannot be too rigid.

#### METEOR, NOW NELSON BLOOM

The Meteor, the queen of the lakes in the early sixties, took out a cargo of lumber from Ontonagon last week. Her name has been changed to the Nelson Bloom and she has had a spectacular career. No one would recognize the present craft as once having been the trimmest and fastest passenger and packet boat which plied these waters.

Many remember the Meteor. She was a two-wheel propeller and was built at a cost of \$110,000. She was launched in 1863 and ran between Cleveland and the head of the lakes. She was owned by J. T. Whiting & Co., of Detroit, and her handsome appearance and speed attracted much attention.

The Meteor's collision with the Pewabic in Lake Huron in 1865 is still vivid in the memories of many of the old time residents. One boat was bound up and the other down. They went together in the early evening with full steam. The Pewabic was sunk and many lives were lost. The

Meteor was damaged only slightly. She was in charge of Capt. Thomas Wilson, and the Pewabic was commanded by Capt. George McKay, who is still living at Cleveland. Both were experienced sailors and what caused the collision is one of the unsolved mysteries. Shortly afterward the Meteor was sold at admiralty sale and was bid in by Mr. Mason, who was at that time president of the Quinev mine.

About a quarter of a century ago the Meteor was burned while lying at dock at Detroit. A few years later the hull was purchased and was rebuilt into a sailing craft, and named the Nelson Bloom. During the past seven or eight years she has been used almost exclusively as a tow barge, although she still carries a full canvas rigging, which is brought into use occasionally.

The Nelson Bloom is owned by Harrow, Lozen & Baker and is in charge of Capt. J. P. Harrow, who has sailed the lakes since 1857.

The Norwegian collier Tricolor, which went ashore with a cargo of coal near Cape Mendocino, Cal., on July 24, has been abandoned by the underwriters. Lloyds' surveyor (Captain John Metcalfe) and James Dickie having reported that the place where she lies is so rocky that any attempt to save her would be futile. The surveyors were taken on the tug Ranger to a spot about half a mile from the vessel, which they tried to board from a life-saving boat, but heavy seas rendered this impossible. The underwriters will not even try to save any of the machinery. The Tricolor cost about \$300,000 and is hardly a year old.



## SOLID BULKHEADS VS. WATERTIGHT DOORS

This is a subject which is now, more than any other, agitating English naval engineers and the authorities at Whitehall as well as the technical and newspaper press of Great Britain. On one side of the controversy are those who would do away with bulkhead doors altogether, and on the other those who would not avoid one difficulty by rushing into another.

Everyone realizes that the weakness of the bulkhead systems of warships and the great passenger liners is that they have many bulkhead doors which sad experience proves are likely to be left open when it is most necessary that they should be closed. The party of the first part, referred to above, a leader among which is Vice Admiral Lord Charles Beresford, believe that the way to repair the weak spot in the bulkhead system is to close up all the doors, ignoring the fact that openings are absolutely necessary to efficiency in the working of the ship and to afford means of escape from one compartment to another. But the party of the second part, by far the larger party of this controversy, favor a solution, not an avoidance of the problem.

Every British technical journal of recent date and a great many newspapers which devote serious attention to naval and marine engineering topics give evidence that this problem of solid bulkheads or watertight doors is a growing one, and that it has gone too far before the eyes of the public to admit of anything less than a rational and finally satisfactory solution. The admiralty minute upon the Victoria disaster is, in nine cases out of ten, drawn upon for evidence that bulkhead openings are not necessarily a source of weakness, but become so by the fact that the proper provision is not made for the closing of these openings in time of danger. Over and over again is printed the dictum of "their lordships" that "the general structural arrangements of the Victoria with the arrangement of watertight doors, armor belt, and protected deck, did not by any fault of principle contribute to the loss of the ship; but that, on the contrary, had the watertight doors, hatches and ports been closed, the ship would have been saved, notwithstanding the crushing blow which she received from the Camperdown." To this one able expert adds, and in doing so he voices a majority opinion, not only of the men who write about ships, but those who officer them, that "what was true twelve years ago is equally true in principle to-day, while scientific progress has served to make its application more effective than ever. There is as little prospect of watertight bulkhead doors being abolished in our warships, as there is of armor belting being done away with."

Another writer in a technical journal tells us that "their lordships have decided to do away, as far as possible, with all watertight doors in the athwartship bulkheads of battleships and cruisers of late design, including the Minotaur now building. This important modification has, of necessity, led to a reconsideration of the means of egress and ingress between the main compartments, and as a solution of this difficulty it has been definitely decided to install lifts wherever possible. This innovation is likely to prove both convenient and useful, as, owing to the great depth of hold in our latest type of warships, ladders would be as much out of place in them as stairways would be in our lofty hotels."

That the closing of all bulkhead openings and the installation of lifts as a means of ingress and egress to the compartments should have been received with derision is not remarkable, and those who do not deride the idea take pains to point out that the admiralty is removing one complication and adding another which will probably give rise to greater

difficulties than those encountered in the operation of the doors.

A few writers come out plainly, and severely berate the admiralty for dodging the whole problem instead of casting about for a solution of its perplexities. One of these reminds the authorities at Whitehall that while they are considering the abolition of means of communication between the compartments, the American navy has found a way out of its difficulty by adopting electrically operated bulkhead doors. In other words, the American designer instead of reducing the importance of the doors has augmented their importance. He saw that the old bulkhead door was a source of weakness and proceeded to find a better door; he has never seriously considered doing away with the doors altogether. He has increased the rank of the bulkhead door to that of an important factor in maintaining the safety and efficiency of a warship at all times, and under all circumstances.

It certainly seems most inopportune at this time when a satisfactory power door has just been evolved to talk of doing away with bulkhead openings altogether because the obsolete bulkhead door is unsatisfactory. To advocate that no doors shall be used precisely at the moment when a safe door has completed its practical evolution and development and has withstood the hard test of actual use aboard ships, is, indeed, somewhat more than inopportune—it is almost ridiculous.

Ship designers have before this decreed that vessels should be built without bulkhead doors. Then the men who had to go to sea in such ships and who were responsible for working them arose and protested until the doors were restored. They found that means of communication from compartment to compartment were absolutely necessary, and so these doors, the weakness of which was all the time acknowledged, continued to be used, and it is a safe prophecy that the time when all openings in bulkheads will be done away with is afar off.

It will be a matter for legitimate pride and satisfaction in America if the English naval designer adopts the way out of his perplexities which his American brother has found in the adoption of the so-called "long-arm" system of electrically operated bulkhead doors and armor hatches. This system is now in operation on or under contract for thirty-two of the newest and most powerful ships in the United States navy, including the cruisers and battleships of the Colorado and Montana type. "It will be interesting to know," remarks the naval expert of the *Western Morning News* of Plymouth, England, "whether the authorities at Whitehall have seriously taken into consideration the solution of the problem which has recommended itself to the navy department at Washington. The authorities of the United States navy appear to be more completely impressed in favor of the "long-arm" system year by year, and it would not be surprising if the present board of admiralty did not strictly investigate its claims before embarking upon a method of subdivision which can not fail to lead to great inconvenience, and might in certain circumstances be inimical to safety owing to the impossibility of getting from one compartment to another and insuring satisfactory ventilation."

It is apparent from the merits of the case, as well as from this and other samples of the manner in which British naval experts treat the subject, that the admiralty will have a hard time convincing the public that the way out of its bulkhead door perplexity is to close up these doors altogether instead of adopting a system of mechanical power-doors that, as the expert just quoted remarks, has proven more satisfactory in our navy year by year.



DEVOTED TO EVERYTHING AND EVERY INTEREST CONNECTED  
OR ASSOCIATED WITH MARINE MATTERS  
ON THE FACE OF THE EARTH.

Published every Thursday by

**The Penton Publishing Company**  
**CLEVELAND.**

CHICAGO:	MONADNOCK BUILDING.
PITTSBURG:	PARK BUILDING.
NEW YORK:	150 NASSAU STREET.

*Correspondence on Marine Engineering, Shipbuilding and  
Shipping Subjects Solicited.*

Subscription, \$3.00 per annum. To Foreign Countries, \$4.50.  
Subscribers can have addresses changed at will.

Change of advertising copy must reach this office on Thursday preced-  
ing date of publication.

The Cleveland News Co. will supply the trade with the MARINE REVIEW  
through the regular channels of the American News Co.

European Agents, The International News Company, Brems Building,  
Chancery Lane, London, E. C. England.

Entered at the Post Office at Cleveland, Ohio, as  
Second Class Matter.

SEPTEMBER 7, 1905.

There are twenty-two ships under order in great lakes shipyards for delivery next year. With the single exception of one steamer of 6,500 tons, these twenty-two ships are of the larger class, four of them capable of carrying 8,000 tons, three 9,000 tons, two 9,500 tons and twelve 10,000 tons and over. To this list must be added some twenty-one ships that were under order at the beginning of the year, having a carrying capacity of from 8,000 to 10,000 tons, making a total of forty-three ships which will be ready for next year's business, with a carrying capacity on a single trip of 397,500 tons, or in an average season of twenty trips, of 7,950,000 gross tons of ore. This is more ore than was carried down the lakes during the full season of 1894, just a little more than ten years ago. Consider what these orders mean to the general industry of the United States. In what manner could work be more widely distributed. A ship is a continuous contribution to labor from the moment the ore leaves the ground until it is worked into the various parts of the vessel. No single product of mankind calls for such diversified employment, for it brings into play a great variety of energy. When these ships go into commission 90 percent of their

actual value will have been distributed among the workmen of the United States. It means a continuous and active circulation of money, in other words, prosperity.

It is interesting to observe that the North German Lloyd Steamship Co. has just placed an order for a duplicate of the Kaiser Wilhelm II. The Kaiser Wilhelm II was built for the express purpose of relieving the Deutschland, of the Hamburg-American line, of her laurels as the fastest steamship afloat. The Deutschland has an engine power of 36,000 H. P., and has been able to maintain a speed of 23 knots. The Kaiser Wilhelm's engine power is 4,000 in excess of this, but her speed is virtually no greater than that of the Deutschland. Under favorable conditions she can make a trifle better time than the Deutschland, but it is so small as to be of no practical use in the time from dock to dock. Whether the duplicate of the Kaiser Wilhelm will be given greater engine power is not as yet known, but it is known that she will be equipped with reciprocating engines. This is especially significant in view of the fact that the Cunard line is now building two turbine steamers designed for 25 knots. Evidently the North German Lloyd Co. is not impressed with the practicability of the turbine for ocean service. British builders, however, are utilizing this form of engine in a variety of ways and recently conducted some experiments with a turbine-driven Channel steamer to show that it could be stopped and backed as quickly as any other.

Very few people realize that the commerce of the great lakes passes through an artificial waterway which is nearly five miles longer than the proposed artificial waterway across the isthmus of Panama. There are nearly forty-five miles of dredged channels from the head of the lakes to Lake Erie, meaning artificial waterways constructed by the government for the passage of vessels. The money expended, however, has been well worth while. The annual sum saved in transportation charges on shipments from the head of the lakes alone is greater than the total amount expended by the government on the great lakes since the navigation of them begun. No better investment can be made by the general government than the improvement of waterways. They must serve forever as a leveler of rates and the cheapness of transit afforded by them must inevitably inure to the benefit of the whole people.

Elsewhere in this issue is given the chronology of the installation of machinery in the steamer Powell Stackhouse at the Orleans street yard of the Detroit Ship Building Co. Certainly no such expedition as this has ever hitherto been obtained on the great lakes, and it would be interesting to know whether foreign shipyards are capable of equaling it. This particular

yard has special opportunities for dispatch in handling machinery, owing to its magnificent river frontage; and in addition it has the advantage of a thoroughly disciplined personnel. The various heads of departments in the machine shop have been there for twenty years or more. They are rapid and excellent workmen and rose splendidly to the test.

Lake Superior has not for many years been visited by a storm of such violence as that which marked the storm of last week. For several days preceding this great storm the lake had been as smooth as glass, but it is well known to navigators that this body of water is subject to violent disturbances. Only the stoutest crafts were able to weather the gale in safety. The list to date shows that four vessels have been lost with forty members of their crews. The aftermath may reveal something more, as one of the little islands in the path of the storm was entirely submerged.

#### HEAVY ORE SHIPMENTS

Ore shipments have again been delayed by the excessive rains in the Lake Superior country which have flooded the Mesabi mines and prevented the movement of ore to upper lake docks. Notwithstanding this handicap, however, there were moved on the great lakes during August 4,996,930 tons of ore, as against 4,011,584 tons for August of last year. The movement up to Sept. 1 of the present year is 21,035,604 tons, as against 11,419,608 tons up to Sept. 1 of last year. There are still two months left wherein favorable weather may be expected and it is almost certain that 10,000,000 tons will be shipped between Sept. 1 and the close of navigation. This will cause the total ore movement to exceed 31,000,000 tons for the year. The movement is being handled almost exclusively by contract vessels, shippers having really all that they can do to supply their contract tonnage. In fact, vessels are rather badly bunched at upper lake docks, owing to the limited movement from the mines. Following are the shipments by ports during August and for the season up to Sept. 1. For purposes of comparison the corresponding period for last year is also given:

	August.		To September.	
	1904.	1905.	1904.	1905.
Escanaba .....	711,756	706,252	1,698,308	3,227,865
Gladstone .....			480	
Marquette .....	366,172	421,685	818,010	1,882,211
Ashland .....	389,043	501,184	967,969	2,148,351
Superior .....	865,090	1,433,556	2,148,919	5,589,491
Duluth .....	865,090	1,433,556	2,148,919	5,589,491
Two Harbors .....	872,245	1,233,256	2,065,833	5,019,660
	4,011,584	4,996,930	9,615,996	21,035,604
1905 increase .....		985,346		11,419,608

Mr. Wm. Randolph Strickland has resigned from the New York Central railroad and is now associated with J. G. White & Co., 43 Exchange Place, New York, as assistant to the secretary. Mr. Strickland is a graduate of the Massachusetts Institute of Technology and during the Spanish-American war served at the Mare Island navy yard as assistant engineer. Mr. Strickland made the hydraulic calculations for the North Fork power house at Denver, Colo., in 1900. After he had completed this work he joined the staff of the Colorado Fuel & Iron Co. as engineer of location on a standard gauge line over McClure Pass.

#### CONTRACTS FOR MORE FREIGHTERS


During the past ten days the American Ship Building Co. has closed contract for three additional freighters for 1906 delivery, making seventeen freighters this company now has under order for next season. The first of these three orders was placed by Herbert H. Oakes of Detroit, to be a duplicate of the Amasa Stone. She will therefore be 545 ft. over all, 525 ft. keel, 55 ft. beam and 31 ft. deep. The second order was placed by Mr. Wm. M. Mills of Tonawanda, to be a duplicate of the four that were built by the American Ship Building Co. for the Pittsburg Steamship Co. This steamer will therefore be 569 ft. over all, 549 ft. keel, 56 ft. beam and 31 ft. deep. The third order was placed by Mr. Charles O. Jenkins of Cleveland, to be virtually a duplicate of the James P. Walsh. The new steamer will be 500 ft. over all, 480 ft. keel, 52 ft. beam and 30 ft. deep. In addition to these orders for seventeen freighters the American Ship Building Co. is to build a car ferry for the Marquette & Bessemer Dock & Navigation Co.

The Great Lakes Engineering Works at Detroit has under order four 10,000-ton steamers for 1906 delivery, besides a car ferry, and the Craig Ship Building Co., Toledo, has under order an 8,000-ton steamer.

The era of the big ship may be said to have begun with the construction of the Augustus B. Wolvin in 1904. The Wolvin was the first 10,000-ton ship to be built on the great lakes. The Wolvin is 560 ft. over all, 540 ft. keel, 56 ft. beam and 31 ft. deep. The following table will show with what rapidity owners have followed the lead set by Mr. Wolvin. Following is a list of big ships that have been constructed or are now under order for construction since the Wolvin was built. It will be seen that they number forty-three, with carrying capacity on a single trip of 397,500 gross tons of ore, or 7,950,000 tons in an average season of twenty weeks:

NAME	Over all Length Feet	Keel Feet	Beam Feet	Depth Feet	Year Built	Capacity Gross Tons	OWNER
Ball Bros.	500	480	52	30	1905	8,000	G. A. Tomlinson, Duluth
Jas. C. Wallace	552	532	56	31	1905	10,000	Acme S. S. Co., "
S. M. Clement	500	480	52	30	1905	8,000	Mitchell & Co., Cleveland
Philip Minch	500	480	52	30	1905	8,000	H. Steinbrenner, "
Amasa Stone	545	525	55	31	1905	10,000	Pickands Mather, "
L. C. Smith	545	525	55	31	1905	10,000	U. S. Trans. Co., "
Sylvania	524	504	54	30	1905	9,000	G. A. Tomlinson, Duluth
Socapa	524	504	54	30	1905	9,000	G. A. Tomlinson, "
W. A. Rogers	545	525	55	31	1905	10,000	Niagara Trans. Co., "
L. C. Hanna	524	504	54	30	1905	9,000	M. A. Hanna & Co., Cleveland
P. Stackhouse	524	504	54	30	1905	9,000	M. A. Hanna & Co., "
Wm. A. Paine	500	480	52	30	1905	8,000	Hutchinson & Co., "
E. H. Gary	569	549	56	31	1905	10,000	Pittsburg S. S. Co., "
W. E. Corey	569	549	56	31	1905	10,000	Pittsburg S. S. Co., "
G. W. Perkins	569	549	56	31	1905	10,000	Pittsburg S. S. Co., "
H. C. Frick	569	549	56	31	1905	10,000	Pittsburg S. S. Co., "
J. E. Davidson	524	504	54	30	1905	9,000	G. A. Tomlinson, Duluth
Hoover & Mason	524	504	54	30	1905	9,000	G. A. Tomlinson, "
W. G. Mather	531	511	60	31	1905	10,000	Cleveland Cliffs I. Co., Cleveland
Peter White	524	504	54	30	1905	9,000	Cleveland Cliffs I. Co., "
Jas. P. Walsh	500	480	52	30	1905	8,000	C. O. Jenkins, "
Un-named	524	504	54	30	1906	9,000	C. L. Hutchinson, "
"	524	504	54	30	1906	9,000	Wilson Transit Line, "
"	545	525	55	31	1906	10,000	C. L. Hutchinson, "
"	545	525	55	31	1906	10,000	John Mitchell, "
"	545	525	55	31	1906	10,000	John Mitchell, "
"	498	416	50	28	1906	6,500	John Mitchell, "
"	534	514	54	31	1906	9,500	Gilchrist Trans. Co., "
"	534	514	54	31	1906	9,500	Gilchrist Trans. Co., "
"	500	480	52	30	1906	8,000	Hugh McMillan, Detroit
"	524	504	54	30	1906	9,000	E. D. Carter, Erie
"	500	480	52	30	1906	8,000	W. C. Richardson, Cleveland
"	550	530	56	31	1906	10,000	Jones & Laughlin, Pittsburg
"	550	530	56	31	1906	10,000	Jones & Laughlin, "
"	550	530	56	31	1906	10,000	Globe S. S. Co., Duluth
"	550	530	56	31	1906	10,000	W. P. Snyder & Co., Pittsburg
"	505	485	56	31	1906	8,000	L. O. Sullivan, Toledo
"	545	525	55	31	1906	10,000	H. A. Hawgood, Cleveland
"	569	549	56	31	1906	10,000	U. S. Trans. Co., "
"	545	525	55	31	1906	10,000	Hawgood & Co., "
"	545	525	55	31	1906	10,000	Herbert H. Oake, Detroit
"	569	549	56	31	1906	10,000	M. M. Mills, Tonawanda, N. Y.
"	500	480	52	30	1906	8,000	C. O. Jenkins, Cleveland

Total in one trip 897,500  
Total in a season of twenty trips 7,950,000



THE STEAMER POWELL STACKHOUSE.

## Rapid Installation of Machinery.

The installation of machinery into the steamer Powell Stackhouse at the yard of the Detroit Shipbuilding Co. marks a record for despatch which has never hitherto been attained on the great lakes. The Stackhouse was launched at Wyandotte at 11 a. m., Aug. 5. Tow lines were already attached to her and she started for the machine shop at the foot of Orleans street in Detroit immediately, arriving there at 2:30 p. m. Three hours later, or at 5:30 p. m., the boilers were landed in the ship. The daily chronology of progress thereafter is extremely interesting. No work, of course, was done on Sunday.

Monday—Hoisted in first, upper breeching, Ellis & Eaves fan; second, ash elevator legs, air pumps and condenser; driving bearing and intermediate shaft, main engine; set engine and boilers and got the template for main steam pipe Monday afternoon and put boiler house deck on and bolted up.

Tuesday—Hoisted in steel spars, stack, pistons and cylinders; finished hoisting in of the machinery, connected up main steam pipe, main and auxiliary feed pipes, auxiliary steam and exhaust pipes; drilled all the holes for holding down bolts for main engine.

Wednesday—Filled the boilers in the forenoon and had preliminary test. At 3 p. m. the United States inspectors inspected the boilers.

Thursday—Finished riveting up the boiler house, started a fire and raised steam. Finished bolting down the main engine.

Friday—Screwed up the joints around boiler and engine, put on cups, etc.; started main engine at 1 p. m. under steam and worked it for three hours at a good stiff gait until satisfied it was ready for sea. Forty-eight working hours only were consumed in installing the boilers and engines and having machinery running smoothly under steam. As soon as the engine was stopped Friday it was cleaned thoroughly, ready for painting.


The fact that the company succeeded in putting the boilers in on the day of the launch made it possible to work the engine on Friday or a day ahead of the time in which it was planned to work her. The work was all prearranged

and nothing but an unforeseen accident could have prevented the company from doing it in the time planned. Absolutely nothing was left to chance. Everything was in readiness, the machinery being on dock in the relative position that it would occupy on board ship and the workmen moved with clock-like regularity not to miss a single moment. Supt. C. B. Calder, under whose supervision the work was done, says that the performance is to be credited purely to the organization of the personnel. Many of the heads of departments of this company have been continuously there for a quarter of a century or more and are skilled and rapid workmen. Supt. Calder gives especial credit to W. G. Henderson, foreman of the machine shop, who has been in the company's employ for twenty years or more; to John Chambers, steam fitter and plumber; to Robert Gray, sheet metal worker; to Hugo Betzold, boiler maker; to Fred Ritchie, who installed the steering gear and hatch fasteners; to James Hunter, who erected the engine in the boat; to John Fitzgerald, an excellent workman, who hoisted the machinery into the boat, and Mr. William Robinson, who was sent up from Cleveland by the American Shipbuilding Co., to act as foreman on cabin work. Supt. Calder says, however, that there were others quite as deserving of special mention as these, and spoke with pride of the fact that even the humblest employee on the dock was imbued with the spirit of the occasion.


It was exactly 113 working hours from the time the Stackhouse was launched until she was furnished and ready for sea. The machinery was completely installed during the first week, the second week being spent in testing the water bottom tanks, in finishing up the joiner work, in painting and putting in furnishings.

This record of fourteen days is not likely to be excelled by any other yard, as the Wyandotte yard has exceptionally good facilities for despatch. As a matter of record it may be noted that it was forty-one days after the W. A. Paine was launched before she went into commission; the Corey, 49 days; the Sylvania, 60 days; the Socapa, 44 days; the





der diameters being 23½, 38 and 63 in. x 42 in. stroke, supplied with steam from two boilers 14 ft. 6 in. diameter and 12 ft. long, allowed 180 lb. pressure and fitted with Ellis &



Eaves induced draft. The propeller is 14 ft. 3 in. in diameter and 14 ft. 6 in. pitch; revolutions per minute, 85. The weight of the machinery is 325 tons.

## LAUNCH OF BATTLESHIP VERMONT



MISS BELL SMASHES THE BOTTLE.

The battleship Vermont was successfully launched from the yard of the Fore River Ship Building Co., Quincy, Mass., on Thursday last, and was christened by Miss Jenny Bell, daughter of Governor Bell, of Vermont. The affair was unusually brilliant as Gov. Douglass, of Massachusetts, and Gov. Bell, of Vermont,

both attended with their official staffs. Quite a delegation also attended from Washington, including the naval attaches from various countries, and altogether the launch was witnessed by several thousand persons.

After the launch a luncheon was served in the mold loft, President F. T. Bowles, of the ship building company, acting

by Gov. Douglass and Gov. Bell. Admiral Bowles proposed a toast to President Roosevelt which was received with the wildest applause. Assistant Secretary of the Navy Darling also in a speech referred to the president and spoke of his part in the victory of San Juan and of his courage in making the recent trip on the submarine boat Plunger. Then he said:


"But greatest of all, he is an envoy of peace. In uniting Russia, our long time friend, and Japan, our foster child, he has added great glory to himself."

The following description of the designs of the Vermont, one of the largest and most powerful battleships yet laid down for the navy, is taken from the official circular published for the information of bidders.

General dimensions and features of the vessel are as follows: Length of load water line, 450 ft.; breadth, extreme, at load water line, 76 10-12 ft.; displacement on trial, not more than, 16,000 tons; mean draft to bottom of keel at trial displacement, 24½ ft.; cross draft, full load about 26¾ ft.; total bunker capacity, coal, about, 2,000 tons; coal carried on trial, 900 tons; feed water carried on trial, 66 tons; trial speed at sea for four hours, 18 knots.

The hull is to be of steel throughout, and will be fitted with docking and bilge keels.


*Armament.*—Main battery: Four 12-in. breech-loading rifles;



BATTLESHIP VERMONT ON THE STOCKS AT FORE RIVER.

as toastmaster. He paid a great compliment to the sons of Vermont who had been in the navy, and hoped that the future officers of the battleship would be worthy successors of Capt. Clark of Oregon fame. Brief speeches were made

eight 8-in. breech-loading rifles; twelve 7-in. breech-loading rifles. Secondary battery: Twenty 3-in., 14-pounder, rapid-fire guns; twelve 3-pounder and semi-automatic guns; six 1-pounder automatic guns; two 1-pounder semi-automatic



LAUNCH OF THE VERMONT.

guns; two 3-in. field pieces; two machine guns, caliber .30; six automatic guns, caliber .30.

The battery will be mounted as follows: The 12-in. guns in pairs in two electrically controlled, balanced, elliptical turrets on the center line, one forward and one aft, each with an arc of fire of about 270 degrees. The 8-in. guns in pairs in four electrically controlled, balanced, elliptical turrets, two on each beam, at each end of the superstructure. The 7-in. guns in broadside on pedestal mounts on the gun deck behind 7-in. armor, each gun being isolated by splinter bulkheads of nickel steel of from 1½ to 2 in. thick; forward and after guns arranged to fire right ahead and right astern respectively; other 7-in. guns to have the usual broadside train.

The guns of the secondary battery in commanding position, having a large arc of unobstructed fire, and protected wherever practicable.

All the 7-in. guns are so arranged that their muzzles train inside the line of the side armor, thus leaving a clear and unobstructed side when it is desired to go alongside a pier or vessel.

Arrangements will be made whereby the 3-in. guns on the main deck can be quickly and conveniently dismantled, housed, and secured.

**Armor and Similar Protection.**—The hull is protected at the water line by a complete belt of armor 9 ft. 3 in. wide, having a maximum thickness of 11 in. for about 200 ft. amidship. Forward and aft of this the maximum thickness is gradually decreased to 4 in. at the stem and stern. The lower casemate armor extends to the limits of the magazine spaces and reaches from the top of the water-line belt to the lower edge of the 7-in. gun ports on the main deck, and is 6 in. in thickness, the athwartship bulkheads at the ends of this casemate also being 6 in. thick.

The casemate armor around the 7-in. guns on the gun deck

is 7 in. thick, and the splinter bulkheads are from 1½ to 2 in. thick. The protection of 3 in. guns is nickel steel 2 in. thick. The upper casemate athwartship armor extending from the shell plating to the 12-in. barbettes is to be 7 in. thick throughout.

The 12-in. barbettes extend from the protective deck to about 4 ft. above the main deck, and consist of 10 in. of armor in front and 7½ in. in the rear above the gun deck. Between the gun deck and protective deck there will be a uniform thickness of 6 in. The barbettes will not have any special framing, the connection of the armor to the decks being sufficient.

The 12-in. turrets will have a front plate 12 in. thick, rear plates 8 in. thick, and top plates 2½ in. thick.

The 8-in. barbettes will be 6 in. thick in front and 4 in. thick in rear, with the upper tube 3¾ in. thick and the lower tube 3 in. thick.

The 8-in. turret front plate will be 6½ in. thick, the rear plate 6 in. thick, and the top plates 2 in. thick.

The conning tower and shield will each be 9 in., and the signal tower 6 in. thick. An armor tube 36 in. in diameter will extend from the base of the conning tower to the protective deck, and will be 6 in. thick throughout.

Teak backing of a minimum thickness of 3 in. will be fitted behind all side, athwartship, and 12-in. armor; 2 in. of backing to be fitted behind the 8-in. turret armor; other armor will be fitted without backing.

**Protective Deck.**—There is a complete protective deck extending from stem to stern, the deck being flat amidships, but sloped at the sides throughout, and sloped at each end. It will be built up of 20-lb. plating throughout, with nickel steel of 40 lbs. on the flat and of 100 lbs. on the slopes.

The following nickel steel protection is also to be fitted:

Hatch covers and gratings in the protective deck; splinter bulkheads on gun deck; sponsons and wing plates for two forward 3-in. guns on gun deck; bullet shields between wing plates for 3-in. guns and 7-in. guns; side protection and wing plates for 3-in. guns on main deck; turret shelf plates; conning tower base plates; 7-in. gun port sill plates; 80-lb. protection on ammunition hoist trunks not otherwise protected by armor, and 80 lbs. protection on coaling trunks on slope of protective deck to the height of berth deck amidships.

Cofferdams about 30 in. thick and extending from protective deck level will be worked from end to end of the vessel, these cofferdams being extended above the berth deck, forward and abaft the transverse armor, to a height of about 36 inches.

The cofferdams will be packed with cellulose or other approved water excluding mineral.

**Ammunition.**—The magazines and shell rooms are so arranged that about one-half the total supply of ammunition will be carried at each end of the ship. Magazine bulkheads adjacent to heated compartments, such as firerooms, engine rooms, and dynamo rooms, are arranged with air spaces.

The ammunition for 7-in. and smaller guns will be conveyed by hoists directly from the ammunition rooms or ammunition passages to the deck on which it is required, or as near that as possible. These hoists will be driven at constant speed by an electric motor and will be arranged to deliver seven pieces per hoist per minute.

The number of hoists will be as follows: Twelve for 7-in., fourteen for 3-in., 3-pounder and 1-pounder combined, and sufficient whip hoists to the tops. To supply the 7-in. hoists, four horizontal ammunition conveyers, operated by electric motors, will be fitted in ammunition passages for the transfer of ammunition from the handling rooms to the base of the hoists.

The turret guns have regular turret ammunition hoists, op-

CONTINUED ON PAGE 32.



# COMPARISON OF TURBINES AND RECIPROCATING ENGINES IN STEAMERS\*

By William Gray.

In January, 1903, the Midland Railway Co. decided to build four new screw steamers for their Irish and Isle of Man services, in view of the approaching completion of their new harbor at Heysham, in Morecambe bay, Lancashire.

After careful consideration of the data available, the Midland Railway Co. decided to fit two of the vessels of their new fleet with reciprocating engines and two with Parsons marine turbines. Three of the vessels, the Antrim, Donegal, and Londonderry, were intended for the Belfast passenger and cargo trade, and the Manxman for the Isle of Man summer passenger traffic, although she was also fitted with portable cabins for taking up the Belfast trade in winter. The principal dimensions of the three former vessels are as follows: Length on the water line, 330 ft.; moulded breadth, 42 ft.; moulded depth, 25 ft. 6 in. The Manxman is similar

Donegal and in the Londonderry and Manxman they are driven by steam engines.

The engines of the Antrim and Donegal consist of two sets of the four-cylinder, triple-expansion type, each driving a three-bladed propeller. The cylinders are 23 in., 36 in., and two of 42 in., by 30 in. stroke.

The turbines in the Manxman are the larger, as they were designed for 25 percent more power than the Londonderry. The Manxman is also fitted with Parsons' vacuum augments. In each vessel there are three turbines, one high pressure and two low pressure. With the latter are incorporated the reversing turbines that work *in vacuo* when not in use. Each of the three turbines drives a separate shaft, and a three-bladed propeller. The low-pressure turbines are on the outer shafts, and the high-pressure turbines on the center shaft.

The propellers of the Antrim and Donegal are three-bladed. The Antrim's is a little smaller in diameter and coarser in pitch. The propellers of the Manxman are as

TABLE II.

Dates	No. of Passages	T.S.S. "Antrim." (Reciprocating Engines.)			T.S.S. "Donegal." (Reciprocating Engines.)			"Londonderry." (Turbines.)			"Manxman." (Turbines.)		
		Tons of Coal Consumed	Hours under Steam	Hours Full Speed	Tons of Coal Consumed	Hours under Steam	Hours Full Speed	Tons of Coal Consumed	Hours under Steam	Hours Full Speed	Tons of Coal Consumed	Hours under Steam	Hours Full Speed
1904													
Sept. 1-10	9	282.0	67.3	55.1	.....	.....	.....	284.8	65.3	54.9	.....	.....	.....
Sept. 23-28	5	159.5	36.3	28.1	.....	.....	.....	161.0	34.3	30.5	.....	.....	.....
Sept. 29-Oct. 17	16	.....	.....	.....	498.4	116.5	103.3	527.4	111.0	97.5	.....	.....	.....
Oct. 18-Nov. 1	13	447.5	89.0	71.0	.....	.....	.....	429.3	92.2	75.0	.....	.....	.....
Dec. 1-15	13	.....	.....	.....	465.0	91.3	78.5	.....	.....	.....	507.7	84.1	74.1
Dec. 16-21	5	204.7	34.0	32.1	.....	.....	.....	.....	.....	.....	187.0	39.1	23.5
1905													
Dec. 29-Jan. 10	11	416.4	73.1	67.0	.....	.....	.....	.....	.....	.....	420.5	73.3	62.5
Jan. 25-Feb. 8	13	.....	.....	.....	520.0	89.8	76.0	.....	.....	.....	532.0	92.1	59.6
Feb. 9-23	13	489.7	89.0	72.1	.....	.....	.....	.....	.....	.....	512.0	83.8	73.5
Mar. 11-25	13	.....	.....	.....	522.0	86.8	77.2	.....	.....	.....	539.0	86.2	70.7
Mar. 31-Apr. 10	9	345.6	58.0	52.5	.....	.....	.....	350.5	62.5	52.2	.....	.....	.....
Apr. 26-May 10	13	.....	.....	.....	551.0	89.2	78.4	512.0	84.0	72.4	.....	.....	.....
May 12-25	12	472.8	74.5	68.2	.....	.....	.....	470.3	67.4	67.5	.....	.....	.....
June 10-24	13	.....	.....	.....	459.1	87.1	78.5	510.5	82.9	72.9	.....	.....	.....
	158	2828.2	521.2	446.1	3015.5	590.7	491.9	3245.8	609.6	522.9	2689.2	458.6	363.9

## SUMMARY.

	"Antrim"	"Donegal"	"Londonderry"	"Manxman"
Number of passages	77	81	90	68
Coal per passage (tons)	36.7	37.2	36.1	39.6
Hours at full speed per passage	5.78	5.07	5.81	5.35
Hours at full speed, percentage of	85.5	87.7	85.7	79.5

in form, and of the same length and depth, but the moulded breadth is 43 ft.

The boiler installation in all the vessels consists of two double-ended and one single-ended boiler, the principal dimensions of which are given in parallel columns:

	Double-ended.	Single-ended.
Number	2	1
Length	22 ft.	11 ft. 6 in.
Diameter	15 ft. 7 in.	.....
Number of furnaces (total)	12	3
Heating surface in each ship	12,500 sq. ft.	.....
Grate area	400 sq. ft.	.....

The working pressure in the Antrim, Donegal and Manxman is 200 lbs. per square inch, and in the Londonderry 150 lbs. per square inch. Forced draught on the closed stokehold system is fitted in all the vessels. The fans for this purpose are driven by electric motors in the Antrim and

\*Abstract of a paper read at the summer meeting of the British Institution of Naval Architects, July 20, 1905.

follows: Center, 6 ft. 2 in. diameter, 5 ft. 7 in. pitch; side, 5 ft. 7 in. diameter, 5 ft. pitch. The Londonderry's are all the same, 5 ft. diameter, 4 ft. 6 in. pitch.

The conditions of the contract were that each vessel was to maintain a speed of twenty knots per hour for six continuous hours with the double-ended boilers only under steam and 300 tons deadweight on board.

The results of the official trials were as follows:

	Antrim.	Londonderry.	Manxman.
Speed in knots	20.6	21.6	22.65

With all the boilers in use the results were:

	Antrim.	Londonderry.	Manxman.
Speed in knots	21.86	22.36	23.12

The amount of water consumed was measured during the progressive trials by counting the strokes of the feed pumps, and the comparative results are given in Table I:



TABLE I.—GALLONS OF WATER CONSUMED PER HOUR.

Speed in Knots.	Antrim and Donegal.	Londonderry.	Manxman.
14	4,500	4,500	4,500
17	6,700	6,100	5,800
20	9,700	8,900	8,300
22	....	13,600	12,500
23	....	....	17,300

These figures throw some light on the relative economy not only of the two systems of propulsion at various speeds, but on the different arrangements in the two turbine steamers themselves. They show that from 14 knots to 20 knots the turbine is more economical. The maximum difference occurs between 19 knots and 20 knots, which is the working speed of the vessels on service. In the case of the Londonderry the decrease in water consumption amounted to 8 percent, and in the case of the Manxman to 14 percent, as compared with the Antrim and Donegal.

Through the courtesy of the officials of the Midland Railway Co., the log books of the four steamers have been placed at the writer's disposal, and it is therefore possible to make some comparisons that may be of interest to those connected with ships. As the question under consideration is reciprocating engines versus turbines, those occasions when the Antrim and Donegal were running together have been omitted. The Londonderry and the Manxman have never been running together on this service.

Table II gives the following particulars for the various steamers, viz: (1) The number of single trips made from Belfast to Heysham, and vice versa. (2) The number of tons of coal consumed while under steam. (3) The total number of hours under steam. (4) The total number of hours at full speed.

The amount of coal consumed in port varies according to circumstances, and as it does not materially affect the matter under discussion, it has been excluded from these tables. It amounts approximately to about eight tons per steamer per single trip. The column "hours under steam" is the time from quay to quay, and includes the time occupied in maneuvering the vessel in harbor.

The table treats the matter from a purely commercial standpoint, that is to say, it ignores the differences of speed and coal consumption due to the relative weights of turbines and reciprocating engines, and only deals with the items that exclusively interest shipowner. It gives the amount of coal that each vessel consumed on a given number of trips. In all four steamers the three boilers have been in use, and all have been working with the same moderate air pressure in the stokeholds. The results, therefore, represent the amount of coal consumed under easy steaming in all circumstances. To show the results obtained from each pair of steamers running simultaneously but in opposite directions, the previous table has been split up, as shown in Table III.

The speeds obtained on the trial trips have been already dealt with, but, valuable as these results are, the conditions in which trial trips are conducted are more or less artificial, and shipowners are justified in not taking them as final guides on the subject.

The logs have been very carefully examined, and, neglecting those runs where full speed was not maintained for the whole time that the vessels were in the open sea, the results are as follows:

TABLE III.—SHOWING RESULTS OBTAINED BY STEAMERS RUNNING SIMULTANEOUSLY, BUT IN OPPOSITE DIRECTIONS.

	Reciprocating Engine.	Turbines.
	"Antrim."	"Londonderry."
Number of trips.....	48	48
Average coal per trip (tons)...	35.6	35.3
Average speed in knots.....	19.7	19.5

	Reciprocating Engine.	Turbines.
	"Donegal."	"Londonderry."
Number of trips.....	42	42
Average coal per trip (tons)...	36.0	36.9
Average speed in knots.....	19.2	19.8
	"Antrim."	"Manxman."
Number of trips.....	20	20
Average coal per trip (tons)...	38.6	38.6
Average speed in knots.....	19.05	20.3
	"Donegal."	"Manxman."
Number of trips.....	39	39
Average coal per trip (tons)...	38.7	40.2
Average speed in knots.....	19.3	20.3

These results point to a marked decrease in the coal consumption of the Manxman, as compared with the Antrim and Donegal. The Manxman did 20.3 knots for the same coal consumption that the Antrim had at 19.5 knots. A similar comparison of the Manxman with the Donegal gives nearly the same results. The performances of the Londonderry are nearly as efficient as those of the Antrim, but they are better than those of the Donegal. They also indicate that the Manxman with higher steam pressure, a smaller number of revolutions, and larger propellers, has done better than the Londonderry.

A further economy in the turbine steamers is effected in the amount of oil used for lubrication. The logs show that this amounts in both steamers to five gallons per single trip. This again permits of a further economy in the reduction of the engine room staff from four greasers to two. Speaking generally, therefore, the performances of the turbine steamers, especially the Manxman, have been greatly superior to those of the steamers fitted with reciprocating engines.

It is not possible to make a quantitative analysis of the cost of upkeep, but so far the turbines have cost practically nothing, and they require very little attention compared with what is necessary in the very best-running engines of the reciprocating type.

There can be no doubt that one great benefit derived from the use of turbines is the elimination of the vibration inseparable from the use of reciprocating engines in channel steamers. The engines in the Antrim and Donegal were most carefully balanced, and the vibration at the service speed is almost imperceptible. The almost unanimous testimony, however, of those who have traveled in the vessel is, that the turbine steamers are steadier.

The only real inferiority in the Londonderry and Manxman is the difficulty of maneuvering from rest in narrow waters. In this respect they compare unfavorably with the Antrim and Donegal. Experiments were made at the trial trips that showed the turbine steamers going full speed could be brought to rest in about one and a half minutes. This is a good result, but actual experience has shown the relative inadequacy of the backing power starting from rest. There is no good reason why sufficient backing power cannot be obtained with small screws if the reversing turbines are made powerful enough.

Having dealt with the question of speed and coal consumption there remain three other points in connection with the design, viz.: Space occupied, weight, and cost. The turbines occupied so much more floor space than the reciprocating engines that the electric plant had to be put in the tunnel. Space may be saved on the upper decks, but this is not an unmixed advantage, as it was effected by reducing the light and air space to the turbine room. The effect of decreasing the light and air space to the turbine room involved an increase in the net tonnage of nearly fifty tons.

In the case of vessels trading between ports where tonnage dues are heavy, this is a matter of great importance, and may

balance the economical gains in oil and fuel. In such cases the gain in space cannot be used with advantage.

The saving of weight in the turbine steamers is considerable. In the hull the weights involved, viz., engine seat, tunnel stools, boss frames, and plating, etc., are reduced by 30 tons. Against this the buoyancy of the bosses is 29 tons less in the turbine than in the other steamers, so that from the draught point of view the saving in hull is neutralized by the loss of displacement. The weight of engines, shafting, and propellers in the Antrim and Donegal was 280 tons. The weight of the corresponding items in the Manxman was 195 tons, so that the total weight to be propelled is about 115 tons less, a difference of nearly 6 percent on the light weight of the steamer.

The difference of the initial cost of the turbines as compared with engines is not great. Comparing the Antrim and the Londonderry it amounted to one and a half percent of the total cost of hull and machinery. In other words, for a speed of 19.5 knots the Antrim requires 38.6 tons of coal and the Manxman 35.0 tons, a saving of 9.3 percent. The Donegal for a speed of 19.3 knots requires 38.7 tons and the Manxman 35.4 tons, a saving of 8.5 percent.

### Launch of Battleship Vermont

CONTINUED FROM PAGE 29.

erated by electric power, these hoists leading directly from the handling rooms or the ammunition passages to the turrets. For transporting 12-in., 8-in. and 7-in. ammunition, trolleys and tracks will be fitted in handling rooms, passages and shell rooms.

*Propelling Machinery.*—The engines will be of the vertical, twin screw, four-cylinder, triple expansion type, of a combined L. H. P. of 16,500. The steam pressure will be 250 lb. The stroke will be 4 ft. The ratio of high pressure to low pressure cylinder will be at least 1 to 7, and the diameters will be sufficient for the required I. H. P. at about 120 revolutions per minute. Each engine will be located in a separate watertight compartment. There will be twelve boilers of the Babcock & Wilcox type, placed in six watertight compartments. They will have at least 1,100 sq. ft. of grate and 46,750 sq. ft. of heating surface, and must be able to furnish steam for the main engines and all necessary auxiliary machinery and other steam machinery throughout the ship with an average air pressure in the ash pits of not more than 1 in. of water. There will be three funnels, each 100 ft. high above the base line.

The following auxiliary steam machinery of approved make and design, in addition to that pertaining to the main engines and dependencies, is to be supplied: steering engine; windlass engine; ash hoist engine for each fire room; forced draft blowers; ice plant with a cooling effect of three tons of ice per twenty-four hours; evaporating plant to consist of not less than four units, having a total capacity of 16,500 gallons of fresh water per day; a distilling apparatus capable of condensing at least 10,000 gallons of water per day. The vessel to be heated by steam throughout.

The weight of all machinery and tools, stores, and spare parts will be about 1,500 tons.

The vessel will be lighted throughout by electricity. The electric plant will consist of eight 100-kilowatt steam driven generating sets, all to be of 125 volts pressure at the terminals, disposed in two separate and independent dynamo rooms.

There will be fitted all the usual means of interior communication, such as telephones, voice pipes, call bells, buzzers, gongs and annunciators, engine and steering telegraphs, revolution and rudder indicators, heeling indicators, automatic fire alarm, warning signals, alarm signals, etc. The total

weight of equipment outfit, complete, will not exceed 355.28 tons.

With the exception of the auxiliaries above mentioned to be operated by steam, all power on board of the vessel will be electric, as, for instance, boat cranes, deck winches, turret turning motors, ventilation blower motors, etc.

All main compartments of the ship below the gun deck, except the coal bunkers, are to be provided with forced ventilation, there being no less than thirty-three blowers, with a combined capacity of not less than 104,000 cu. ft. per minute. Special attention has been given to spaces subject to habitually high temperature, such as engine rooms, fire rooms, and dynamo rooms. The ventilation system will be designed to cut the minimum number of watertight bulkheads. All blowers, except forced draft blowers, are to be electrically operated.

The coal bunkers are to be arranged with satisfactory reference to the rapid and efficient supply of coal to the fire rooms and have a maximum capacity of about 2,200 tons. There are to be provided for coaling not less than six winches, twelve booms, and all necessary fixed chutes, scuttles, hatches and other openings. There will be two bill boards and four hawse pipes, each hawse pipe to be so designed that stockless anchors may be stowed in them. There will be four heavy anchors, two of the navy type and two of the stockless type.

The following boats will be carried, adequate provision being made for their convenient stowage and handling, two electrically operated boat cranes, eight pairs of boat davits, adjustable boat chocks, and all necessary fittings being provided for this purpose: One 50-ft. steam cutter, two 36-ft. steam cutters, one 36-ft. steam launch, three 33-ft. launches, five 30-ft. cutters, two 30-ft. whaleboats, one 30-ft. gig whaleboat, one 30-ft. barge, two 20-ft. dingies, one 16-ft. dingey, one 14-ft. dingey, and two life rafts.

The vessel is designed as a flagship, and the arrangement of quarters providing ample accommodations for the following complements: A flag officer, a chief of staff, nineteen wardroom officers, ten junior officers, ten warrant officers, and not less than 761 men, including 60 marines.

There is a lower bridge both forward and aft, and a flying bridge forward, according to the latest practice. On the flying bridge is fitted a screen of bronze for the protection of the men at the wheel, and there is also a bronze chart house forward.

There are steel masts forward and aft, the foremast having an upper and lower top, the main mast a lower top only. Masts are arranged for wireless telegraphy. There is one signal yard on each mast, also a searchlight platform forward and aft, with a crow's nest on the foremast.

A summary of the weights to be carried on trial is as follows:

	Tons.
Guns, mounts, magazine equipments, etc.....	944.04
Ammunition, two-thirds full supply.....	393.97
Steam engineering complete, with water in boilers, condensers, piping, etc., and stores, etc., not to exceed .....	1500.
Reserve fresh water for steaming purposes.....	60.
Coal, normal supply .....	900.
Boats and outfits .....	51.27
Masts and spars .....	30.08
Equipment complete, including anchors, chains, electric plant, etc., and two-thirds equipment stores.....	355.28
Miscellaneous stores and water, two-thirds full supply .....	81.32
Provisions, clothing and small stores, two-thirds full supply .....	146.84
Officers, crew and effects.....	103.32
Total protection, including armor, armor backing, armor bolts, cellulose, and splinter bulkheads.....	3992.

## DISASTROUS STORM ON LAKE SUPERIOR

The storm which broke out in the vicinity of the Apostle Islands, Lake Superior, during the latter part of last week was one of the most disastrous in lake history. It is not unusual for a storm to affect the modern freighter with its great strength and great displacement but this greatly crippled a number and made several seek shelter. It completely wrecked the steel steamer *Sevona*, owned by James McBrier, of Erie. The *Sevona* was bound down from Allouez to Erie with ore. She ran into the teeth of a northwester on Friday last. Capt. D. S. McDonald tried to make headway against the heavy sea but turned and ran for shelter when the storm became too violent. The location in which he found himself is one of the most dangerous in Lake Superior. Sand Island is in the center of a cluster of dangerous reefs. One and a half miles east of the light on the island is the Sand Island reef. The storm was so severe that the lookout did not see the Raspberry Island light. When the Sand Island lighthouse was sighted it was too late. Capt. McDonald tried to put about but the storm swept him irresistibly on the reefs. Within half an hour after striking, the fury of the waters had hammered the *Sevona* in half. The vessel broke in two just aft of the fourth hatch. Life boats were launched and the crew under command of Engineer Phillippi endeavored to take the women passengers ashore. They succeeded in doing so after a night of terror. Capt. McDonald, the two mates and four sailors remained on the broken forward half of the vessel in the hope of rescue but they were drowned. The *Sevona* was built by F. W. Wheeler at West Bay City in 1890, for Hollister Bros., of Buffalo, and when she came out was known as the *Emily P. Weed*. She was lengthened 72 ft. last year at the Buffalo yard of the American Ship Building Co., and was insured for \$160,000.

The steamer *Iosco*, owned by W. A. Hawgood & Co., of Cleveland, and its tow, the *Olive Jeanette*, also foundered in the gale. The first known of this catastrophe was conveyed by wreckage through which the tug D. L. Hebard passed near Huron Island. The lighthouse keeper on Huron Island saw a big schooner founder four miles north of the light but was unable to determine her name. He saw no steamer at the time, but the Hawgoods gave up hope on Wednesday that the *Iosco* could possibly be afloat. The *Iosco* carried a crew of nineteen men and the *Olive Jeanette* of seven.

The *Iosco* was a wooden steamer and was built by F. W. Wheeler & Co., West Bay City, in 1891. She was 291 ft. long, 41 ft. beam and 20 ft. deep. The *Olive Jeanette* was also built at Bay City by Wheeler & Co., and came out in 1890. She was 242 ft. long and 39 ft. beam. The *Iosco* was insured for \$65,000 in companies represented by Smith, Davis & Co., of Buffalo. The *Jeanette* was insured for \$40,000. The *Iosco* and her tow left Duluth at noon on Thursday last with ore shipped by M. A. Hanna & Co., of Cleveland.

The schooner *Pretoria* also foundered in the gale. She was owned by James Davidson, of Bay City, and is the first vessel that Capt. Davidson has lost through storms. She was built in 1900 and was 338 ft. long, 44 ft. beam and 25 ft. deep. She was valued at about \$75,000, but no insurance was carried on her. Four lives were lost on her.

The storm caused the great steel steamer D. M. Clemson to put back into Two Harbors with a list of 4 ft. When the storm broke the steamer was boarded by heavy seas and two hatches were broken open. It was then determined to seek shelter.

Vessel masters agree that the storm was the worst that they had experienced in twenty-five years. Frank Smith, the second engineer of the steamer *R. L. Ireland*, was washed

overboard about sixty miles east of Keweenaw Point and was lost. John Linquist, a seaman, was washed overboard from the steamer *Samuel Mather* off Knife Island and was lost.

The new steamer *Powell Stackhouse*, just out of the shipyard, went through the storm all right, but Capt. Millen reported that the patent hatches would spring and allow water to enter the hold. She was drawing 20 ft. 5 in. when she reached Sault Ste. Marie and had to lighten her cargo in the rivers to cross the Lime Kilns.

It is impossible to determine at this moment just how many lives were lost in this great storm, but the number is between thirty and forty.

## CHICAGO GRAIN REPORT

Chicago, Sept. 5.—Total shipments of the past week were upward of 4,000,000 bu. with flour movement of 166,700 bbls., but reflecting the continued steady call of vessel room rates ruled unchanged at basis 1½ cents and 1¼ cents Buffalo corn, according to quantity and location, and at basis 4 cents through to Montreal. Deliveries on September contracts are well up to expectations and likely to occasion some fair chartering activity, but it will require the movement of Northwest grain in order to vest this quarter with any substantially improved tone.

Shipments of the week are distributed as follows: Via all rail lines of flour, 70,770 bbls.; wheat, 128,735 bu.; corn, 180,523 bu., and oats, 857,519 bu. To Buffalo and other American points, of flour, 90,949 bbls.; wheat, 97,000 bu.; corn, 2,178,681 bu., and oats, 118,000 bu. And via lake to Canada, of flour, 5,058 bbls.; wheat, 52,000 bu.; corn, 417,300 bu. and oats, 194,000 bu.

## Lake and Rail shipments:

	This week.	Last week.	Same week last year.
Wheat .....	291,156	459,276	323,514
Corn .....	2,776,515	2,580,757	2,172,806
Oats .....	1,180,390	1,545,140	912,050
Rye .....	66,937	3,303	14,221
Barley .....	34,291	126,127	29,907
	4,349,289	4,714,663	3,452,489
Flour .....	166,777 (bbls.)	197,329	100,032
		Since Jan. 1, 1905.	Same time last year.
Wheat .....		9,265,860	9,720,110
Corn .....		65,017,156	46,199,440
Oats .....		36,465,710	31,750,960
Rye .....		697,893	858,488
Barley .....		2,652,727	2,864,236
		114,099,346	91,393,214
Flour .....		4,032,873 (bbls.)	5,164,674

## Stocks in Public and Private Elevators:

	This week.	Last week.	Same week last year.
Wheat .....	5,493,000	5,586,000	3,691,000
Corn .....	3,444,000	3,548,000	3,773,000
Oats .....	8,095,000	7,350,000	7,304,000
Rye .....	142,000	156,000	642,000
Barley .....	53,714	52,714	96,000
	17,227,714	16,692,714	15,506,000

The steamer *Columbia*, of the Detroit River Ferry Co., which is one of the largest and best excursion boats on the lakes, will come to Cleveland this month. She will be here Sept. 13 and 19 and will give two lake rides each day. Her passenger capacity is 3,566, and nearly 1,000 persons can dance at one time on the boat. Mr. Walter E. Campbell, of Detroit, is manager of the big boat.

## ACCEPTANCE TRIAL OF THE PENNSYLVANIA

The recent performance of the Cramp-built armored cruiser Pennsylvania during her final acceptance trial is worthy of careful study. The Pennsylvania is one of six cruisers, built or building at the Union Iron Works, Newport News Co. and Cramps, two at each yard. They are all sisters, identical in type and specifications. The final acceptance trial was conducted with the navy department's crew of engineers and firemen, and the Pennsylvania is the only vessel of the American navy which has accomplished a trial of four hours with forced draft with the regular crew wherein the contract speed has been exceeded. Prior to the Colorado and Pennsylvania it was the custom of the navy department to conduct the final acceptance trials so that the boilers were run under maximum natural draft conditions for a set period. On these two cruisers a full forced draft four hours' trial was added and the success achieved was so marked that in the future such forced draft trials are apt to be required for all vessels. Such a policy would do much towards inspiring the entire service with the capabilities of the fleet. It also tests the drill and efficiency of the engineering force and refutes the old idea that naval vessels could never attain the speed that the contractors could under more advantageous conditions. The trial was conducted by the Board of Inspection and Survey, Capt. James H. Dayton, president; Capt. H. C. Leutz, Capt. Joseph J. Woodward, Com'dr Isaac S. Reeves and Com'dr Templin M. Potts, recorder.

The contract for the six vessels of the Pennsylvania class called for the development of a speed of 22 knots an hour with an indicated horse power of 23,000. Under the former policy of the Bureau of Construction and Engineering certain latitude was allowed the builders in modification of design in order to enlist their heartiest cooperation. In the case of the Pennsylvania the results obtained are directly attributable to certain modifications in the boiler room and engine room which resulted greatly in improving the speed and efficiency of the ship. The changes allowed by the government were the installation of a battery of thirty-two modified Niclausse boilers, the modifications being in the direction of larger tubes and drum and general simplification of details. The main steam pipe was increased from 13 in. to 15 in. diameter, because it was considered that for a piston speed of nearly 1,100 ft. a minute a pipe of the larger diameter would be a necessity. The boilers were built for 300 lbs. and the arrangement of the cylinders was modified so as to give a more direct flow to the steam; the order in the department design being low pressure, high pressure, intermediate and low pressure, which is changed in the Cramp design to high pressure, intermediate, low pressure and low pressure. Another radical change was that instead of the low pressure cylinders being assisted by introducing live steam from the boilers, this connection was dispensed with and instead the exhaust from the auxiliary was fed direct to the low pressure cylinders. It will thus be seen that the changes were thoroughly in touch with the latest marine practice involving high boiler pressure, ample steam pipe connections to convey an abundance of steam to the cylinders and a literal adherence to the principles of triple compound expansion by using live steam only in the high-pressure cylinders and allowing it to develop its full expansive efficiency from throttle to condenser. A comparison of the trials of a sistership built at another yard becomes interesting. On her contractors' trial trip the average speed of this ship was 22.12 knots, with 25,750 H. P. on a coal consumption of 3.2 lbs. per indicated horse power per hour. The Pennsylvania on her contractors' trial trip last year averaged 22.43 knots, with an average indication of 27,750 H. P. on an average coal consumption of 2.2 per

horse power per hour, the temperature in the uptake in the first case being over 1,000 degrees and in the case of the Pennsylvania 650 degrees.

The Pennsylvania left Newport harbor about noon on Tuesday, July 25. At 2:40 p. m. her official forced draft trial lasting four hours was commenced under practically the same conditions as she maintained in the contractor's trial. The engine performance was highly creditable to the engine force of the ship, as the maximum indicated horse power of 30,150 was reached, the average for four hours being 29,843; average speed 22.08 knots.

Immediately after the completion of the four-hour forced draft test an eight-hour natural draft trial was commenced with all boilers in use. This lasted from 7 p. m. Tuesday until 3 a. m. Wednesday. The average results obtained were 10.8 speed and the average horse power 17,040. After the completion of the steam trials the batteries as installed were tested and showed that the ship was perfectly strong in every respect and fit for immediate active service.

The speed of 22.08 knots under forced draft was ascertained by plotting the number of revolutions 125.66 for four hours on the speed curve constructed from the results of standardizing trials made at Provincetown a few weeks before. The draught of water on the trial course does not exceed 25 fathoms, which certainly is not enough for a vessel of the size and draught of the Pennsylvania. Had she been tried on the English deep water courses she would have possibly increased her speed one to one and a half knots. As it was the patent log showed an average of 22.8 knots. The Pennsylvania has not been docked since November which makes the performance all the more remarkable. This trial also was a triumph for the Niclausse boilers. At all times during the four hours' run there was an abundance of steam and the safety valves were blowing off. The coal used was run of the mine Cumberland instead of Pocahontas as used by the contractors in the official trials. By reason of the magnificent condition of the vessel in all departments, too much praise cannot be given to the very efficient organization under command of Capt. T. C. McLean.

Data in detail of the forced draft and of the natural draft trials is herewith given.

	Starboard.	Port.
Numbers of hours forced draft..	4.	
Mean revolutions of engines....	124.95	126.37
Mean revolution of both engines .....	125.66	
Steam pressure in boilers.....	283.75	
Steam pressure in H. P. cylinder	256.	
Steam Pressure in 1st receiver absolute .....	122.75	125.
Steam pressure in 2nd receiver absolute .....	36.25	40.
Steam cut-off in H. P. cylinder..	.80	.80
Steam cut-off in L. P. cylinder..	.76	.77
Steam cut-off in L. P. cylinder..	.79	.78
Vacuum .....	24.375	24.
Temperatures, fireroom .....	102.5	102.5
" injection .....	73.	73.
" discharge .....	132.2	129.
" feed water .....	180.5	179.
Revolutions of air pumps per minute .....	11.	20.
Revolutions of circulating pumps per minute .....	115.	170.
Grate surface in use.....	1,600.	
I. H. P. main engines.....	14,212.75	14,480.85
I. H. P. both engines.....	28,693.6	
I. H. P. auxiliaries.....	1,149.85	
Aggregate I. H. P.....	29,843.45	
Pounds of coal per hour.....		52,332.5
" " per sq. ft. of grate in use.....		32.707
" " per I. H. P. main engines.....		1.82
" " per I. H. P. main engs. & auxs...		1.75
Mean draft at beginning of trial F. 22' 10 1/2" A. 25' 7"		



## Displacement.

Mean speed by patent log in knots per hour.....	22.8
Mean speed by speed curve in knots per hour.....	22.08
Slip of screw, percent.....	19.2
Average air pressure, in inches of water.	

## FINAL ACCEPTANCE TRIAL OF PENNSYLVANIA.

	Sta board.	Port.
Number of hours natural draft	8.	
Mean revolutions of engines....	108.18	108.66
"    both engines.	108.42	
Steam pressure in boilers.....	232.	
"    H. P. cylinder.....	200.	
"    1st receiver		
absolute ..	79.7	75.
"    2nd receiver		
absolute ..	22.8	23.8
Steam cut-off in H. P. cylinder..	.80	.80
"    I. P. cylinder...	.76	.77
"    L. P. cylinder.	.79	.78
Vacuum .....	25.375	25.25
Temperatures, fireroom .....	115.8	115.8
"    injection .....	73.	73.
"    discharge .....	121.5	122.7
"    feed water .....	170.6	170.6
Revolutions of air pumps per		
minute .....	12.8	17.3
"    circulat'g pumps		
per minute... 123.		148.2
Grate surface in use.....	1,600.	148.2
I. H. P. main engines.....	8,271.55	8,129.7
I. H. P. both engines.....	16,401.25	
I. H. P. auxiliaries.....	640.7	
Aggregate I. H. P.....	17,041.95	
Pounds of coal per hour.....	48,523.7	
"    per sq. ft. of grate in use.....	30.32	
"    per I. H. P. main engines.....	2.95	
"    per I. H. P. main engs. & aux....	2.84	
Mean draft at beginning of trial.		

## Displacement.

Mean speed by patent log in knots per hour.....	20.66
Mean speed by speed curve in knots per hour.....	19.8
Slip of screw, percent.....	.16
Average air pressure.	

## BONAPARTE ARRAIGNS NAVAL OFFICERS

Secretary Bonaparte in his action upon the findings in the court of inquiry in the case of the Bennington explosion severely arraigns some officers of the vessel for failure to look after the safety valves; orders Com'dr Lucien Young before a court-martial to clear himself of the "charge of neglect of official duty"; directs the court-martial of Ensign Wade on the charge of "neglect of duty," and disapproves the court of inquiry's finding that the Bennington was "in an excellent state of discipline and in good and efficient condition."

Ensign Wade was in charge of the machinery. The action as to Com'dr Young was taken in view of the fact that the court of inquiry in its findings and opinion did not pass expressly upon his conduct and the question of his responsibility for the explosion. Referring to the findings of the court that the ship was in an excellent state of discipline and in a good and efficient condition, Secretary Bonaparte says:

"The department does not consider this particular finding sustained by the evidence; the proof tends strongly to show that the enlisted force of the engineering division had been permitted to fall into habits of laxity and inattention in the discharge of their duty, and at least some of this force were also imperfectly instructed regarding their duties. In the view of the department, the evidence establishes, further, that certain appurtenances, to wit, the safety and sentinel valves of at least one of the boilers, were not in an efficient condition at the date mentioned, and had not been in such condition for a considerable time previously, and, in the

judgment of the department, this evidence renders the statements that the ship was in a 'good and efficient condition,' and that her boilers were in 'fair condition and efficient,' inappropriate to the facts disclosed by the proof."

The secretary then discusses certain portions of the evidence which, he says, were sufficient to justify the court in advancing another charge of neglect of duty against Ensign Wade and proceeds:

"The department approves the recommendation of the court of inquiry that Ensign Charles T. Wade, United States navy, be brought to trial by court-martial upon the charges contained in the opinion of said court of inquiry. Such court-martial is hereby ordered, but the judge advocate is instructed to include in the charges and specifications the further charge hereinbefore set forth.

"Inasmuch as the court of inquiry did not pass expressly in its findings and opinion upon the conduct of Com'dr Lucien Young, United States navy, commanding the United States ship Bennington, and the question of his responsibility, the department must treat this silence as an implied finding that he was not thus responsible. After very careful consideration the department is compelled to disapprove this implied finding.

"The provisions of the regulations, and the facts disclosed by the report of the court of inquiry, make it the duty of the department to require Com'dr Lucien Young to clear himself before a general court-martial of the charge of neglect of his official duty above indicated. Such court-martial is therefore ordered."

Secretary Bonaparte then praises "the highly creditable conduct of all the survivors of the officers and crew of the Bennington after the explosion occurred." He includes in this commendation Com'dr Lucien Young and Ensign Charles T. Wade and Lieut. A. F. H. Yates.

"Notwithstanding the severe loss sustained by the ship's complement," says the secretary, "discipline was fully maintained; all the officers seem to have discharged their duties with entire presence of mind, intelligence, and courage; the crippled vessel was handled judiciously and skilfully, and survivors of the crew showed bravery and humanity in the rescue of their unfortunate shipmates worthy of the honorable traditions of our service. The department notes with pleasure these redeeming features of an appalling and also discreditable disaster."


## PENOBSCOT TO BE LENGTHENED NINETY-SIX FEET

The Lake Transit Co., of Buffalo, has closed a contract with the Craig Ship Building Co., of Toledo, for lengthening the steamer Penobscot 96 ft. during the coming winter. This plan of increasing carrying capacity became quite popular last winter when six lake vessels each received an additional 72 ft. amidship, increasing their capacity about 1,500 tons. That a contract for this work on the Penobscot should be let thus early may be taken as a fair indication that several others will be lengthened this winter as vessels enlarged have performed very satisfactorily and owners are pleased with the outcome. Owners as a rule do not consider this work until the end of the season, and it is definitely known where the boat will be after delivering her final cargo.

There are on the Pacific coast two completed naval dry-docks, one at the Mare Island, Cal., navy yard, and the other at the Bremerton navy yard on Puget Sound. Active construction of a third dock began on Aug. 1 at Mare island. The Vallejo Chamber of Commerce has been reorganized and will urge the claims of the Mare island navy yard on the senators and representatives from California. The building of another stone drydock on the Pacific coast is to be recommended by the navy department.


### LAUNCH OF THE FRANK J. HECKER

The launch of the steamer Frank J. Hecker at the St. Clair yard of the Great Lakes Engineering Works on Saturday



COL. FRANK J. HECKER.

last was an event of more than usual importance, and was so characterized by the ceremony which marked it. The Hecker is the second vessel which the Great Lakes Engineer-




THE HECKER ON THE STOCKS.

ing Works has launched at St. Clair, but the first that it has launched since it became the actual owner of the yard. The company gave emphasis to its possession of this yard by an elaborate banquet at the Oakland Hotel immediately following the launch of the Hecker. It is the intention of the company to greatly enlarge its facilities at this plant and also to extend the area of the yard. At present there is provision for building only one steamer at a time, but it is intended

eventually to make the yard capable of constructing three steamers at one time.

The Hecker was named by Mme. de Szilassy in honor of her father, Col. Frank J. Hecker. The launch was successful in every way, the Hecker taking the water on an even keel and without any hitch whatever. The steamer is building for the Gilchrist Transportation Co., of Cleveland, and is a sister ship of the George H. Russel, launched at this yard in April last. Both the Russel and Hecker are 484 ft. over all, 464 ft. keel, 50 ft. beam and 28 ft. deep, and are equipped with triple-expansion engines, 22, 36 and 60 in. cylinder diameters by 40 in. stroke, supplied with steam from two Scotch boilers, 13 ft. in diameter and 11 ft. 6 in. long. While both boats are classed as 7,500-ton boats, the Russel, which has been in commission for some time, has carried 8,200 tons.


The launching party went from Detroit to St. Clair in a special car and included Col. and Mrs. F. J. Hecker, Mme. de Szilassy, Antonio C. Pessano, president and general man-



LAUNCH OF THE HECKER.

[Copyrighted, 1905, by Detroit Publishing Co.]

ager of the Great Lakes Engineering Works; Mr. John R. Russel, Henry Russel, S. R. Russel, Mr. and Mrs. J. C. Hutchins, Frank E. Kirby, Capt. A. E. Stewart, J. C. Mc-



DECK VIEW OF THE HECKER.

Donald, Miss Nora Johnson and Miss Hance, of Detroit; Mr. J. C. Gilchrist, Mr. J. D. Gilchrist, Mr. W. B. Gilchrist,

Mr. and Mrs. F. D. Gilchrist, H. S. Snyder, Mr. and Mrs. Lee Selover, of Cleveland; Capt. Joseph Perew, J. S. Waterson, H. S. Sill, of Buffalo; Mr. and Mrs. B. S. Wood, Bellevue, O.; Mr. and Mrs. B. T. Knowlton, Cadillac, Mich., and Mr. G. F. Thompson, Youngstown, O. The party were joined at the banquet at the Oakland by Congressman Henry McMorran.

President Antonio C. Pessano acted as toastmaster at the banquet and responses to toasts were made by Col. Hecker, Henry Russel, Congressman McMorran, Mr. J. C. Hutchins and Mr. J. C. Gilchrist.

### COMMERCE OF SAULT STE. MARIE CANAL

The commerce of the Sault Ste. Marie canal during August reached the figure of 6,327,595 net tons, as against 5,644,772 net tons for August of last year. The year 1905 is the only year in which the commerce of these canals has reached the six-million mark. The total movement of freight to Sept. 1 of the present year has been 26,164,799 tons, as against 14,842,975 tons to Sept. 1 of last year, and 22,628,170 tons to Sept. 1, 1903. The great increase has been in the iron ore movement and some of the other commodities show a decided falling off. Following is the summary of traffic brought up to Sept. 1 of the present year with comparative tables for the corresponding period during 1903 and 1904:

#### MOVEMENT OF PRINCIPAL ITEMS OF FREIGHT TO AND FROM LAKE SUPERIOR.

Items	To Sept. 1, 1905.	To Sept. 1, 1904.	To Sept. 1, 1903.
Coal, anthracite, net tons.....	550,786	518,574	645,894
Coal, bituminous, net tons.....	3,427,034	2,355,166	3,976,210
Iron ore, net tons.....	19,596,553	8,696,180	14,980,989
Wheat, bushels.....	16,086,194	18,617,797	27,248,292
Flour, barrels.....	2,126,092	1,645,403	3,821,120

#### REPORT OF FREIGHT AND PASSENGER TRAFFIC TO AND FROM LAKE SUPERIOR, FROM OPENING OF NAVIGATION TO SEPT. 1 OF EACH YEAR FOR THREE YEARS PAST.

##### EAST BOUND.

Items.	To Sept. 1, 1905.	To Sept. 1, 1904.	To Sept. 1, 1903.
Copper, net tons.....	56,580	48,847	59,269
Grain, other than wheat, bushels.....	12,705,843	8,744,364	11,726,457
Building stone, net tons.....	7,468	14,234	8,440
Flour, barrels.....	2,118,917	1,645,296	3,821,090
Iron ore, net tons.....	19,596,553	8,696,180	14,980,989
Iron, pig, net tons.....	39,724	21,190	8,963
Lumber, M. ft. B. M.....	570,119	493,324	576,118
Silver ore, net tons.....		1,313	
Wheat, bushels.....	16,086,194	18,617,797	27,248,292
Unclassified freight, net tons.....	55,937	51,748	53,185
Passengers, number.....	20,384	13,881	23,019

##### WEST BOUND

Coal, anthracite, net tons.....	550,786	518,574	645,894
Coal, bituminous, net tons.....	3,427,034	2,355,166	3,976,210
Flour, barrels.....	7,175	107	30
Grain, bushels.....	1,533	625	1,000
Manufactured iron, net tons.....	65,829	69,904	88,569
Salt, barrels.....	257,206	248,837	255,253
Unclassified freight, net tons.....	408,955	285,485	307,945
Passengers, number.....	23,164	13,946	23,195

#### SUMMARY OF TOTAL FREIGHT MOVEMENT IN TONS.

	To Sept. 1, 1905.	To Sept. 1, 1904.	To Sept. 1, 1903.
East bound freight, all kinds, net tons.....	21,673,180	10,576,709	17,566,297
West bound freight, all kinds, net tons.....	4,491,619	4,266,266	5,061,873
Total freight, net tons.....	26,164,799	14,842,975	22,628,170

Total number of vessel passages to Sept. 1, 1905, was 13,077, and the registered tonnage, 21,710,816.

Coming into Duluth canal on Sunday night the steamer North Wind was driven by a wave against the pier and stove in her port bow. Tugs were signaled and the steamer attempted to get into the Northern Pacific slip, but sank when getting to dock. She will be raised at once and docked. The same storm smashed a protection pier on the Superior entry which was being built for the purpose of saving the new concrete. This was washed away for the second time this year.

### AT THE HEAD OF THE LAKES

Duluth, Sept. 5.—The steel ship P. P. Miller bunted into the interstate drawbridge across the Duluth-Superior harbor Saturday, and put both ship and draw out of commission, though to both the damage was really quite small. The ship went to the dock of the Superior Ship Building Co.

There is a very large amount of ore tonnage always in harbor this summer, attributed by vesselmen to the failure of the mines to get ore down as fast as schedule. But in point of fact the mines and mining roads are up to their schedules, and the movement out of the docks of the Duluth, Missabe & Northern road last month was the largest on record and almost up to the facilities of the dock system. This is estimated by the company as 1,500,000 tons a month, and August's tonnage was 1,433,000 gross tons. The Duluth & Iron Range road moved about 1,250,000 tons and the Great Northern 700,000 tons, so that the Minnesota ore shipment for the month was 3,400,000 tons. The Mesabi range has shipped so far this year a total of 12,650,000 tons of ore, the Vermillion range 1,140,000. This is about the full season's figures for two or three years ago.

Grain receipts at the head of the lakes were larger in August, on account of the movement to Duluth of 500,000 bu. wheat from Minneapolis for eastern mills, and the commencement of the fall movement of new barley. Receipts for the month were 2,588,000 bu., shipments 2,336,000. New wheat is coming as an occasional carload only, but sales from the country of wheat "to arrive" have begun and the flood is expected during the present month. The same is true of flax. If half that is told of the new flax crop is correct there will be such a flood of it as has never been seen, and the wonder is what can be done with it. The talk now is for a crop in the region tributary to Duluth of about 29,000,000 to 30,000,000 bu., and the country's consumption is less than 20,000,000 per annum. There are somewhat less than 5,000,000 bu. seed, some of it three years old, in store here, which cost the owners all the way from 90 cents a bushel to \$1.25 and more.

There is much interest in Superior in the announcement that the Superior Ship Building Co. had been awarded one of the new contracts taken by the American company for a large freighter. There is no work in sight for the yard aside from this. It is considered probable that two ships may be built here.

Work was commenced on the Osborne coal dock at Superior, the Clark Dredging Co. having put its men at work this week. Contracts for the superstructure have not been let.


W. S. Cleaves, of Portage Lake, has been making extensive improvements to his marine machinery plant, and contemplates the erection of a large and modern drydock the coming year.

If ore business continues to increase at the present rate and the new ships become more and more common, it is probable that at least two more ore docks will be built at the head of the lakes the coming winter, or possibly a year later, and that one or two of those now in use will be torn down. If new ones are built they will probably be the largest and highest ever constructed. There has been some talk of figuring on steel construction for new docks, but this will scarcely come about yet. The final type and size is not yet definitely known.

E. G. Todt, formerly superintendent in the engine department of the Chicago Ship Building Co., South Chicago, has resigned to become vice president and general manager of the Gunnell Machine Co., Manitowoc, Wis., manufacturers of marine engines, propelling machinery, etc.

**HEAD-ON COLLISION IN KAISER WILHELM CANAL**

Accompanying this article are two pictures showing the effect of a head-on collision which happened on June 16 in the Kaiser Wilhelm canal. Both steamers were going at



STEAMER SKELLEFTEA.

low speed and when they tried to clear each other the steamer Stadt Schleswig did not obey the rudder. The pilot ordered full speed ahead in order to get steerage way but it was too late to avoid collision. The Schleswig struck the steamer Skelleftea on the starboard bow and while she lost her anchors (the broken shaft can be seen in the hawse pipe) and bent her bow, she also inflicted severe injuries to the Skelleftea.

**FINE ENDORSEMENT OF PROPELLER WHEEL**

The MacKinnon Manufacturing Co., Bay City, Mich., boiler makers, founders and machinists, have received a letter from Capt. Frank Elliott, master of the steamer Oregon which affords a striking endorsement of the propeller wheels manufactured by this company. Capt. Elliott writes as follows:

"Mr. H. D. MacKinnon, Bay City, Mich. Dear Sir—Your letter bearing date of Aug. 1 was handed me by Capt. J. A. Calbick, and will say that the wheel has proved a perfect success. I never was able to pull my barge over seven miles per hour until this summer, and it is no trouble for me to pull eight since I put on your wheel. Of course I did some work to our engine which has helped our time some, but take it all around, your wheel, for both running and pulling, can't be beat, and I think, without a doubt, you will get more


orders from this company. I have also told all my friends who would be liable to want a wheel, our work is advertised enough and should give you a good boost in getting more orders. Yours very truly,

"CAPT. FRANK ELLIOTT."

**CHANNEL FRAMING FOR TURBINE STEAMERS**

The two turbine steamers to be built by Roach's ship yard, Chester, Pa., for the Metropolitan Steamship Co., of New York, as well as the turbine steamer building for the Eastern Steamship Co. at the same yard, will be constructed under special survey for the highest class in the United States Standard Register. The Metropolitan line steamers will have channel framing with the channel section split at the turn of the bilge to form bottom frame and reverse frame as patented by Mr. Sinclair Stuart, of the United States Standard Steamship Owners, Builders & Underwriters' Association, Ltd. This form of construction was adopted in the steamers Minnesota and Dakota of the Great Northern line, in the Shawmut and Tremont of the Boston Steamship Co.'s fleet and in the steamers built by the Maryland Steel Co. for the Atlantic Transport Co. It has been accepted by the British Corporation, Lloyd's Register and the United States Standard Register.

The United States cruiser Chicago, flagship of the Pacific coast squadron, started Aug. 24 for Puget Sound. She will



STEAMER STADT SCHLESWIG.

be placed in drydock at the Bremerton navy yard for the purpose of ascertaining whether she suffered any damage when she ran on the rocks of Angel island, San Francisco bay.



## A UNIT TYPE OIL FILTER


The Burt Mfg. Co., Akron, O., have recently brought out a system of filtering oil in which a number of separate units may be connected together to filter the oil used in a large plant. Each unit is independent in itself, and new units may be added as the plant grows, thus keeping capacity of the oil filter system up to the size of the plant.

A sectional view of a single unit is shown in the accompanying illustration. The dirty oil enters the waste oil receptacle and passes through the small perforations, flowing thence horizontally to the two filtering cylinders, and in passing into these two cylinders, the heavy impurities fall by gravity into the sediment pan. They are thus disposed of and do not clog the filtering cloths or filtering material. The filtering cylinders are wrapped with cloths through which the oil passes before entering the cylinders. The cylinders are filled with a quantity of animal bone black, through which the oil must flow before entering the two tubes which lead from the cylinders to the bottom of the filter. Two plates are attached to the bottom of the tubes and the oil is spread out in a very thin film by means of these plates.


It is thus thoroughly washed by the water in the filter and any remaining impurities in the oil drop to the bottom of the filter and can be flushed out at any time desired by simply opening the gate valve, which connects with the sewer.

A hot water chamber surrounds the upper part of the filter which contains the filtering mechanism. The water in this chamber is heated by a small steam coil which is fed with live or exhaust steam, from any convenient source. The oil is thus heated before filtering and flows more freely, thereby increasing the speed of filtration and the filter capacity. When the dirty oil is heated it spreads out and most of the dirt and grit then falls into the sediment pan. The bulk of the sediment in this type of filter is at the top, where it can be readily removed without interfering in any way with the supply of pure oil for the oiling system. The maker guarantees that the filter will handle successfully the heaviest grades of oil, such as lard, gas engine and cylinder oil.

In the construction of the unit type of filter heavier iron is used than in the regular type of filter, and the body is riveted to a heavy wrought iron frame. All



SECTIONAL VIEW OF OIL FILTER UNIT.



OIL FILTERING PLANT CONSISTING OF THREE UNITS CONNECTED TOGETHER.

seams are lapped, riveted and soldered. The upper and lower part of the filter cylinders are made of cast iron, nickel plated on the top. The tubes leading from the filtering cylinders to the bottom of the filter are of wrought iron. The filter is painted dark blue, decorated with gold, and is an ornament to any first-class power plant.

The filters are so constructed that they may be used with or without an oiling system. They can, if desired, be installed and operated at first without being connected with an oiling system, and later on, if an oil system is added to the plant, pipe connections can readily be made to the filter at slight expense.

It is not necessary to shut down a system and disconnect pipe connections in order to clean the filter. If more than one unit is used it is only necessary to shut off the flow of oil to the filter to be cleaned, the other units being able to handle easily the extra amount. When only one filter is installed, the cloth around one cylinder can be removed instantly, and if the filtering material also needs to be removed, one cylinder is unscrewed and a plug which is furnished for the purpose is screwed into the tube, so as to keep the dirty waste oil from flowing into the filter. The other cylinder continues in operation while the first is being cleaned.

Any type of filtering material can be used in the cylinder, such as white waste, sponges, excelsior, raw wool, etc. The manufacturer recommends the use of animal bone black, which is in use in all oil refineries for purifying oil. This material can be washed with hot water or gasoline and used many times. Filtering cloths may also be used to purify the oil. As any number of cloths may be wrapped around the filtering cylinders and in changing them nothing but the cloths need be removed, the cloths can be removed while the filter is in operation without changing or touching any pipe connections.

This type of filter is recommended by the makers for use with gas engines of large capacity, as the hot water from the engine cylinders can be used for the purpose of heating the oil. It is also recommended for use in gas or steam turbines, for the reason that an exceptionally large quantity of oil is used on these machines, and the oil being very thin will filter rapidly through this type of filter, owing to the effect of the hot water chamber at the top. It has been installed by a large number of prominent manufacturers in the United States. It has been largely adopted for use in the United States navy, and also the Japanese and Russian navies.


### A NEW MARINE GOVERNOR

A new type of marine governor has been placed on the market recently by the Sheffield Engineers Limited, Sheffield, England. This governor is designed to overcome difficulties which have been discovered in the action of other marine governors, involving slowness of action and difficulty of attachment to existing engines. It is primarily designed to prevent racing of marine engines, when the propeller leaves the water or upon the breaking of the propeller shaft. The governor acts upon the principle that the power necessary to move water through a small aperture increases with the velocity of the water.

The governor is shown in the accompanying illustration. In the frame is cast a pump cylinder of 2 in. in diameter. In this frame is also cast a crosshead slide. The pump piston A is connected by a piston rod to the crosshead B; the connection is made by the means of a pin C. This pin has a slight motion in a slot in the crosshead, in the direction of the axis of the piston rod. This motion is independent of the movement of the pump piston. A connecting rod D joins the crosshead to the engine shaft or any other part of the engine

which will give a reciprocating motion to the crosshead. At a central point on the frame of the governor is mounted a lever E. This lever is arranged to have a slight rotation about a pin at its center, and is joined to the throttle valve by wires or chains running from its extremities. It is operated by means of a two-armed tappet lever F, which is pivoted on the crosshead pin.

The operation of the governor is as follows: When the pump piston A is operated by the engine, water is drawn through a suction valve G from a small tank. This water is



delivered back to the tank through a valve H. This valve is so arranged as to form an adjustable opening. When the engine is running at normal speed the crosshead and pump piston move in unison. They are kept in their extreme relative position by means of a spiral spring J. On the tappet lever F is a small piece which acts with the crosshead pin, so that when the spring is not compressed the forked end on the right hand side of the tappet lever is in the path of a pin on the lever E, and holds it in the position shown, thus keeping open the throttle valve.

When the engine increases in speed by means of the propeller leaving the water, or any other accidental cause, resistance to the passage of water through the valve H is increased. This causes a greater pressure in the pump cylinder, so that the pump travels somewhat slower than the crosshead owing to the compression of the spring J. The pin C thus moves along the slot in the crosshead and throws the tappet lever F to such a position that the fork on the left hand side of the lever engages the pin on that side of the lever E. Upon the completion of the stroke the lever E is rotated to a position opposite, as shown in the illustration, thus closing the throttle valve and slowing down the engine.

The tappet lever remains in such a position as to keep the throttle valve closed just so long as the increased resistance is maintained in the pump cylinder. When the speed of the engine is reduced and the resistance in the pump cylinder comes back to normal the spring J will bring the pin C into the position shown in the illustration and cause the tappet lever to return to its original position, and then will engage with the pin on the right hand end of the lever and move

it to the position shown in the illustration, thus reopening the throttle.

Mounted above the valve H is a spring and bridge K which enables the latter to act as a relief valve. The approximate outside dimensions of the governor are 20 in. x 9 in. x 10 in., and the weight of the governor is about 100 pounds.

### RUSSIAN SAILING VESSELS

A list of Russian sailing vessels of 75 tons and upwards has just been published at Riga by Mr. A. Bandrewitch, and attached to it is an introduction giving particulars of the development and present position of the building of small wooden sailing ships along the Baltic coast. The list contains some hundreds of these craft, and the accompanying statistics show that the construction of these small ships is still going on. Last year, however, it was not so brisk, owing probably to the war and the circumstances arising from it: only fourteen small sailers, measuring altogether 2,956 registered tons, having been built, against twenty (4,507 tons) in 1903, thirty-three (6,220 tons) in 1902, and thirty-six (6,745 tons) in 1901. This fleet of sailing ships is, of course, of no importance from an international point of view, nevertheless the reproduction of a few of the remarks made upon it will probably not be without interest.

In the first place we are told that up to the 70's of last century the trading firms of Riga, Windau, and Libau were exclusively the owners of merchant vessels in the Baltic provinces, and even later than that some of these firms have been the possessors of a large number of sailing ships. The members of these firms also acted as experts in maritime affairs on the exchange committees at the ports where they resided. Early in the 70's, however, this state of things was altered. On the initiative of the Grand Duke Constantine, seamen's training schools were founded at various places on the coast according to the plan of C. Waldemar, who was likewise the originator of the scheme for the formation of the Volunteer fleet. A road was thus opened to the dwellers on the coast, especially the fishermen, for a thorough sea training. This movement was fostered and assisted by the Society for the Development of the Russian Mercantile Navy, formed at Moscow in 1873, and in a short time about forty training schools for seamen came into existence. Navigation schools for the training of officers were also established to the number of four, but by virtue of a law passed in 1902 three of these were abolished, an only one was left, that at Haynasch, and the chances of the poorer inhabitants of the coast becoming experienced navigators were much diminished.

That which had been accomplished, however, in the way of maritime training for the coast population had the effect of arousing an interest in the construction of small sea-going craft, and by a gradual process the whole Baltic sailing fleet quitted the possession of the trading firms and became the property of the inhabitants of the coast, and by the same process those firms lost touch with the maritime circles and the exchange committees.

In 1904 the administration for Russian Maritime Trade and Seaports returned the cost price of the 875 sailing ships registered in the Baltic ports, measuring altogether 103,527 registered tons net, at 5.6 million roubles, being equal to about 62½ roubles per ton. The craft included in the above-mentioned list are mostly ships built within the last ten years, the value of which is estimated at a higher figure than that just quoted, namely, from 75 to 85 roubles per ton. The present cost of building, however, is put at 95 to 110 roubles per ton, if built on the coast, and at a somewhat higher figure if built in the seaports.

### WORLD'S FOUR GREATEST NAVIES

Editor *Marine Review*: The United States now holds fourth place as a naval power, with 316,523 registered tons. Germany holds third place with, according to the *Hamburger Nachrichten*, 341,243 tons. The United States has 324,500 warship tonnage under construction, says the same paper, and Germany has 126,557 tons. When the war vessels now building by each are completed, the United States will have a warship tonnage of 641,023 and Germany will have 467,800. This will put the United States in third place, with a lead over Germany of 173,223 tons.

France has a present war tonnage of 603,721, with 170,279, a total of 774,000, or 306,200 tons more than Germany. The combined lead of the United States and France will be 947,223 tons.

Great Britain has 1,593,871 tons in use, and 338,129 tons building, a total of 1,932,000 tons. When all the warship construction now under way by the four countries is completed, the world's four greatest navies will line up, as follows: Great Britain, 1,932,000 registered tonnage; France, 774,000 registered tonnage; United States, 641,023 registered tonnage; Germany, 467,800 registered tonnage.

Schenectady, N. Y.

WALTER J. BALLARD.

### A WORD OF APPRECIATION.

President Pro Tempore  
United States Senate.

Mr. Harvey D. Goulder,  
President Merchant Marine League.

My Dear Sir:

I have just had an interview with Mr. A. R. Smith, commissioner of the Merchant Marine League, of which you are president. You have entered upon a very important work and seem to be pushing it vigorously. I am glad to have help in my endeavor to restore our Merchant Marine to its proper position on the ocean from the mid-West, and to find at the head of this association a gentleman for whose ability I have such high respect.

Your commissioner, Mr. Smith, is a hustler, and has been of great aid to me in the past, and there is no limit to the amount of intelligent work he will do.

I am, Very truly yours,

WM. P. FRYE.

Lewiston, Me., Aug. 24, 1905.


For some time past the Union Iron Works of San Francisco have been making extensive repairs on the Russian converted cruiser *Lena*, which has been interned at the Mare Island navy yard since September, 1904. Much of the cruiser's machinery has been removed and taken to the shipyards of the Union Iron Works. The crew has done as much as possible in repairing the vessel, which will return to Russia as soon the arrangements between Japan and Russia permit. On Aug. 9 the *Lena*, escorted by the torpedo boat *Fox* and the tug *Wheeler*, made a trial trip in San Francisco bay. She was permitted to go anywhere within the limits of the bay but not outside the Heads. She returned to Mare island on the morning of the 10th.

### A NEW FORM OF METALLIC PACKING

The Goodyear Tire & Rubber Co., Akron, O., have recently brought out a new form of metallic packing, which is illustrated herewith. This packing can be applied to any rod or valve stem without trouble or loss of time. The packing is made of two materials, metal and rubber. The actual packing is done by the metal pieces, the rubber acting merely as a cushion for the metal part, and does not touch the rod. The metal portion is made in the form of a ring which is broken into three pieces. The cross section of this ring is roughly the quadrant of a circle. Two rings are placed together so as to break joints. The rubber ring is then placed between each pair of metal rings and the hole tightened up in the stuffing box.

In packing, a half ring of rubber "A" is first placed in the stuffing box. The metal ring "B" is next placed on the rod so that the beveled side will fit into the offset in the ring "A." To place the metal rings it is necessary that one of the small copper wires "C" joining the various portions of the ring be cut, which will permit of the ring being spread so that it can be easily placed around the rod. A second metal ring is placed on the first with the flat sides of the two together, care being taken to see that the joints are broken. A complete rubber ring "I" is then placed over the metal ring, and so on until the stuffing box is filled. A half rubber ring "A" is placed at the outer end of the stuffing box. The gland of the stuffing box is turned up with hand so that it rests firmly against the packing. If there is any leakage when first starting the engine, the packing will soon adjust itself without tightening the stuffing box.


The maker states that it is a perfect packing for steam, air, ammonia, oil, water, and glass. It has been installed in a number of plants and has held under very severe conditions. For instance, at the Carnegie Steel Works great difficulty was experienced in packing a large steam hammer. The packing rarely lasted over nine



METAL PACKING RING, GOODYEAR METALLIC PACKING.



RUBBER CUSHION-RING, GOODYEAR METALLIC PACKING.



GOODYEAR METALLIC PACKING.

days. Packing of this type was tried and ran sixty days without being renewed. The maker guarantees the packing to hold for one year, it having been tried in the shop for that length of time before being placed on the market for any given service.

### TRADE NOTES

The Falls Hollow Staybolt Co. have orders for hollow staybolt iron bars for export to the Imperial railway of North China and a leading railway of Japan.

Charles Cory & Son are furnishing material and installing complete the interior means of communication, Battle & Range order signals, comprising telephones, electrical engines, steering and helm order telegraphs, speed and direction revolution indicators, fire alarm systems, general alarm systems, speaking tubes and call bells on the following naval vessels: Charleston, Virginia, Louisiana, Minnesota, Washington, Kansas, Georgia, St. Louis.

The Wilcox Manufacturing Co. of Aurora, Ill., has increased its capacity in the overhead trolley track department by enlarging its plant and installing heavy machinery for the manufacture of all types of cranes. At the head of the engineering department has been placed Mr. C. F. Blake, a member of the A. S. M. E., formerly with the Shaw Electric Crane Co., Muskegon, Mich., who has had many years' successful experience in designing and erecting cranes of all descriptions.

The combination of modern cranes with its overhead trolley system, says the Wilcox company, places it in position to make bids on equipment to hoist and transport "anything anywhere any time."

The advent of the independent air pump and condenser has had much to do with the practical development of the compound engine in medium and small sizes for with this combination there are now obtainable economic results which not long since were expected only from the large compound engine with direct connected air pump. It is seldom that a non-condensing plant can be found where an increase of 20 to 30 percent in the output cannot be obtained coincidentally with a reduction of 15 to 25 percent in the steam consumed per horse-power. The convenience of application and operation of the separate condenser are appreciated by every engineer. That the jet and the surface type have their respective fields, is clearly recognized. Both designs in a full line of sizes are now being manufactured by the W. H. Blake Steam Pump Co., of Hyde Park, Mass. They range in capacity from 600 to 40,000 pounds of steam condensed per hour with injection water at 70 degrees F.

Elisha Webb Jr., of Elisha Webb & Son, Philadelphia, manufacturers of steamship equipment, leaves on the 25th inst. for an extended trip along the lakes from Buffalo to Duluth, thence by rail to Seattle, Tacoma, Portland and San Francisco, for the purpose of renewing acquaintances and making new friends and customers for his firm, whose clients in the West have increased to such an extent that a periodical visit is as pleasant as it is profitable. The many specialties manufactured by Messrs. Elisha Webb & Son for the equipment of vessels, makes their line not only desirable but interesting to ship builders and owners. The demand for the "Webb Perfection Circulating System" for supplying hot and cold water on shipboard in connection with their galley ranges, has far exceeded their most sanguine expectations. This departure from the ordinary methods of supplying this necessary commodity on shipboard, is explained at considerable length in a pamphlet describing the apparatus, which the firm is publishing and will be mailed upon application. A trip to Yellowstone Park for a little recreation will be a feature of Mr. Webb's trip.





VOL. XXXII.

CLEVELAND, SEPTEMBER 7, 1905.


No. 10.

## THE BIRD-ARCHER CO.

209 Washington St.  
NEW YORK

We Guarantee our Metallic Boiler Compound to remove all Scale, Oil, and Grease from Boilers; prevent the formation of new; prevent Pitting, Corrosion, and Galvanic Action, Guaranteeing that it will not cut Lubrication, or Injure Packing; that it will do away with the necessity of using Zinc and will not cause Boilers to Foam or Prime, or no pay.

## MARINE METALLIC BOILER COMPOUNDS



## CORRIGAN, MCKINNEY & CO.

716-719 PERRY-PAYNE BUILDING.

IRON ORES  
& BIG IRON.

James Corrigan  
Stevenson Burke  
Price McKinney

Cleveland, O., June 1, 1905.

Bird Archer Co.,  
209 Washington St.,  
New York, N. Y.


Gentlemen:—

I was never in favor of using compound until Mr. Bennett induced me to try a trial package at the Genesee Furnace, and was very much pleased on opening the boilers to find them free from oil, grease and scale. I find it also stops pitting and corrosion. I am using the compound on all of our boats and furnaces with the same result. I can cheerfully recommend your compound to any engineer who desires a superior article.

Yours truly,

H. J. REYNOLDS,  
Superintending Engineer.

CAN WE NOT DO THIS FOR YOU?



## Morison Suspension Boiler Furnaces

For Land and Marine Boilers

Uniform Thickness—Easily Cleaned  
UNEXCELLED FOR STRENGTH


Also Fox Corrugated Furnaces

Manufactured  
by

**THE CONTINENTAL IRON WORKS,**

West and Caylor Sts., NEW YORK.

Near 10th and 23d Sts. Ferries  
Borough of Brooklyn.



## THE "NEPTUNE" LOG

The "Neptune" Ship Log has  
ball bearings for high speeds.  
We also make the "CHERUB"  
and "HARPOON" Ship Logs.

MAKERS TO THE BRITISH NAVY

## THOMAS WALKER & SON

BIRMINGHAM, ENGLAND.

## The Brown Hoisting Machinery Company, Incorporated.

Engineers, Designers and Manufacturers of Special Machinery for  
hoisting, conveying, storing and handling material of all kinds under the  
well known "BROWNHOIST" Patents.

**Bridge Unloaders**  
for rapidly discharging bulk car-  
goes from vessels directly to cars  
to storage on docks.

**Fast Plant Unloaders**  
for rapidly handling either bulk or  
package freight.

**Cranes**  
of every description for every kind of service.

26 Cortlandt St.  
NEW YORK CITY

MAIN OFFICE AND WORKS  
**CLEVELAND, O., U. S. A.**

Carnegie Building  
PITTSBURG, PA.

European Office, 39 Victoria St., LONDON, S. W.

## New Metal Cargo Hoisters



Wrought Iron Hook and  
Strap, Galvanized Iron  
Shells and Sheaves.  
Sheaves fitted with Genu-  
ine Star Metaline Bush-  
ings with Metaline Side  
Bearings.



Star Metaline  
Bushing

These Blocks Save the Rope  
and Outwear all others.

Send for No. 15 Cata-  
logue M. A. R. FREE

**SELF-OILING**

Manufactured only by  
**BOSTON & LOCKPORT BLOCK CO.**

BOSTON, MASS.

LOCKPORT, N. Y.

SHIP MACHINERY, embodying the  
latest designs and  
many important  
patented improve-  
ments.

Sole builders of the  
Original and Only  
**AUTOMATIC  
STEAM TOWING MACHINE.**

Established  
1857

## AMERICAN SHIP WINDLASS CO.

Providence, R. I.

P. O. Box 53


We have completed our new Iron Foun-  
dry, and are pre-  
pared to execute  
orders for Castings,  
guaranteeing first-  
class work, prompt  
service and reason-  
able prices.

Send for illustrated  
catalogue

Address **FRANK S. MANTON, President**

**MARINE IRON WORKS,**  
INCORPORATED.  
BUILDERS OF **MARINE ENGINES** AND **BOILERS.**  
HIGH PRESSURE  
COMPOUND  
TRIPLE EXPANSION  
PADDLE WHEEL.  
COMPLETE OUTFITS OF  
**MARINE MACHINERY**  
A SPECIALTY.  
STATION A. CHICAGO, ILL.  
SUPPLEMENTARY CATALOGUE FREE ON REQUEST.

## THE COWING LIFT BRIDGE



THE JEFFERSON STREET BRIDGE, CLEVELAND, OHIO.

The Cowing Bridge represents the most modern type of Lift Bridge.

Highest Award at  
St. Louis, Mo. 1904.

Plans and estimates  
promptly furnished.

**JOHN P. COWING**

GEO. P. COLBURN, Eastern Agent  
1201 Fuller Bldg., New York City.

CONTRACTING  
ENGINEER

426 Citizens Building  
CLEVELAND, OHIO

## OTIS STEEL

SHIP PLATES FLANGE PLATES TANK PLATES STEEL CAR AXLES FORGINGS OF ALL KINDS

"Otis" Fire Box Plates a Specialty.

**STEEL CASTINGS FROM 100 TO 100,000 LBS.**

**OTIS STEEL CO., Ltd.,** Head Office and Works, **CLEVELAND, O.**


New York: Thorpe, Platt & Co., 97 Cedar St.  
Montreal: Homer Taylor, 183 St. James St.

AGENCIES.

St. Louis: C. A. Thompson, 516 N. Third St.  
San Francisco: John Woodlock, 154-156 First St.

Detroit: George W. House, Union Trust Building.





## The American Ship Building Company

MAIN OFFICE CLEVELAND, OHIO



Marine and  
Stationary Engines

### STEEL SHIPS

Boilers and  
Auxiliary Machinery

Sole Agents for the Lakes for the Ellis & Eaves Induced Draft System, as applied to boilers, giving increased power and great economy.

WORKS AT CLEVELAND AND LORAIN.



## Detroit Ship Building Company

### SHIP AND ENGINE BUILDERS

Sole Owners for the Lakes and Atlantic Coast of the HOWDEN HOT DRAFT SYSTEM as applied to Boilers, giving increased power and great economy.

Steel Ship Yard located at Wyandotte, Michigan  
Wooden Ship Yards and Dry Docks, Foot of Orleans Street, and Foot of Clark Ave., Detroit, Mich.

Alexander McVittie, President and Manager  
William C. McMillan, Vice President  
M. E. Farr, Secretary and Treasurer  
Charles B. Calder, General Superintendent  
Frank E. Kirby, Consulting Engineer

WM. L. BROWN, Pres.


J. C. WALLACE, Vice-Pres.

R. C. WETMORE, Sec'y and Treas.

O. W. FREY, Ass't. Treas.

ALFRED G. SMITH, Gen'l Supt.

## Chicago Ship Building Company




### STEEL SHIPS

*Passenger or Freight*

ANY SIZE

Yards, Dry Docks and Repair Shops at South Chicago, Ill.



## The Superior Ship Building Company

### SHIP AND ENGINE BUILDERS

*Dry Docks and Repairs of all kinds*

Large stock of material always on hand for Repairing Wooden and Metal Ships.

Repairing promptly attended to, Night or Day.

WEST SUPERIOR

WISCONSIN





## Pintsch Gas Lighted Buoys

BURN CONTINUOUSLY

FROM 80 TO 365 DAYS AND NIGHTS WITHOUT ATTENTION AND CAN BE SEEN AT A DISTANCE OF SIX MILES.

**Brilliant & Steady Illumination. Economical & Reliable in Operation.**


Adopted by the English, German, French, Russian and United States Light House Departments for Channel and Harbor Lighting; over 1800 gas buoys and gas beacons in service.

Controlled by the

**SAFETY CAR HEATING & LIGHTING COMPANY**

160 Broadway,

NEW YORK CITY.



## Milwaukee Dry Dock Company

MILWAUKEE

WISCONSIN

**SHIP REPAIRS  
OF ALL KINDS**


We have two ship yards offering every facility for the repair of both steel and wooden vessels. South Yard Dock is 450 ft. long on keel blocks; 460 ft. over all; 60 ft. width of gate and 16 ft. over sill. West Yard Dock is 312 ft. on keel blocks; 45 ft. width of gate and 12 ft. over sill. Rudder pit in each dock.

Electric lights for night work.

**MAIN OFFICE AT SOUTH YARD**

Foot of Washington Street

Telephone Main 3



## The Buffalo Dry Dock Company

BUFFALO

NEW YORK


Operating four Docks, Sixty-Ton Shear Legs, and in every way equipped with modern plant for the building and economical repairs of **STEEL AND WOODEN SHIPS.**

EDWARD SMITH, President

ADAM STEEL, Superintendent

WILLIAM KNIGHT, Asst. Sec'y and Treas.

Office Telephone, 515 Seneca. President's Office Telephone, 2329 Seneca.  
President's Residence Telephone, 209 Bryant. Asst. Sec'y's Telephone, 324 North.  
Superintendent's Telephone, 2294 Howard.



## CRAIG SHIP BUILDING CO.

TOLEDO, OHIO.


**METAL - AND - WOODEN - SHIP - BUILDERS.**

New Dry Dock—525 feet long, 110 feet wide on top,  
55 feet wide on bottom, 16 feet of Water on Sill.

**Repairs to Metal and Wooden Ships  
A SPECIALTY.**

# OUR SHIPYARD

WITH ITS ACCOMPANYING DRY DOCKS  
AND WORKS, WAS CAREFULLY DESIGNED,  
EQUIPPED AND COMPLETED FOR THE




CONSTRUCTION AND REPAIRING  
IN EVERY DETAIL OF


BATTLE SHIPS · ARMORED CRUISERS ·  
PROTECTED CRUISERS · GUN BOATS ·  
TORPEDO BOATS · TORPEDO BOAT  
DESTROYERS · SUBMARINE BOATS ·  
OCEAN LINERS · PASSENGER STEAM  
ERS · FREIGHT CARRIERS · ETC · ETC ·

NEWPORT NEWS SHIPBUILDING & DRY DOCK CO.  
1 BROADWAY NEW YORK — NEWPORT NEWS, VA.

**THE BIG  
4  
FOR  
EVERY  
ENGINEER**



Penberthy  
Automatic Injector




Penberthy  
Auto Positive Injector

**-THIS-  
TRADE**

# PENBERTHY


MARK

**is a Guarantee of Excellence.**  
**No Boiler Room is Complete  
Without Them**



Penberthy  
Force Feed Oil Pump

**SIMPLE  
RELIABLE  
DURABLE  
ECONOMICAL**



Penberthy  
Injector Co.  
Detroit, U.S.A.

**Success**  
Vacuum Auto Water Gage



**There ought to be a  
U.S. AUTOMATIC  
INJECTOR**

## In Every Boiler Room.

It is the one perfect injector for every type of steam boiler. It is almost as indispensable for the perfect operation of a boiler as the water which it feeds.

It brings satisfaction to every engineer because it brings complete freedom from injector troubles. Its simple and strong construction insures freedom from repair bills, makes it easy to keep clean, and is the secret of its well-known reliability. The U. S. Automatic injector starts at lower steam pressure and works to higher than any other; can be used as lifting or non lifting injector, and its range and capacity are *guaranteed* by a certificate accompanying each. Demand the genuine "U. S." Take no substitute.

Some interesting facts about boilers and their care, with a few words about injectors, are contained in our famous "Engineer's Red Book." Sent free to all who write. Let us hear from you.

**American Injector Company,  
Detroit, U. S. A.**

## Woodhouse Special Dredge



**For Steam Shovels, Cranes,  
Dredges, Slings.**

**POSITIVELY THE BEST ON THE MARKET**

*Write for testimonial and prices.*


We also manufacture chain for  
Ship Cables



**Woodhouse Chain Works  
TRENTON, N. J.**

## TRUSCOTT

**THE DEPENDABLE MARINE MOTOR**



Made to withstand the most severe and continuous service. A practical design characterized by the accessibility, compactness and simple ignition, gas producing and oiling features. Perfect control.

Four cycle type two and four cylinders, from 8 to 65 H.P. Smaller sizes of the two cycle type.

Catalogue and copy of The Launch for the asking.

Department 46.


**Truscott Boat Mfg. Co.  
ST. JOSEPH, MICHIGAN.**



CLYDE LINE APACHE



U.S. BATTLESHIP MAINE




THE  
WM.  
**CRAMP**  
— & SONS —  
**SHIP & ENGINE BUILDING Co.**  
ESTABLISHED 1830

**I.P. MORRIS COMPANY**  
(ESTABLISHED 1829)

**KENSINGTON SHIPYARD Co**

**WARSHIPS AND MERCHANT STEAMERS**  
Pumping, Blowing and Hoisting Engines, Dry Docks  
Vertical and Horizontal Turbines  
Centrifugal Pumping Machinery  
Marine Railway.  
Repairs to all classes  
of vessels

LARGE TURBINE



**Philadelphia**

VIEW OF ONE OF OUR DRY DOCKS





**CLEAN BOILERS**

**Dearborn Water Treatment** made to suit the case. Takes off the scale, keeps it off, stops corrosion and foaming. Send gallon of water for analysis.

**DEARBORN DRUG & CHEMICAL WORKS**

**G. R. CARR,**  
Mgr. Marine Dept.

16 BRANCH OFFICES IN THE U. S.

**227-234 Postal Telegraph Bldg., CHICAGO.**

**KIESLER AUTOMATIC BUCKETS**


Orange Peel  
Open

**Orange Peel and Clam Shell Types**  
for handling Coal, Iron Ore and Excavating

We guarantee our Orange Peel to always fill in large lump Soft Coal and Iron Ore. Has two flat lips and will not damage boats or cars. Are from 30 to 50% lighter than any other buckets. Digging ability due to powerful system of leverage.

*Write for Catalogue and Prices.*

**MAYO & BAILEY** 1548 1st Nat'l Bank Bldg.  
CHICAGO



Orange Peel Closed  
showing load

**THE STANLEY B. SMITH COAL AND DOCK CO.,**  
TOLEDO HARBOR, TOLEDO, OHIO.

1,800 Feet of Dock.

6 McMyler Derricks.

Capacity 8,000 Tons Daily.

**Fuel Lighters.** —"KANAWHA."  
—"PENNSYLVANIA."  
—"HOCKING."

**Docks.** —PENNSYLVANIA R. R.  
—HOCKING VALLEY R. R.  
—TOLEDO AND OHIO CENTRAL R. R.

**SMITH'S COAL DOCK, Detroit River, DETROIT, MICH.**

12 Pockets.

Platform.

Low Dock.

Operated by STANLEY B. SMITH & CO.

MARINE SUPPLY COMPANY—STORE AND ICE HOUSE ON DOCK.

**PITTSBURG COAL COMPANY**

GENERAL OFFICE, LAKE DEPARTMENT, PERRY-PAYNE BUILDING, CLEVELAND, OHIO

**Steamboat Fueling Facilities at Various Points on the Great Lakes**

CLEVELAND HARBOR { 4 Car Dumpers.  
3 Lighters.

FAIRPORT HARBOR { 1 Car Dumper.  
1 Lighter.

ERIE HARBOR { 1 Car Dumper.  
Fuel Pockets.

ASHTABULA HARBOR { 1 Car Dumper.  
1 Lighter.

DETROIT RIVER BRANCH { Docks and Pockets at  
Sandwich and Amherstburg.

SAULT RIVER BRANCHES { Dock and Pockets at Detour.  
Dock and Pockets at Sault Ste. Marie. (The Port Royal Dock Co.)


—WE FURNISH ONLY THE BEST GRADE OF—

**PITTSBURG AND YOUGHIOGHENY COAL**

# MARYLAND STEEL COMPANY

BUILDERS OF STEEL STEAMSHIPS,  
TOW BOATS, SAILING VESSELS,  
BARGES AND STEAM CRAFT  
OF EVERY DESCRIPTION

STEEL FLOATING DRY DOCKS  
CAPABLE OF DOCKING  
THE LARGEST VESSELS




FLOATING DRY DOCK BUILT BY US FOR UNITED STATES GOVERNMENT

SPARROW'S POINT,  
MARYLAND.



# Hyde Windlasses and Capstans



Steamship Minnesota equipped with Hyde Windlass and Capstans.

Selected for the Minnesota and Dakota of the Great Northern Steamship Co.'s fleet—the largest vessels ever built in the United States. They are also being installed on nearly all of the vessels now building for the Navy Department, Revenue Cutter service, Lighthouse Board and the United States Coast Survey.

*Reason—Their Superiority*

*Send for Illustrated Catalog.*

**HYDE WINDLASS COMPANY**

BATH, MAINE

## "Wiltbonco" Steam Plant Accessories

Awarded Gold Medal at Universal  
Exposition, St. Louis, 1904.

### REFLEX WATER GAUGES AND WILTBONCO GAUGE MOUNTINGS

Used by all the principal Navies of the world, Merchant Marine, and for Locomotives, Automobiles, Stationary and Portable Boilers.

**"THE WATER SHOWS BLACK"**  
**ESPECIALLY ADAPTED FOR HIGH PRESSURE.**


**CUSHION PRESSURE SEATED CONTROL COCKS** For all liquids and gases.

**"FREEPORT" VALVES** For all purposes, but particularly designed for high pressures and superheated steam.

**"SAFETY" PLASTIC METALLIC PACKING,**

**COOPERITE SHEET PACKING,** For high pressures and superheated steam, acids, ammonia, etc.

**WILTBONCO-HOGAN OIL FILTERS.**



## The Wm. T. Bonner Co.

MERCHANT ENGINEERS, AND MANUFACTURERS

Head Office, 246 Summer St., Boston. New York Sales Office, 141 Broadway



Modern Highway and Electric Railway Scherzer Rolling Lift Bridge open for the passage of large vessel. Superseded and replaced a center pier swing bridge.

## More than **60 SCHERZER ROLLING LIFT BRIDGES**

have already been built, superseding and replacing swing bridges and other old types of movable bridges for railroads, electric railways and highways in the most progressive cities and harbors of the world.

### **HIGHEST AWARD**


**World's Fair, St. Louis, 1904**

"Center pier swing bridges form **artificial obstructions**, blocking **navigation** and **commerce**. They are condemned, removed and replaced by modern **SCHERZER ROLLING LIFT BRIDGES** wherever **Manufacturing, Commerce, Transportation, Railroads** and **Ships** are valued, protected and advanced."

*Write us for photographs, information, sketches and estimates*

### **THE SCHERZER ROLLING LIFT BRIDGE COMPANY**

**Main Offices: Monadnock Block, Chicago, U. S. A.**



Modern Railroad Scherzer Rolling Lift Bridge in the open position. Longest span Basc le Bridge in the world. Also Highway Scherzer Rolling Lift Bridge open further down the river.



## **RALPH M. PARSONS** **SHIP ENGINEER & BUILDER**

Ship yard and offices, 24 Lawrence Street, CHICAGO

## **Light Draught Stern Paddle-Wheel Craft**

**A Specialty**

*Steam or Gasoline*

## **Boats of all Classes**


**for**

**Sectional or  
"Knock Down"  
Shipment**





Northern Pacific Railway, Tacoma, Wash. Coal is taken from Bunkers shown at left by Link-Belt Carriers, and delivered into Carrier at right angles running out to sea. This latter Conveyor is carried by hinged Truss. Normal capacity 700 tons per hour.



Northern Pacific Railway Co., Tacoma, Wash.  
Loading 700 Tons per Hour

Philadelphia

The Link Belt Engineering Co.

# Ship Loading Plants

## We Design and Build

Complete equipments for transporting material of all kinds from cars to vessels or vessels to cars with or without intermediate storage. We have equipped many of the largest transportation companies in the world with machinery of this character whereby the space occupied and the time and labor otherwise consumed in loading and unloading vessels has been greatly reduced. We will submit plans and estimates on request.

## We also Design and Install

Machinery of the highest efficiency for HANDLING MISCELLANEOUS FREIGHT in Steamship Docks and Warehouses.

**The Link-Belt Machinery Co.**  
Engineers, Founders, Machinists. **CHICAGO**

The MIETZ & WEISS

Two Cycle

## OIL ENGINES

Constant Thrust

—Operated by—


**Kerosene Oil, Fuel Oil, Distillate or Crude Oil.**

**Simplest, Safest, most Reliable and most Economical Engines on the market.**

### MARINE TYPE.

No Valves, Cams or Gears.  
No Electric Sparking Devices.  
Automatic Ignition by Compression.


No Dangerous Gasolene used.



1 to 60 horse power.

### STATIONARY TYPE.

Especially adapted for operating electric generators for lighting launches, yachts and house boats. Perfect regulation, greatest economy and absolute safety.



1 to 75 horse power.


SEND FOR CATALOG,  
DEPT. 102.

## AUGUST MIETZ,

Iron Foundry and Machine Works,

128-138 Mott Street

NEW YORK, U.S.A.



Adjustable Bevel Band Saw—Will bevel both ways at 45 degrees. Power Movement to change angles. Power feed in three directions.

Established 1869.

Incorporated 1896.

## Atlantic Works Incorporated

Successors to Berry &amp; Orton Company,

Manufacturers of

### MACHINERY FOR WORKING WOOD ALSO BAND SAW BLADES

For use in Ship Yards, Car Shops, Railroad Shops.

HOLLOW CHISEL MORTISERS.


CAR SILL DRESSERS.

Estimates Furnished—Send for Catalogue.

2870-72-74-76-78 Gray's Ferry Road, PHILADELPHIA, PA.

## GREACEN-DERBY ENGINEERING COMPANY

Engineers and Contractors



Manufacturers of the BLACKBURN-SMITH PATENT

### REFLEX FILTERS

for extracting Oil, Grease, Air, Mud, Sand, or any Foreign Mechanical Matter from BOILER FEED WATER

Guaranteed indisputable merits over any other Filter on the market, viz.: Effective surface per Boiler Horse-Power. Weight per H.P. Rating. Efficiency due to double filtration.

ACCESSIBILITY — PRICE — COMPACTNESS — SIMPLICITY  
DURABILITY — TERMS

PERTH AMBOY, N. J.

## SAFETY FIRE BUCKET TANK



An airtight Tank, containing a supply of chemical solution and Six Fire Buckets with self-raising handles.

THIS SOLUTION

REQUIRES NO  
ATTENTION—  
WILL NOT  
EVAPORATE—  
FOUL—FREEZE

Always Ready for Use

Now in use by  
Hamburg-American Line—  
International Navigation Co.  
North German Lloyd Co.Ferry Boats of  
Penn. R. R. S. I. R. T. Co.  
Erie R. R. D. L. & W. R. R.  
C. R. R. of N. J. N. Y. C. & H. R. R. R.

Write for Booklet

Safety Fire Extinguisher Co.

SPALDING BUILDING

29-31-33 West 42d Street

NEW YORK



No. 70.

## CRANE - NAVY VALVES

UNION BONNET

GLOBE, ANGLE, CROSS AND CHECK

REGRINDING

FOR 175 LBS STEAM PRESSURE TESTED TO 250 LBS. HYDRAULIC. CAN BE REGROUND WITHOUT DETACHING FROM PIPE. MAY BE PACKED WHILE VALVE IS OPEN AND PRESSURE ON. ARE EXTENSIVELY USED ON STEAM VESSELS WHERE A PERFECTLY RELIABLE VALVE IS REQUIRED.

NEW YORK  
PHILADELPHIA  
BALTIMORE  
CINCINNATI  
ST. LOUIS  
KANSAS CITY  
SIOUX CITY  
ST. PAUL  
DULUTH  
OMAHA

WRITE FOR COMPLETE POCKET CATALOGUE

CRANE CO.

CHICAGO

ESTABLISHED 1855

MINNEAPOLIS  
SALT LAKE CITY  
SAN FRANCISCO  
LOS ANGELES  
PORTLAND, ORE.  
BIRMINGHAM  
SEATTLE  
SPOKANE  
MEMPHIS  
DALLAS

## THE NICLAUSSE BOILER.

The largest merchantmen in the world, the S. S. Minnesota and Dakota, of 33,000 tons and 11,000 H. P. each, are equipped with Niclausse Boilers.

**641,000 HORSE POWER IN THE NAVIES OF ELEVEN NATIONS.**

THE NEW JAPANESE CRUISERS, KATORI AND KASHIMA, OF 16,000 H. P. EACH, AND IN THE UNITED STATES NAVY THE ARMORED CRUISERS PENNSYLVANIA AND COLORADO, 23,000 H. P. EACH, AND THE BATTLESHIPS GEORGIA AND VIRGINIA, 19,000 H. P. EACH, WILL BE FITTED WITH THESE BOILERS.

**THE ONLY WATER-TUBE BOILER SUCCESSFULLY USED AND PROVED IN LARGE SHIPS.**

Requires no space at sides or rear—cleaned from the front.

Employs no tube-caps—tubes can readily be withdrawn without mutilation.

**FORGED STEEL THROUGHOUT.**

**THE STIRLING COMPANY, General Offices, Trinity Building, NEW YORK.**

## THE ROBERTS SAFETY WATER-TUBE BOILER CO.

Manufacturers of  
High Grade

### Marine Water Tube Boilers

Generators of the Highest Quality of Steam

NEARLY 1500 IN USE

Send for circulars  
and stock sheet

MAIN OFFICE


39 Cortlandt St. New York City

Phone 599 Cortlandt

Works: Red Bank, N. J.  
Phone, 49 Red Bank

Cable Address  
"Bruniva"

## LUNKENHEIMER MONITOR WATER GAUGE



*Provided with Automatic Closing  
Check Valves, which will  
positively seat should  
Gauge Glass breaks.*

*Positively the most Reliable,  
Durable and Practical  
Water Gauge on  
the Market.*

*Quick Closing,  
Regrinding  
Valves.*

IF YOUR LOCAL DEALER CANNOT  
FURNISH THEM, NOTIFY US.

### The Lunkenheim Company

Largest Manufacturers of Engineering  
Specialties in the world.

GENERAL OFFICES AND WORKS Cincinnati, Ohio, U. S. A.

BRANCHES New York—26 Cortlandt St.  
London, S. E.—35 Great Dover St.


We manufacture a complete line of Brass and Iron Valves, Lubricators, Oil and  
Grease Cups, Generator Valves, Whistles, Injectors, Etc. 2 M. R.



### GASOLINE MARINE ENGINES

Suitable for all Boats from 3½ to 200 HP.  
Over 100 in successful use.


Also the well known and always  
reliable Woolters Gas or Gasoline  
Stationary Engines.



### HOISTING ENGINES

Of all kinds and sizes, and  
for all purposes, especially  
for ship use.

Docking and Hauling Engines  
and Wire Rope Windlasses.



### AUTOMATIC TOWING MACHINES

Somewhat the cheapest, and  
altogether the best. Positively  
guaranteed.

Automatic Fog Whistle Machines  
Steam Steering Engines.

FOR THESE AND OTHER WELL KNOWN SPECIALTIES ADDRESS ALL INQUIRIES TO.

**THE CHASE MACHINE CO. Engineers and Machinists, CLEVELAND, OHIO.**



# New York Shipbuilding Company

Main office and works, Camden, N. J., New York office No. 1 Broadway

**Builders of**  
**SHIPS — ENGINES — BOILERS**  
**HEAVY MACHINERY**



Launch of "Mongolia," Pacific Mail S. S. Co., July 25, 1903.  
615 feet long, 65 feet beam, 51 feet deep.

## Best Facilities for Repair Work

**Pneumatic and Electric Tools;  
ample wharfage accomodation.**

**100 ton crane.**

**Repairs done under shelter.**




# Arbecam's Alidade

## Adjustable Compass Deviation Corrector

**POSITION AND DISTANCE FINDER**

*"Should be on every ship worth insuring."*



*An entirely new instrument. Simple, Effective, Durable. Readily attached to any binnacle. Designed to instantly correct any deviation without computation. Takes bearings, cross bearings, etc., directly from the compass without possibility of error. It is unaffected by vibration, rolling or pitching. Adjusts itself to every motion of the vessel. Endorsed by highest naval and merchant marine officials.*


*"A modern necessity on board ship."*

Pat. May 23d, 1905.  
Other Patents Pending in U. S. and Abroad.

### BENJAMIN VARNUM HOW

General Agent

**BOSTON - MASS.**



**CAPACITY** of production, durability and fuel economy are the three distinguishing points of superiority which predominate


## DEARING WATER-TUBE BOILERS

For further information

**Dearing Water-Tube Boiler Co.**

Dept. C.

DETROIT, MICH.



## RAILWAY DRY DOCKS

STEEL AND TIMBER  
CONSTRUCTION

**Safe, Rapid, Convenient,  
Reliable, Economical**

**H. I. Crandall & Son Co.**

Engineers and Contractors

East Boston

Mass.


# GREAT LAKES ENGINEERING WORKS

**DETROIT, MICH.**

ANTONIO C. PESSANÒ, President and Gen. Mgr.

GEORGE H. RUSSEL,  
Vice President.

JOHN R. RUSSEL,  
Secretary and Treasurer.



**Designers and Builders of  
Steel Freight and Passenger Ships.  
Marine Engines. = Hydraulic Dredges.**



ICE CRUSHING CAR FERRY "DETROIT."

**Marine Repairs a Specialty.**

# BELLEVILLE WATER-TUBE BOILERS

**NOW IN USE (MARCH, 1905)**

**On Board Sea-going Vessels, NOT INCLUDING New Installations Building or Erecting.**

French Navy	-	-	-	-	-	-	-	360,560 H. P.
English Royal Navy	-	-	-	-	-	-	-	966,300 "
Russian Imperial Navy	-	-	-	-	-	-	-	253,800 "
Japanese Imperial Navy	-	-	-	-	-	-	-	122,700 "
Austrian Imperial Navy	-	-	-	-	-	-	-	56,700 "
Italian Royal Navy	-	-	-	-	-	-	-	32,500 "
Chilian Navy	-	-	-	-	-	-	-	26,500 "
Argentine Navy	-	-	-	-	-	-	-	13,000 "
The "Messageries Maritimes" Company	-	-	-	-	-	-	-	87,600 "
Chemins de fer de l'Ouest: (The French Western Railway Co.)	-	-	-	-	-	-	-	Steamships
plying between Dieppe and Newhaven	-	-	-	-	-	-	-	18,500 "
Compagnie Generale Transatlantique	-	-	-	-	-	-	-	1,500 "
<b>Total Horse Power of Boilers in Use</b>								<b>1,939,660</b>

## Société Anonyme des Etablissements Delaunay Belleville

CAPITAL: 8,000,000 FRANCS

Works and Dock Yards of the Ermitage at Saint-Denis (Seine), France.

Telegraphic Address: Belleville, Saint-Denis-Sur-Seine

### Geo. L. McCurdy

169 Jackson Boulevard

CHICAGO ILLINOIS

### INSURANCE

HULLS and CARGOES


DIRECT REPRESENTATIVE OF LEADING  
AMERICAN AND FOREIGN UNDERWRITERS

#### TUBES

For shipment immediately on receipt of order we have in stock a complete assortment of Boiler Tubes, 2" to 5" inclusive — various lengths.

See monthly stocklist.

THE  
BOURNE-FULLER CO.  
IRON STEEL  
PIG IRON  
COKE  
Cleveland, Ohio.



#### ASHTON

Cam Lever Pop Safety Valves  
and Non-Corrosive  
Steam Gauges.

give highest efficiency and durability.  
Specify them and get the best.

The Ashton Valve Co.

Boston New York Chicago  
U. S. A.

# Buyers' Directory of the Marine Trade

For a more complete classification than that represented by advertisers in the Marine Review, see the BLUE BOOK OF AMERICAN SHIPPING, marine and naval directory of the United States, published by The Marine Review, Cleveland.

See accompanying index of Advertisers for full addresses of concerns in this directory.

**AIR COMPRESSORS, AIR HOISTS, ETC.**  
Great Lakes Engineering Works.....Detroit.  
Mietz, Aug. ....New York.

**AIR PORTS, DEAD LIGHTS, ETC.**  
Marine Mfg. & Supply Co.....New York.

**AIR PUMPS AND APPLIANCES.**  
Fore River Ship & Engine Co., Quincy, Mass.  
Great Lakes Engineering Works.....Detroit.

**ANCHORS.**  
Bowers, L. M. & Co.....Binghamton, N. Y.

**ANTI-FRICTION METALS.**  
Cramp, Wm. & Sons.....Philadelphia.

**ARTIFICIAL DRAFT FOR BOILERS.**  
American Ship Building Co.....Cleveland.  
Detroit Ship Building Co.....Detroit.  
Great Lakes Engineering Works.....Detroit.  
Sturtevant, B. F., Co.....Hyde Park, Mass.

**ASH EJECTORS.**  
Great Lakes Engineering Works.....Detroit.

**ATTORNEYS AND PROCTORS IN ADMIRALTY.**

Gilchrist, Albert J.....Cleveland.  
Goulding, Holding & Masten.....Cleveland.  
Hoyt, Dustin & Kelley.....Cleveland.  
Jenkins, Russell & Eichelberger.....Cleveland.  
Kremer, C. E.....Chicago.  
MacDonald, Ray G.....Chicago.  
Shaw, Warren, Cady & Oakes.....Detroit.  
White, Johnson, McCaslin & Cannon Cleveland

**BAROMETERS, MARINE GLASSES, ETC.**  
Ritchie, E. S. & Sons.....Brookline, Mass.

**BELT CONVEYORS.**  
Link Belt Machinery Co.....Chicago.

**BLOCKS, SHEAVES, ETC.**  
Boston & Lockport Block Co.....Boston, Mass.  
Cleveland Block Co.....Cleveland.

**BLOWERS.**  
Power Specialty Co.....Detroit.  
Sturtevant, B. F. Co.....Hyde Park, Mass.

**BOAT BUILDERS.**  
Drein, Thos. & Son.....Wilmington, Del.  
Kahnweiler's Sons, David.....New York.  
Lane & DeGroot.....Long Island City, N. Y.  
Marine Construction & D. D. Co.....  
.....Mariner's Harbor, S. I., N. Y.  
Truscott Boat Mfg. Co.....St. Joseph, Mich.  
Willard, Chas. P. & Co. Winthrop Harbor, Ill.

**BOILER CLEANING DEVICE.**  
Power Specialty Co.....Detroit.

**BOILER COMPOUNDS.**  
Dearborn Drug & Chemical Works....Chicago.

**BOILER MANUFACTURERS.**  
Almy Water Tube Boiler Co., Providence, R. I.  
American Ship Building Co.....Cleveland.  
Atlantic Works.....East Boston, Mass.  
Chicago Ship Building Co.....Chicago.  
Cramp, Wm. & Sons.....Philadelphia.  
Dearing Water Tube Boiler Co.....Detroit.  
Delaunay, Belleville & Co., St. Denis, France.  
Detroit Ship Building Co.....Detroit.  
East End Boiler Works.....Detroit.  
Fletcher, W. A. & Co.....Hoboken, N. J.  
Fore River Shipbuilding Co.....Quincy, Mass.  
Great Lakes Engineering Works.....Detroit.  
Kingsford Foundry & Machine Works.....  
.....Oswego, N. Y.  
Marine Iron Works.....Chicago.  
Maryland Steel Co.....Sparrows Point, Md.  
Milwaukee Dry Dock Co.....Milwaukee.  
Mosher Water Tube Boiler Co.....New York.  
Newport News Ship Building Co.....  
.....Newport News, Va.

**BOILER MANUFACTURERS—Continued.**  
New York Shipbuilding Co.....Camden, N. J.  
Northwestern Steam Boiler & Mfg. Co.....  
.....Duluth, Minn.  
Quintard Iron Works Co.....New York.  
Roberts Safety Water Tube Boiler Co.....  
.....New York.  
Stirling, The Co.....New York.  
Superior Ship Building Co.....Superior, Wis.  
Taylor Water Tube Boiler Co.....Detroit.

**BOILER RIVETS.**  
Bourne-Fuller Co.....Cleveland.

**BOILER STAYBOLTS, IRON OR STEEL, HOLLOW OR SOLID.**  
Falls Hollow Staybolt Co., Cuyahoga Falls, O.

**BRASS AND BRONZE CASTINGS.**  
Cramp, Wm. & Sons.....Philadelphia.  
Fore River Ship & Engine Co., Quincy, Mass.  
Great Lakes Engineering Works.....Detroit.  
Lunkenheimer Co.....Cincinnati.  
Macbeth Iron Co.....Cleveland.

**BRIDGES, BUILDERS OF.**  
Cowing, John P.....Cleveland.  
Scherzer Rolling Lift Bridge Co.....Chicago.

**BUCKETS, ORE AND COAL.**  
Brown Hoisting & Conveying Machine Co.....  
.....Cleveland.  
McMyler Mfg. Co.....Cleveland.  
Mayo & Bailey .....Chicago.

**BULKHEAD DOORS, WATERTIGHT.**  
"Long Arm" System Co.....Cleveland.

**CABIN AND CABINET FINISHING WOODS.**  
Martin-Barriss Co.....Cleveland.

**CANVAS SPECIALTIES.**  
Baker & Co., H. H.....Buffalo.  
Bunker, E. A.....New York.  
Upson-Walton Co.....Cleveland.

**CAPSTANS.**  
American Ship Windlass Co., Providence, R. I.  
Hyde Windlass Co.....Bath, Me.  
Marine Mfg. & Supply Co.....New York.

**CEMENT, IRON FOR REPAIRING LEAKS.**  
Smooth-On Mfg. Co.....Jersey City, N. J.

**CHAINS.**  
Woodhouse Chain Works.....Trenton, N. J.

**CHAIN CONVEYORS, HOISTS.**  
Brown Hoisting Machinery Co. (Inc.).....  
.....Cleveland.  
General Electric Co.....Schenectady, N. Y.

**CHAIN HOISTS.**  
Boston & Lockport Block Co.....Boston, Mass.

**CHARTS.**  
Penton Publishing Co.....Cleveland.  
Potter, J. D.....London.

**CLOCKS (Marine and Ship's Bell) AND CHRONOMETERS.**  
Ashton Valve Co.....Boston.  
Ritchie, E. S. & Sons.....Brookline, Mass.

**COAL PRODUCERS AND SHIPPERS.**  
Hanna, M. A. & Co.....Cleveland.  
Ironville Dock & Coal Co.....Toledo, O.  
Pickands, Mather & Co.....Cleveland.  
Pittsburg Coal Co.....Cleveland.

**COAL AND ORE HANDLING MACHINERY.**  
Brown Hoisting Machinery Co. (Inc.).....  
.....Cleveland.  
Link Belt Machinery Co.....Chicago.  
McMyler Mfg. Co.....Cleveland.

**COMPASSES.**  
Ritchie, E. S. & Sons.....Brookline, Mass.

**COMPASS CORRECTORS.**  
How, Benj. V.....Boston.

**CONDENSERS.**  
Great Lakes Engineering Works.....Detroit.  
Thropp & Sons Co., John E., Trenton, N. J.

**CONTRACTORS FOR PUBLIC WORKS.**  
Breyman & Bros., G. H.....Toledo.  
Buffalo Dredging Co.....Buffalo.  
Dunbar & Sullivan Dredging Co.....Buffalo.  
Fitz-Simons & Connell Co.....Chicago.  
Great Lakes Dredge & Dock Co.....Chicago.  
Hickler Bros.....Sault Ste. Marie, Mich.  
Hubbell Co., H. W.....Saginaw, Mich.  
Lake Superior Contracting & Dredging Co.,  
.....Duluth, Minn.  
Smith Co., L. P. & J. A.....Cleveland.  
Starke Dredge & Dock Co., C. H., Milwaukee.  
Sullivan, M.....Detroit.

**CORDAGE.**  
Baker & Co., H. H.....Buffalo.  
Upson-Walton Co.....Cleveland.

**CORK JACKETS AND RINGS.**  
Armstrong Cork Co.....Pittsburg, Pa.  
Kahnweiler's Sons, D.....New York.

**CRANES, TRAVELING.**  
Brown Hoisting Machinery Co.....Cleveland.  
McMyler Mfg. Co.....Cleveland.

**DIVING APPARATUS.**  
Morse, A. J. & Son.....Boston.  
Schrader's Son, Inc., A.....New York.

**DRAFT, MECHANICAL.**  
Sturtevant Co., B. F.....Hyde Park, Mass.

**DREDGING CONTRACTORS.**  
Breyman & Bros., G. H.....Toledo.  
Buffalo Dredging Co.....Buffalo.  
Dunbar & Sullivan Dredging Co.....Buffalo.  
Fitz-Simons & Connell Co.....Chicago.  
Great Lakes Dredge & Dock Co.....Chicago.  
Hickler Bros.....Sault Ste. Marie, Mich.  
Hubbell Co., H. W.....Saginaw, Mich.  
Lake Superior Contracting & Dredging Co.,  
.....Duluth, Minn.  
Smith Co., L. P. & J. A.....Cleveland.  
Starke Dredge & Dock Co., C. H., Milwaukee.  
Sullivan, M.....Detroit.

**DREDGING MACHINERY.**  
Quintard Iron Works Co.....New York.

**DRYING APPARATUS.**  
Sturtevant, B. F. Co.....Hyde Park, Mass.

**DRY DOCKS.**  
American Ship Building Co.....Cleveland.  
Atlantic Works.....East Boston, Mass.  
Buffalo Dry Dock Co.....Buffalo.  
Chicago Ship Building Co.....Chicago.  
Craig Ship Building Co.....Toledo, O.  
Cramp, Wm. & Sons.....Philadelphia.  
Detroit Ship Building Co.....Detroit.  
Great Lakes Engineering Works.....Detroit.  
Lockwood Mfg. Co.....East Boston, Mass.  
Milwaukee Dry Dock Co.....Milwaukee.  
Newport News Ship Building Co.....  
.....Newport News, Va.  
Shipowners Dry Dock Co.....Chicago.  
Superior Ship Building Co.....Superior, Wis.  
Tietjen & Lang Dry Dock Co.....Hoboken, N. J.

**DREDGE BUILDERS.**  
Manitowoc Dry Dock Co.....Manitowoc, Wis.

**DYNAMOS.**  
General Electric Co.....Schenectady, N. Y.  
Mietz, Aug.....New York.  
Sturtevant, B. F. & Co.....Hyde Park, Mass.  
Thropp & Sons, John E.....Trenton, N. J.

**ECONOMIZERS, FUEL.**  
Sturtevant Co., B. F.....Hyde Park, Mass.

**ELECTRIC HOISTS AND CRANES.**  
General Electric Co.....Schenectady, N. Y.



# WANTED and FOR SALE Department.

## PROPOSALS.

U. S. ENGINEER OFFICE, Duluth, Minn., Aug. 19, 1905. Sealed proposals for U. S. Engineer Building at Duluth, Minn., will be received here until noon, Sept. 18, 1905, and then publicly opened. Information on application. CHAS. L. POTTER, Major Engrs. Sept. 14.

U. S. ENGINEER OFFICE, 57 Park St., Grand Rapids, Mich., Aug. 21, 1905. Sealed proposals for repair of Pier and Revetments at Charlevoix, Mich., will be received here until 3 p.m., Sept. 20, 1905, and then publicly opened. Information furnished on application. M. B. ADAMS, Col. Engrs. Sept. 14.

SEALED PROPOSALS will be received at the office of the Light-House Board, Washington, D. C., until 2 o'clock p. m., Sept. 14, 1905, and then opened, for furnishing the materials and labor of all kinds necessary for the construction and delivery of the twin-screw steel steam light-house tender Sunflower, in accordance with specifications, copies of which, with blank proposals and other information, may be had upon application to REAR ADMIRAL B. P. LAMBERTON, U. S. N., Chairman.

U. S. ENGINEER OFFICE, 57 Park St., Grand Rapids, Mich., Sept. 4, 1905. Sealed proposals for extension of Piers at Holland (Black Lake), Mich., will be received here until 3 p. m., October 4, 1905, and then publicly opened. Information furnished on application. M. B. ADAMS, Col. Engrs. Sept. 28.

## FOR SALE.

### For Sale.

Fore and aft Compound Marine Engine, size 6 x 12 x 6, and in perfect condition. Built by the Marine Iron Works, Chicago. Inquire of H. B. Larsen, Manistee, Mich.

## FOR SALE.

### Grab Bucket.

FOR SALE.—One "Hulett" two-rope clam-shell bucket. Slightly used. Address Box 82, Marine Review, Cleveland.

### Marine Boiler.

For Sale.—One 50 H. P. Scotch Marine Boiler, 10 ft. long, 78 in. diameter, 160 lbs. steam pressure. Manufactured by Ritter & Co., Buffalo, N. Y. In first-class shape. For particulars, write The Detroit Stove Works, Detroit, Mich. t. f.

## FOR SALE.

### GASOLINE DELIVERY BOAT "I-NO-U."

Hull 38½ ft. long and 8½ ft. beam. Built very heavy and in the best manner possible. Keel 5¼ in. x 10½ in. Frames 2 in. x 3 in. at bottom and 2 in x 2 in. at top.

Planked and ceiled with 1½ in oak. Lacy Bros. 15-H. P. engine. Throws a 34 in. two-bladed reversible wheel 300 revolutions per minute and runs 8½ miles per hour. Nicely modeled boat and handles well. This is her second season and she is nearly as good as new. Lowest cash price \$1,800. Photo on application, but she should be seen to be appreciated.

**THE HARDY & DISCHINGER CO.**  
Oils and Supplies,  
TOLEDO, - OHIO.

## FOR SALE.

### FOR SALE \$3500.00.

### The Steamer Gordon Campbell.

Burned on spar-deck, forward only—easy to cut down to lumber barge, to carry million feet. Machinery, boilers and hull untouched and in good condition. Boat in dry dock and thoroughly overhauled last summer. Can be seen in Chicago. Address Room 613, 59 Dearborn St., Chicago. t f

### Tug for Sale.


Tug Kate for sale cheap at one-third of her actual cost. Sixty-three ft. keel, 16 ft. beam, 7 ft. draught. Engine 16 x 18; A1 boiler. Easy on fuel. Has winch for hauling in tow line and closing rafts. Full equipment. Just laid up. Snap for some one. JOSEPH GANLEY, Agent, Sault Ste. Marie, Mich.

### McMyler Derricks.

Several second-hand whirley derricks for sale. Address Box 83, Marine Review, Cleveland.

### Steam Capstans.

Two steam capstans in perfect condition for sale. Installed but never used. Address Box 81, Marine Review, Cleveland.



## Ritchie Liquid Compass

The Standard Liquid Compass used exclusively by the U. S. Navy for over 35 years. Over 25,000 used in Merchant Service.

Made in all sizes and styles, from 2 to 12 inches diameter of card. All compasses made by us have our name printed below the North point or prominently upon the card. **None other are genuine.** Latest form with four or six needles, the best instrument for iron ships. For sale by ship chandlers and nautical instrument dealers. Catalogue free.

**E. S. RITCHIE & SONS, Brookline, Mass., U. S. A.**  
MANUFACTURERS OF NAUTICAL AND PHYSICAL APPARATUS.

## SAFETY AT SEA

in time of danger depends upon the closure of the ship's bulkhead doors. A long series of maritime disasters shows that this can only be accomplished by means of

### THE "LONG-ARM" SYSTEM

By this system, consisting of a central emergency station from which power doors and hatch-plates are unfailingly controlled, the electric motor does the work, leaving nothing to chance or individual initiative and bravery. Adopted after searching tests for use on 36 vessels of the United States Navy. Further information may be obtained from

The "Long-Arm" System Co., Cleveland, O.

## SHIPMATE RANGES



8 sizes, 11 styles

A range that does its work well.

If you have a poor range in your galley, you are quite as likely to get into a terrible stew yourself as you are to have a good stew for dinner.

With a Shipmate range you can "lay a true course" for good cooking. They are sold on the Lakes by

Bean, Schermerhorn & Co., 69 Main St., Buffalo,  
R. T. Mitchell, 64 Prospect St., Cleveland,  
The T. R. Rayl Co., 112-116 Woodward Ave., Detroit,  
J. B. Sperry, Port Huron  
Geo. B. Carpenter & Co., 202-208 So. Water St., Chicago,  
Lott, Burton & Co., 86 Lake St., Chicago,  
John Black, 81-170 92nd St., South Chicago.

MADE BY

THE STAMFORD FOUNDRY COMPANY, STAMFORD, CONN.

## Buyers' Directory of the Marine Trade.—Continued.

**ELECTRIC LIGHT AND POWER PLANTS.**

General Electric Co.....Schenectady, N. Y.  
Mietz, Aug. ....New York.  
Sturtevant, B. F. & Co.....Hyde Park, Mass.  
Thropp & Sons, John E.....Trenton, N. J.

**ENGINE BUILDERS, MARINE.**

American Ship Building Co.....Cleveland.  
Atlantic Works.....East Boston, Mass.  
Chicago Ship Building Co.....Chicago.  
Chase Machine Co.....Cleveland.  
Cramp, Wm. & Sons.....Philadelphia.  
Craig Ship Building Co.....Toledo, O.  
Detroit Ship Building Co.....Detroit.  
Fletcher, W. & A. Co.....Hoboken, N. J.  
Fore River Shipbuilding Co.....Quincy, Mass.  
Great Lakes Engineering Works.....Detroit, Mich.  
Hall Bros.....Philadelphia.  
Lockwood Mfg. Co.....East Boston, Mass.  
Marine Iron Works.....Chicago.  
Maryland Steel Co.....Sparrows Point, Md.  
Mietz, Aug. ....New York.  
Milwaukee Dry Dock Co.....Milwaukee.  
Mosher, Chas. D.....New York.  
Moulton Steering Engine Co.....New York.  
Newport News Ship Building Co.....Newport News, Va.  
New York Shipbuilding Co.....Camden, N. J.  
Northwestern Steam Boiler & Mfg. Co.....Duluth, Mich.  
Quintard Iron Works Co.....New York.  
Roach's Ship Yard.....Chester, Pa.  
Sheriffs Mfg. Co.....Milwaukee.  
Superior Ship Building Co.....Superior, Wis.  
Thropp, J. E. & Sons Co.....Trenton, N. J.  
Trout, H. G.....Buffalo.

**ENGINE BUILDERS, STEAM.**

Sturtevant Co., B. F.....Hyde Park, Mass.

**ENGINE ROOM TELEGRAPH, CALL BELLS, ETC.**

Cory, Chas. & Son.....New York.  
Marine Mfg. Supply Co.....New York.

**ENGINE TESTING.**

Parsons, Ralph M.....Chicago.

**ENGINEERING SPECIALTIES AND SUPPLIES.**

Crane Co.....Chicago.  
Kieley & Mueller.....New York.  
Lunkenheimer Co.....Cincinnati.  
Northwestern Steam Boiler & Mfg. Co.....Duluth, Minn.

**ENGINEERS, MARINE, MECHANICAL, CONSULTING.**

Hynd, Alexander.....Cleveland.  
Hunt, Robt. W. & Co.....Chicago.  
Kidd, Joseph.....Duluth, Minn.  
Mosher, Chas. D.....New York.  
Nacey, James.....Cleveland.  
Roelker, H. B.....New York.  
Wood, W. J.....Chicago.

**FANS FOR VENTILATION, EXHAUST, ETC.**

Sturtevant, B. F. Co.....Hyde Park, Mass.

**FEED WATER PURIFIERS AND HEATERS.**

Greacen-Derby Engineering Co.....Perth Amboy, N. J.  
Ross Valve Co.....Troy, N. Y.

**FIRE EXTINGUISHERS.**

Safety Fire Extinguisher Co.....New York.

**FIXTURES FOR LAMPS, OIL OR ELECTRIC.**

General Electric Co.....Schenectady, N. Y.

**FORGES.**

Sturtevant, B. F. Co.....Boston.  
Sutton Co., C. E.....Toledo, O.

**FORGINGS FOR CRANK, PROPELLER OR THRUST SHAFTS, ETC.**

Cleveland City Forge & Iron Co.....Cleveland.  
Fore River Shipbuilding Co.....Quincy, Mass.  
Macbeth Iron Co.....Cleveland.

**FLUE WELDING.**

Fix's, S. Sons.....Cleveland.

**FUEL ECONOMIZERS.**

Sturtevant Co., B. F.....Hyde Park, Mass.

**FUELING COMPANIES AND COAL DEALERS.**

Hanna, M. A. & Co.....Cleveland.  
Ironville Dock & Coal Co.....Toledo, O.  
Parker Bros. Co., Ltd.....Detroit.  
Pickands, Mather & Co.....Cleveland.  
Pittsburg Coal Co.....Cleveland.  
Smith, Stanley B. & Co.....Detroit.  
Smith Coal & Dock Co., Stanley B. Toledo, O.

**FUELING PLANTS, BUILDERS OF**

Link Belt Machinery Co.....Chicago.

**FURNACES FOR BOILERS.**

Continental Iron Works.....New York.

**GAS BUOYS.**

Safety Car Heating & Lighting Co.....New York.

**GAS AND GASOLINE ENGINES.**

Chase Machine Co.....Cleveland.

**GAUGES, STEAM AND VACUUM.**

Ashton Valve Co.....Boston.  
Lunkenheimer Co.....Cincinnati.

**GAUGES, WATER.**

Bonner Co., Wm. T.....Boston.  
Lunkenheimer Co.....Cincinnati, O.

**GENERATING SETS.**

Sturtevant Co., B. F.....Hyde Park, Mass.  
General Electric Co.....Schenectady, N. Y.

**GRAPHITE.**

Dixon Crucible Co., Joseph.....Jersey City, N. J.

**GREASE EXTRACTORS.**

Greacen-Derby Engineering Co.....Perth Amboy, N. J.

**HAMMERS, STEAM.**

Chase Machine Co.....Cleveland.

**HEATING APPARATUS.**

Sturtevant, B. F. Co.....Hyde Park, Mass.  
Sutton Co., C. E.....Toledo, O.

**HOISTS FOR CARGO, ETC.**

American Ship Building Co.....Cleveland.  
Brown Hoisting Machinery Co. (Inc.).....Cleveland.  
Chase Machine Co.....Cleveland.  
General Electric Co.....New York.  
Georgian Bay Engineering Works.....Midland, Ont.  
Hyde Windlass Co.....Bath, Me.  
McMyler Mfg. Co.....Cleveland.  
Marine Iron Co.....Bay City.  
Mietz, Aug. ....New York.

**HOLLOW SHAFTINGS, IRON OR STEEL.**

Falls Hollow Staybolt Co.....Cuyahoga Falls, O.

**HOLLOW STAYBOLT IRON.**

Falls Hollow Staybolt Co.....Cuyahoga Falls, O.

**HYDRAULIC DREDGES.**

Great Lakes Engineering Works.....Detroit.

**HYDRAULIC TOOLS.**

Watson-Stillman Co., The.....New York.

**ICE MACHINERY.**

Great Lakes Engineering Works.....Detroit.  
Roelker, H. B.....New York.

**INDICATORS FOR STEAM ENGINES.**

Ashton Valve Co.....Boston.

**INJECTORS.**

American Injector Co.....Detroit.  
Crane Co.....Chicago.  
Jenkins Bros.....New York.  
Lunkenheimer Co.....Cincinnati.  
Penberthy Injector Co.....Detroit, Mich.

**INSURANCE, MARINE.**

Elphicke, C. W. & Co.....Chicago.  
Fleming & Co., E. J.....Chicago.  
Gilchrist & Co., C. P.....Cleveland.  
Hawgood & Co., W. A.....Cleveland.  
Helm & Co., D. T.....Duluth.  
Hutchinson & Co.....Cleveland.  
McCarthy, T. R.....Montreal.  
McCurdy, Geo. L.....Chicago.  
Mitchell & Co.....Cleveland.  
Parker Bros. Co., Ltd.....Detroit.  
Peck, Chas. E. & W. F.....New York & Chicago.  
Prindiville & Co.....Chicago.  
Richardson, W. C.....Cleveland.  
Sullivan, D. & Co.....Chicago.

**IRON CASTINGS.**

Sutton Co., C. E.....Toledo, O.

**IRON ORE AND PIG IRON.**

Bourne-Fuller Co.....Cleveland, O.  
Hanna, M. A. & Co.....Cleveland.  
Pickands, Mather & Co.....Cleveland.

**LAUNCHES—STEAM, NAPHTHA, ELECTRIC.**

Marine Iron Works.....Chicago.  
Truscott Boat Mfg. Co.....St. Joseph, Mich.

**LIFE PRESERVERS, LIFE BOATS, BUOYS.**

Armstrong, Cork Co.....Pittsburg.  
Drein, Thos. & Son.....Wilmington, Del.  
Gaynor, T. F.....New York.  
Kahnweiler's Sons, D.....New York.  
National Cork Co.....Brooklyn.

**LIGHTS, SIDE AND SIGNAL.**

Russell & Watson.....Buffalo.

**LOGS.**

Nicholson Ship Log Co.....Cleveland.  
Walker & Sons, Thomas.....Birmingham, Eng.  
Also Ship Chandlers.

**LUBRICATING GRAPHITE.**

Dixon Crucible Co., Joseph.....Jersey City, N. J.

**LUBRICATORS.**

Crane Co.....Chicago.  
Lunkenheimer Co.....Cincinnati.

**LUMBER.**

Martin-Barriss Co.....Cleveland.  
Rayner, J. ....Chicago.

**MACHINISTS.**

Chase Machine Co.....Cleveland.  
Hickler Bros.....Sault Ste. Marie, Mich.  
Lockwood Mfg. Co.....East Boston, Mass.

**MACHINE TOOLS (WOOD WORKING).**

Atlantic Works, Inc.....Philadelphia.

**MARINE RAILWAYS.**

Hickler Bros.....Sault Ste. Marie, Mich.

**MARINE RAILWAYS, BUILDERS OF.**

Crandall & Son, H. I.....East Boston, Mass.

**MATTRESSES, CUSHIONS, BEDDING.**

Fogg, M. W.....New York.

**MECHANICAL DRAFT FOR BOILERS.**

American Ship Building Co.....Cleveland.  
Detroit Ship Building Co.....Detroit.  
Great Lakes Engineering Works.....Detroit.  
Sturtevant, B. F. Co.....Hyde Park, Mass.

**METALLIC PACKING.**

Katzenstein, L. & Co.....New York.

**MOTORS, GENERATORS—ELECTRIC**

General Electric Co.....Schenectady, N. Y.  
Sturtevant, B. F. Co.....Hyde Park, Mass.

**NAUTICAL INSTRUMENTS.**

Ritchie, E. S., & Sons.....Brookline, Mass.

**NAVAL ARCHITECTS.**

Hynd, Alexander.....Cleveland.  
Vidd, Joseph.....Duluth, Minn.  
Mosher, Chas. D.....New York.  
Nacey, James.....Cleveland.  
Wood, W. J.....Chicago.

**OAKUM.**

Stratford, Oakum Co.....Jersey City, N. J.

**OIL ENGINES.**

Mietz, Aug. ....New York.

**OILS AND LUBRICANTS.**

Dixon Crucible Co., Joseph.....Jersey City, N. J.  
Standard Oil Co.....Cleveland.

**PACKING.**

Crane Co.....Chicago.  
Jenkins Bros.....New York.  
Katzenstein, L. & Co.....New York.

**PAINTS.**

Baker, Howard H. & Co.....Buffalo.  
Upson-Walton Co.....Cleveland.

**PATTERN SHOP MACHINERY.**

Atlantic Works, Inc.....Philadelphia.



# Blue Book of American Shipping

AMERICA'S STANDARD  
MARINE DIRECTORY  
(Tenth Annual Edition)

It isn't a book of fiction but a valuable work of reference which should be in the hands of everybody interested in shipping affairs. Serviceably and attractively bound in cloth—five hundred pages 10 x 7 inches.

## A Few Index Headings.

1  
9  
0  
5

E  
D  
I  
T  
I  
O  
N

Boiler manufacturers of the world.  
Builders of ships, engines and boilers in various parts of the world.  
Canals and locks of St. Mary's river, particulars of.  
Cargo records of largest lake freighters.  
Coal, coke, iron, etc., production in United States.  
Coal movement of the Great Lakes.  
Gas and gasoline engine builders of the United States.  
Iron furnaces and steel works, lists of.  
Iron mines of Minnesota, map of.  
Iron mining companies, Lake Superior region, addresses of mines, owners, sales agents, etc.  
Iron mining industry, Lake Superior region.  
Iron mining ranges of Lake Superior, map of.  
Iron ore analyses.  
Iron ore carriers, capacities.  
Iron ore, output from Lake Superior by mines and ranges.  
Iron ore, receipts at Lake Erie docks and shipments to furnaces.  
Iron ore shipping docks, particulars of.  
Iron ore sales agents handling Lake Superior product.  
Pig iron production in the United States.  
Pig iron, world's production of.  
Steel and iron industrial statistics, miscellaneous.  
Steel and iron manufacturers of the United States.  
Steel rails and open hearth steel, production of.  
Steel works and furnaces, list of those using Lake Superior ores.

1  
9  
0  
5

E  
D  
I  
T  
I  
O  
N

*We will send you a complete table of contents free. Ask for it.*

**Price Five Dollars, Expressage Prepaid.**

**We should have your order now—the edition is limited**

**THE PENTON PUBLISHING CO.**  
**CLEVELAND**

## Buyers' Directory of the Marine Trade.—Continued.

**PILE DRIVING AND SUBMARINE WORK.**

Buffalo Dredging Co. .... Buffalo.  
 Dunbar & Sullivan Dredging Co. .... Buffalo.  
 Fitz-Simons & Connell Co. .... Chicago.  
 Great Lakes Dredge & Dock Co. .... Chicago.  
 Hickler Bros. .... Sault Ste. Marie, Mich.  
 Hubbell Co. H. W. .... Saginaw, Mich.  
 Lake Superior Contracting & Dredging Co. .... Duluth, Minn.  
 Parker Bros. Co., Ltd. .... Detroit.  
 Smith Co., L. P. & J. A. .... Cleveland.  
 Starke Dredge & Dock Co., C. H. .... Milwaukee.  
 Sullivan, M. .... Detroit

**PIPE, WROUGHT IRON.**

Bourne-Fuller Co. .... Cleveland, O.  
 Crane Co. .... Chicago.  
 Macbeth Iron Co. .... Cleveland.  
 Reading Iron Co. .... Reading, Pa.

**PLANING MILL MACHINERY.**

Atlantic Works, Inc. .... Philadelphia.

**PLATES—SHIP, STRUCTURAL, ETC.**

Bourne-Fuller Co. .... Cleveland, O.  
 Otis Steel Co. .... Cleveland.

**PRESSURE REGULATORS.**

Kieley & Mueller .... New York.  
 Ross Valve Co. .... Troy, N. Y.

**PROPELLER WHEELS.**

American Ship Building Co. .... Cleveland.  
 Atlantic Works. .... East Boston, Mass.  
 Cramp, Wm. & Sons. .... Philadelphia.  
 Detroit Ship Building Co. .... Detroit.  
 Fore River Shipbuilding Co. .... Quincy, Mass.  
 Great Lakes Engineering Works. .... Detroit.  
 Hyde Windlass Co. .... Bath, Me.  
 Lockwood Mfg. Co. .... East Boston, Mass.  
 Marine Iron Works. .... Chicago.  
 Milwaukee Dry Dock Co. .... Milwaukee.  
 Newport News Ship Building Co. .... Newport News, Va.  
 Roelker, H. B. .... New York.  
 Sheriffs Mfg. Co. .... Milwaukee.  
 Superior Ship Building Co. .... Superior, Wis.  
 Thropp & Sons Co., J. E. .... Trenton, N. J.  
 Trout, H. G. .... Buffalo.

**PROJECTORS, ELECTRIC.**

General Electric Co. .... Schenectady, N. Y.

**PUMPS FOR VARIOUS PURPOSES.**

Great Lakes Engineering Works. .... Detroit.  
 Marine Iron Works. .... Chicago.  
 Kingsford Foundry & Machine Works. .... Oswego, N. Y.

**PUNCHES AND SHEARS.**

Sutton Co., C. E. .... Toledo, O.

**RANGES.**

Stamford Foundry Co. .... Stamford, Conn.

**REFRIGERATING APPARATUS.**

Great Lakes Engineering Works. .... Detroit.  
 Roelker, H. B. .... New York.

**REGISTER FOR CLASSIFICATION OF VESSELS.**

Great Lakes Register. .... Cleveland.

**RIVETS, STEEL FOR SHIPS AND BOILERS.**

Bourne-Fuller Co. .... Cleveland, O.

**SAFETY VALVES.**

Ashton Valve Co. .... Boston.  
 Crane Co. .... Chicago.  
 Lunkenheimer Co. .... Cincinnati.

**SAIL MAKERS.**

Baker, Howard H. & Co. .... Buffalo.  
 Upson-Walton Co. .... Cleveland.

**SALVAGE COMPANIES.**

See Wrecking Companies.

**SEARCH LIGHTS.**

General Electric Co. .... Schenectady, N. Y.

**SHAFTING, HOLLOW.**

Falls Hollow Staybolt Co. .... Cuyahoga Falls, O.

**SHEARS.**

See Punches, and Shears.

**SHIP AND BOILER PLATES AND SHAPES.**

Bourne-Fuller Co. .... Cleveland, O.  
 Otis Steel Co. .... Cleveland.

**SHIP BUILDERS.**

American Ship Building Co. .... Cleveland.  
 Atlantic Works. .... East Boston, Mass.  
 Buffalo Dry Dock Co. .... Buffalo.  
 Cramp, Wm. & Sons. .... Philadelphia.  
 Craig Ship Building Co. .... Toledo, O.  
 Chicago Ship Building Co. .... Chicago.  
 Detroit Ship Building Co. .... Detroit.  
 Fore River Shipbuilding Co. .... Quincy, Mass.  
 Great Lakes Engineering Works. .... Detroit.  
 Lockwood Mfg. Co. .... East Boston, Mass.  
 Manitowoc Dry Dock Co. .... Manitowoc, Wis.  
 Maryland Steel Co. .... Sparrows Point, Md.  
 Milwaukee Dry Dock Co. .... Milwaukee.  
 Newport News Ship Building Co. .... Newport News, Va.  
 New York Shipbuilding Co. .... Camden, N. J.  
 Roach's Ship Yard. .... Chester, Pa.  
 Shipowner's Dry Dock Co. .... Chicago.  
 Smith & Son, Abram. .... Algonac, Mich.

**SHIP CHANDLERS.**

Baker, Howard H. & Co. .... Buffalo.  
 Marine Mfg. & Supply Co. .... New York.  
 Upson-Walton Co. .... Cleveland.

**SHIP DESIGNERS.**

Kidd, Joseph. .... Duluth.  
 Steel, Nacey & Hynd. .... Cleveland.  
 Wood, W. J. .... Chicago.

**SHIP LANTERNS AND LAMPS.**

Russell & Watson. .... Buffalo.

**SHIPMATE RANGES.**

Stamford Foundry Co. .... Stamford, Conn.

**SHIP TIMBER.**

Martin-Barriss Co. .... Cleveland.  
 Rayner, J. .... Chicago.

**SMOOTH-ON COMPOUND, FOR REPAIRS.**

Smooth-On Mfg. Co. .... Jersey City, N. J.

**STAYBOLT IRON OR STEEL BARS, HOLLOW OR SOLID.**

Falls Hollow Staybolt Co. .... Cuyahoga Falls, O.

**STEAM VESSELS FOR SALE.**

Gilchrist & Co., C. P. .... Cleveland.  
 Holmes, Samuel. .... New York.  
 Lester, S. S. .... Quebec, Can.  
 McCarthy, T. R. .... Montreal, Can.

**STEAMSHIP LINES, PASS. AND FREIGHT.**

American Line. .... New York.  
 Anchor Line. .... Buffalo.  
 Boston Steamship Co. .... Boston.  
 Cleveland & Buffalo Transit Co. .... Cleveland.  
 International Mercantile Marine Co. .... Philadelphia.  
 Mallory Line. .... New York.  
 Merchants' Montreal Line. .... Montreal.  
 New York & Cuba Mail S. S. Co. .... New York.  
 Red Star Line. .... New York.  
 United Fruit Co. .... Boston.

**STEEL CASTINGS.**

Otis Steel Co. .... Cleveland.  
 Sutton Co., C. E. .... Toledo, O.

**STEERING APPARATUS.**

American Ship Building Co. .... Cleveland.  
 Chase Machine Co. .... Cleveland.  
 Detroit Ship Building Co. .... Detroit.  
 Hyde Windlass Co. .... Bath, Me.  
 Marine Mfg. & Supply Co. .... New York.  
 Moulton Steering Engine Co. .... New York.  
 Sheriffs Mfg. Co. .... Milwaukee.

**SUBMARINE DIVING APPARATUS.**

Morse & Son, A. J. .... Boston.  
 Schrader's Son, Inc., A. .... New York.

**SURVEYORS, MARINE.**

Gaskin, Edward. .... Buffalo.  
 Hynd, Alexander. .... Cleveland.  
 Parker Bros. Co., Ltd. .... Detroit.  
 Nacey, James. .... Cleveland.  
 Steel, Adam. .... Cleveland.  
 Wood, W. J. .... Chicago.

**TESTS OF MATERIALS.**

Hunt, Robert W. & Co. .... Chicago.  
 Lunkenheimer Co. .... Cincinnati, O.

**TOOLS, METAL WORKING, FOR SHIP AND ENGINE WORKS.**

Watson-Stillman Co. .... New York.

**TOOLS, WOOD WORKING.**

Atlantic Works, Inc. .... Philadelphia.

**TOWING MACHINES.**

American Ship Windlass Co. .... Providence, R. I.  
 Chase Machine Co. .... Cleveland.

**TOWING COMPANIES.**

Donnelly Salvage & Wrecking Co. .... Kingston, Ont.  
 Great Lakes Towing Co. .... Cleveland.

**TRAPS, STEAM.**

Kieley & Mueller. .... New York.  
 Sturtevant Co., B. F. .... Hyde Park, Mass.

**TRUCKS.**

Boston & Lockport Block Co. .... Boston.

**TUBING, SEAMLESS.**

Shelby Steel Tube Co. .... Pittsburgh, Pa.

**VALVES, STEAM SPECIALTIES, ETC.**

Ashton Valve Co. .... Boston.  
 Crane Co. .... Chicago.  
 Jenkins Bros. .... New York.  
 Kieley & Mueller. .... New York.  
 Lunkenheimer Co. .... Cincinnati.  
 Ross Valve Co. .... Troy, N. Y.

**VALVES FOR WATER AND GAS.**

Lunkenheimer Co. .... Cincinnati.  
 Ross Valve Co. .... Troy, N. Y.

**VARNISHES.**

Detroit Varnish Co. .... Detroit.  
 Detroit White Lead Works. .... Detroit.  
 Also Ship Chandlers.

**VENTILATING APPARATUS FOR SHIPS.**

Sturtevant, B. F. Co. .... Hyde Park, Mass.  
 Sutton Co., C. E. .... Toledo, O.

**VESSEL AND FREIGHT AGENTS.**

Boland, John J. .... Buffalo.  
 Brown & Co. .... Buffalo.  
 Elphicke, C. W. & Co. .... Chicago.  
 Fleming & Co., E. J. .... Chicago.  
 Gilchrist & Co., C. P. .... Cleveland.  
 Hall, John B. .... Buffalo.  
 Helm & Co., D. T. .... Duluth.  
 Hawgood & Co., W. A. .... Cleveland.  
 Holmes, Samuel. .... New York.  
 Hutchinson & Co. .... Cleveland.  
 Lester, S. S. .... Quebec, Can.  
 McCarthy, T. R. .... Montreal.  
 Mitchell & Co. .... Cleveland.  
 Parker Bros. Co., Ltd. .... Detroit.  
 Prindiville & Co. .... Chicago.  
 Richardson, W. C. .... Cleveland.  
 Sullivan, D. & Co. .... Chicago.

**WATER GAUGES.**

Bonner Co., Wm. T. .... Boston.  
 Lunkenheimer Co. .... Cincinnati, O.

**WATERTIGHT BULKHEAD DOORS.**

"Long Arm" System Co. .... Cleveland.

**WHISTLES, STEAM.**

Ashton Valve Co. .... Boston.  
 Lunkenheimer Co. .... Cincinnati.

**WILFORD'S WATERPROOF CLOTH.**

Bunker, E. A. .... New York.

**WIRE ROPE AND WIRE ROPE FITTINGS.**

Baker, H. H. & Co. .... Buffalo.  
 DeGrauw, Aymar & Co. .... New York.  
 Upson-Walton Co. .... Cleveland.

**WINDLASSES.**

American Ship Windlass Co. .... Providence, R. I.  
 American Ship Building Co. .... Cleveland.  
 Hyde Windlass Co. .... Bath, Me.  
 Marine Mfg. & Supply Co. .... New York.

**WINCHES.**

American Ship Windlass Co. .... Providence, R. I.  
 Georgian Bay Engineering Works. .... Midland, Ont.  
 Hyde Windlass Co. .... Bath, Me.

**WOOD WORKING MACHINERY.**

Atlantic Works, Inc. .... Philadelphia.

**WOODS, FOREIGN.**

Rayner, J. .... Chicago.

**WRECKING AND SALVAGE COMPANIES.**

Donnelly Salvage & Wrecking Co. .... Kingston, Ont.  
 Great Lakes Towing Co. .... Cleveland.  
 Parker Bros. Co., Ltd. .... Detroit.

**YACHT AND BOAT BUILDERS.**


Drein, Thos. & Son. .... Wilmington, Del.  
 Manitowoc Dry Dock Co. .... Manitowoc, Wis.  
 Truscott Boat Mfg. Co. .... St. Joseph, Mich.

**YAWLS.**

Drein, Thos. & Son. .... Wilmington, Del.



### THE MOSHER PATENT WATERTUBE BOILER




Simplest, lightest most compact boiler made. Most accessible for cleaning and repair. Five vertical rows or as many as 45 tubes may be cleaned or withdrawn by removing the cover from a single hand hole. Largest grate surface on a given floor space. No joints in the fire. All joints expanded. Greater steam room and water capacity than any other boiler. Built in sizes up to 2000 H. P. Mosher Boilers have been supplied for eleven torpedo boats and the monitor Florida of the U. S. Navy, amounting to over 26,000 H. P., six torpedo boats for the Russian Navy two gun boats for the Mexican government, one cruiser and one

torpedo boat for the Brazilian government; the steam yachts Arrow, El-lide, Feiseen, Wauneta, Presto, and numerous other yachts and vessels.

SEND FOR DESCRIPTIVE CATALOGUE.

**MOSHER WATERTUBE BOILER CO., No. 1 Broadway, N. Y.**



### Detroit Scotch Water Tube Boiler

Internally Fired.

Scotch and Water Tube types combined, eliminating all objections.

Half the weight of ordinary Scotch boilers.


Standard corrugated furnaces.

Patent applied for.

Investigate before buying any other.

**EAST END BOILER WORKS**

**Detroit, Mich.**




### Taylor Water Tube Boiler Co.

Vertical Tubes, sectional, large steam space and liberating area. Fire box, combustion chamber, and course for the furnace gases similar to the Scotch Marine. Free circulation type.

Send for full description.

**322 Franklin St.  
DETROIT, MICH.**



### 250 STEAM VESSELS

Now Equipped With

### ALMY'S PATENT

**SECTIONAL**

**Water Tube Boilers**

Bear Evidence of Their


**Excellent Qualities**

**Almy Water-Tube  
Boiler Co.**

PROVIDENCE, R. I.

### John E. Thropp & Sons Co.

TRENTON, N. J.



Builders of Single, Compound, Triple-Expansion and Direct Connected Engines.

Boyer Sectional Water Tube boilers and machinery complete for light draft Passenger Boats, Yachts, Tugs, Etc.



### MARINE BOILERS

OF ALL TYPES

**KINGSFORD  
FOUNDRY &  
MACHINE  
WORKS,**

Oswego, N. Y.

### LATEST PATENT ANCHOR

### THE NATIONAL

APPROVED BY LLOYDS.

Manufactured by

**L. M. BOWERS & CO.,**

Binghamton, N. Y.

Catalogue on Application.

The National and International

### ANCHORS.

Furnished to the Lake Trade by

**The Upson-Walton Co.,**

CLEVELAND, O.



### Northwestern Steam Boiler & Mfg. Co.


DULUTH, MINN.

Manufacturers of

**BOILERS, ENGINES  
AND MACHINERY**

Special facilities for Marine Work. Repairs promptly attended to Night or Day.

We carry a complete line of Marine and Engineers' Supplies.



TELEPHONES: OFFICE AND WORKS, 615.  
RESIDENCE CALLS: M. A. F. VAN, Pres. and Gen'l Mgr., 776-R;  
J. H. OPPERMAN, Secretary, 579-R; E. KRIZ, Superintendent, 557-M.




## G. H. Breymann & Bro's

### CONTRACTORS FOR PUBLIC WORKS

Dredging, Dock Building, Etc.

5, 6 AND 7 MARINE BUILDING  
TOLEDO, OHIO.

## GREAT LAKES DREDGE & DOCK CO.



OWNS AND OPERATES THE PLANTS  
OF THE FORMER COMPANIES:

Lydon & Drews Co.  
Hausler & Lutz Co.  
Green's Dredging Co.  
Chicago Star Con. & D. Co.  
McMahon & Montgomery Co.  
Chicago Dredging & Dock Co.  
Griffith, McDermott & Watt  
Dredging Co.  
Duluth Dredge & Dock Co.

Contractors for

### RIVER AND HARBOR IMPROVEMENTS.

Main Office: 1319-1322 Chamber of Commerce - CHICAGO

## Buffalo Dredging Co.

### GENERAL CONTRACTORS —ON— SUBMARINE WORK

Office  
D. S. Morgan Bldg.

BUFFALO, N. Y.

## Hickler Brothers

SAULT STE. MARIE, MICH.

### MARINE RAILWAY

Capacity, 1,000 tons. Draft, 7½ ft.  
forward, 13½ ft. aft. Length on  
keel blocks, 180 ft.; over all, 190 ft.

Machine Shop, Foundry and Steam Forge,  
Dredges, Drill Boats and Derrick Scows.

## DUNBAR & SULLIVAN DREDGING CO.

BUFFALO, N. Y.

Will contract to remove ROCK or EARTH on the Great Lakes to 40 ft. depth.  
To remove ROCK on Atlantic Coast to 40 ft. depth.

THAT'S ALL.

We SOMETIMES rent plant to responsible parties at OUR terms.

**Dredges**  
Brian Boru, Steel.  
Tipperary Boy, Steel.  
Erin Go Bragh.

**Drill Boats**  
Geo. A. Howells and  
another, both Steel.

**Tugs**  
Shaugbraun, Steel  
Phil. Sheridan, Steel  
Spalpeen, Steel

Paddy Miles, Steel  
Shaun Rhue, Steel  
**Derrick**  
Faugh a Ballaugh

**Scows**  
Monroe Doctrine, 600 yds., Steel.  
Protective Policy, 500 yds., Steel.  
Reciprocity, 600 yds., Steel.  
Cuba Libre, 250 yds., Steel.  
Gold Standard, 250 yds., Steel.  
No. 5, 600  
No. 6, 600  
No. 7, 600  
No. 8, 600

4,600  
McMyler derrick handling 10 tons  
at 75 ft. radius.  
**Small Scows**

## H. W. HUBBELL CO.

### Submarine Work of all kinds

SAGINAW

MICH.

## The Fitz-Simons & Connell Co.

### CONTRACTORS —FOR— PUBLIC WORKS

DREDGING  
DOCKS  
PILE DRIVING  
BREAKWATERS

TUNNELS  
CANALS  
BRIDGES  
FOUNDATIONS

Offices: 1010-1014 Tacoma Building, Chicago.

## Lake Superior Contracting & Dredging Company

### GENERAL CONTRACTORS for PUBLIC and PRIVATE WORK RIVER AND HARBOR IMPROVEMENTS

Two 20-inch Hydraulic Dredges specially equipped  
for handling Clay, Gravel and all kinds of dredgeable  
material. Filling and reclaiming lands a specialty.

General Office, Wolvin Building

DULUTH, MINN

THE  
L. P. & J. A. SMITH  
COMPANY

**CONTRACTORS FOR PUBLIC WORKS**

Dredging	Dry Docks and	Bridges,
Harbor Work,	Pier Building,	Submarine
Pile Driving,	Railroads,	Foundations,
Breakwaters,	Canals,	Etc., Etc.

Offices: Williamson Bldg., CLEVELAND, O.

**J. RAYNER**  
MAHOGANY LUMBER  
VENEERS  
FOREIGN WOODS

Foot E. Houston St.  
NEW YORK CITY

Fulton & Morgan Sts.  
CHICAGO

**C. H. STARKE DREDGE & DOCK CO.,**

Contractors for Public Works.

**DREDGING, PILE DRIVING,  
—AND—  
SUBMARINE PIPE LAYING.**

Canal Street, West of First Avenue,  
Milwaukee, - - Wisconsin.

**CATALOGS  
WANTED.**

We are requested to inform the INDUSTRIALS of all branches that our French contemporary, "LE MOIS SCIENTIFIQUE ET INDUSTRIEL," of 8 rue Nouvelle at PARIS, 9°, has established an Information Branch from which particulars on any question may be obtained.

It is of great interest for all manufacturers to send regularly their "Catalogues" to "Le Mois Scientifique et Industriel" from where they will be forwarded to every one interested in the line.

*Do not delay* to send them and note the address is

**LE MOIS SCIENTIFIQUE ET INDUSTRIEL**  
8 rue Nouvelle at Paris--9°

Ask for a specimen notice free on application.

**N. SULLIVAN,**  
DREDGING OF ALL KINDS.


THE REMOVING OF DEEP  
WATER EARTH AND ROCK  
A SPECIALTY. - - -

53 Woodward Ave. Terrace,  
DETROIT, - - - MICH.

**PICKANDS, MATHER & CO.**

FUEL LIGHTERS at Buffalo, Erie, Ashtabula and Cleveland.

At Detour, Mich., a Fuel Dock equipped with shute capacity of 600 tons. Best quality Pittsburgh coal furnished at any time during Day or Night.



Western Reserve Building,

CLEVELAND, O.

**Steamboat Fuel at Ashtabula.**

Large Supplies of Best Quality.

Lighter Carrying Different  
Grades at all Times.



Fuel Scow with elevators and discharging spouts. Storage of 800 tons. Discharges 250 tons an hour into steamers while unloading cargo.

**M. A. Hanna & Co., Miners and Shippers,**  
Main Office, Perry-Payne Bldg., Cleveland.

Toledo Office, 429 Spitzer Bldg.

Cleveland Office, 610 Perry-Payne Bldg.

Fueling } Ironville Dock (Toledo Harbor)  
Plants } Huron Dock (Huron Harbor)

**THE IRONVILLE DOCK & COAL  
COMPANY**

**BITUMINOUS COAL**

For Steamboat Fuel and Cargo Shipment

CLEVELAND, OHIO.

610 Perry-Payne Building

Bell Phone Main 572



## Merchants Montreal Line

ST. LAWRENCE RIVER ROUTE  
PASSENGER STEAMERS

### CITY OF MONTREAL CUBA

Commencing June 15th, weekly service (Thursdays)  
to the following points:

Toronto Cornwall  
Kingston Prescott  
Brockville Montreal

For rates and further information apply to

G. E. JAKES & CO., Mgrs. W. J. FARASEY, Agent,  
Montreal, 107-115 River St.,  
Quebec. Tel. M 2049 Cleveland, O.



## THE CLEVELAND & BUFFALO TRANSIT COMPANY

UNPARALLELED NIGHT SERVICE  
The Twin Flyers of The Lakes

"CITY OF BUFFALO" "CITY OF ERIE"

Both together being, without doubt, in all respects the finest and fastest that are run in the interest of the traveling public in the United States.

TIME CARD.—DAILY INCLUDING SUNDAY. CENTRAL STANDARD TIME.

Leave CLEVELAND 8 p. m. Arrive BUFFALO 6:30 a. m.

" BUFFALO 8 p. m. " CLEVELAND 6:30 a. m.

Connections made at Buffalo for all Eastern and Canadian points;

at Cleveland for Toledo, Detroit and all points West and Southwest.

Tickets reading over L. S. & M. S. Ry. will be accepted

on this Company's Steamers without extra charge.

Special Low Rates Cleveland to Buffalo and Niagara Falls every

Saturday Night, also Buffalo to Cleveland. Ask Ticket Agents for

tickets via C. & B. Line. Send four cents for illustrated pamphlet.

W. F. HERMAN, G. P. A., Cleveland, O.

## "Graphite as a Lubricant"



A practical treatise on  
GRAPHITE LUBRICATION

52 pages. Illustrated  
COPIES FREE

Mention Marine Review

JOSEPH DIXON CRUCIBLE CO.

JERSEY CITY, N. J.

You do not have to guess at the speed of your  
vessel if equipped with the




## NICHOLSON LOG

The exact speed of the moment is constantly before you on a dial, and is recorded on a paper chart. The distance traveled is correctly shown on a counter. Guaranteed to register within 2%. No expense to operate if not abused. Wind the clock once a day and it will do its work automatically.

Catalogues and Full Information  
on request.

Nicholson Ship Log Co.  
204 Superior Street, CLEVELAND, O.

Thirty Years' Experience building



Engines  
and  
Propeller  
Wheels.

H. G. TROUT,  
King Iron Works,  
226 Ohio St.,  
BUFFALO, N. Y.

ESTABLISHED, 1854.



**SHERIFFS**  
MANUFACTURING CO.

Manufacturers of  
PROPELLER  
WHEELS  
Marine Engines  
and Repairs.


Milwaukee, Wis.

Phone S. 163

## YOU

will wonder how you ever  
got along without it, once  
you buy the

## Diamond Steam Flue Blower



The Diamond Blower in Operation

To overcome the difficulty we experienced last season in supplying the demand we suggest the placing of orders early for future delivery.

**POWER SPECIALTY CO.**

500 Washington St.

DETROIT, MICH.

**WARD LINE**THE NEW YORK & CUBA MAIL  
STEAMSHIP CO.POPULAR ROUTE TO  
**CUBA, NASSAU, MEXICO**FINEST AND LARGEST STEAMSHIPS SAILING  
FROM NEW YORK TO OTHER THAN EUROPEAN  
PORTS. HOLDERS OF THE RECORD BETWEEN  
HAVANA AND NEW YORK -- 1,240 MILES IN 61  
HOURS.FOUR SAILINGS EACH WEEK BETWEEN  
**NEW YORK and HAVANA.**WEEKLY SERVICE TO GUANTANAMO, SANTIAGO, MANZANILLO  
AND CIENFUEGOS, CUBA, PROGRESO, VERA CRUZ  
AND TAMPICO, MEXICO.SEMI-MONTHLY SAILINGS TO  
**Nassau, N. P. Bahamas.**

LOW RATES OF FREIGHT AND PASSAGE.

SEND FOR OUR SCHEDULES, RATES AND DESCRIPTIVE MATTER.

**James E. Ward & Co.**

GENERAL AGENTS

90 Wall Street, NEW YORK.

**AMERICAN LINE**PLYMOUTH  
CHERBOURG  
SOUTHAMPTON

Sailing From New York Every Saturday at 9:30 a. m.

**St. Louis**

(11,629 tons)

**New York**

(10,798 tons)

**St. Paul**

(11,629 tons)

**Philadelphia**

(10,786 tons)

Special Express Train from Plymouth and Southampton  
to London and between Cherbourg and Paris.**RED STAR LINE**NEW YORK  
ANTWERP  
LONDON  
PARIS

CALLING AT DOVER FOR LONDON AND PARIS.

Sailing Every Saturday at 10:30 a. m.

**Finland**

(12,760 tons)

**Vaderland**

(12,017 tons)

**Kroonland**

(12,760 tons)

**Zeeland**

(11,905 tons)

One of the Shortest Routes to LONDON, PARIS, BELGIUM, HOL-  
LAND, GERMANY, THE RHINE, SWITZERLAND AND ITALY

9 Broadway, New York.

Broad and Sansom Sts., Philadelphia.  
India Building, 84 State Street, Boston.  
1306 F St., N. W., Washington, D. C.  
219 St. Charles St., New Orleans  
90-96 Dearborn St., Chicago.  
Century Building St., Louis.  
Guaranty Building, S., Minneapolis.  
21 Post St., San Francisco.  
375 Robert St., St. Paul.  
41 King St., East Toronto.  
17 St. Sacramento St., Montreal.**PIERS: 14 & 15 NORTH****RIVER, FOOT OF FUL-****TON ST., NEW YORK.****United Fruit Co's  
Steamship Lines**

CARRYING FAST UNITED STATES AND FOREIGN MAILS.

**First-Class Passenger Service to Jamaica**

Weekly Sailings from

**BOSTON, PHILADELPHIA and BALTIMORE**

Fare One Way, \$40.00—Round Trip, \$75.00

For full information apply to  
**DIVISION PASSENGER AGENT**  
At either port.**"MALLORY LINE"**

(New York &amp; Texas Steamship Company)

Steamers Leave Piers New 15, 16 East River, NEW YORK

**For GALVESTON, TEXAS**Every WEDNESDAY and SATURDAY, taking FREIGHT for all Points in  
TEXAS, MEXICO, NEW MEXICO, ARIZONA, UTAH, KANSAS, OKLA-  
HOMA, MISSOURI, COLORADO and CALIFORNIA.

Saturday's Steamer touches at Key West, Fla.

**For MOBILE, ALA.**A Steamer sails every FRIDAY, 3 p. m., taking FREIGHT for ALABAMA,  
MISSISSIPPI, MISSOURI and the SOUTHWEST.**For BRUNSWICK, GA.**A Steamer sails every FRIDAY, 3 p. m., taking FREIGHT for all Points in  
GEORGIA, FLORIDA, ALABAMA, LOUISIANA and the SOUTH and  
SOUTHWEST.**PASSENGER DEPARTMENT**Six days Ocean voyage to GALVESTON, Texas, thence by rail to All points  
South-west. Six days to MOBILE, Ala., through tickets to NEW  
ORLEANS, 65 hours to BRUNSWICK, Ga., thence rail to Interior South-  
eastern Points.An especially attractive route through famous "SEA ISLANDS" to  
JACKSONVILLE, Florida.

Through Bill of Lading. Insurance at lowest rates.

**C. H. MALLORY & Co., General Agents,**  
129 Front Street Branch Office, 385 Broadway, New York.**BOSTON STEAMSHIP CO.**

S. S. "SHAWMUT" S. S. "TREMONT" S. S. "LYRA"

**Japan, South China and Manila Steamship Line**

Operated in connection with the

**Northern Pacific and Great Northern  
Railway Companies.**Monthly Passenger and Freight Service from  
Tacoma and Seattle, Washington.New Twin-screw American Steamships of  
10,000 tons register. Exceptionally large  
staterooms, all outside.OWING TO THE GREAT SIZE OF THE SHIPS,  
AND THE IMMENSE CARGOES CARRIED IT HAS  
NEVER BEEN NECESSARY TO USE RACKS ON  
THE DINING TABLES.

Rates at any office of

NORTHERN PACIFIC RAILWAY,  
GREAT NORTHERN RAILWAY,  
CHICAGO, BURLINGTON & QUINCY RAILWAY,  
THOMAS COOK & SONS, Tourists Agents.A. WINSOR, PRES.  
Boston, Mass.F. WATERHOUSE, AGENT,  
Seattle, Wash



## VESSEL AND INSURANCE AGENTS.

JOHN J. BOLAND & CO.,  
Vessel and Insurance Agents.  
800-804 Prudential Bldg.  
Both Phones. BUFFALO, N. Y.

C. W. Elphicke. J. J. Rardon.  
C. W. ELPHICKE & CO.  
Vessel and Insurance Agents.  
No. 6 Sherman St. CHICAGO, ILL.  
Telephone, Harrison 1194.

E. J. FLEMING & CO.  
Vessel and Insurance Agents.  
24-25 No. 6 Sherman St., CHICAGO.  
Office: Tel., Harrison 4975. Residence: Tel. Drexel 1736.

C. P. GILCHRIST & CO.  
Vessel and Insurance Agents.  
Sale and Exchange of Vessels a Specialty.  
Lumber and Coal Chartering.  
Full Telephone Service, Office and Residence. (Local and Long Distance.)  
411 Perry-Payne Bldg., Cleveland, O.

JOHN B. HALL,  
Vessel Agent.  
17 Exchange Bldg., 202 Main St.,  
Telephone, Seneca 892.  
BUFFALO, N. Y.

W. A. Hawgood. Arthur H. Hawgood.  
W. A. HAWGOOD & CO.  
Vessel and Insurance Agents.  
220-21 Perry-Payne Bldg., Cleveland, O.  
Telephones: { Office, Main 2395.  
{ Res. W. A. Hawgood, Doan 84-J.  
{ Res. A. H. Hawgood, Doan 841-J.

D. T. HELM & CO.  
Vessel and Insurance Agents.  
Telephones—Office 263.  
—Res. 381-3.  
DULUTH, - - - MINN.

SAMUEL HOLMES,  
Steamship Offices,  
For Selling, Chartering and Building all  
Classes Steam Vessels.  
Steam Vessel Circulars  
Weekly Freight Circulars.  
Morris Bldg., 66-8 Broad St., New York.

C. L. Hutchinson. W. H. McGean.  
HUTCHINSON & CO.  
Vessel and Insurance Agents.  
Phones: { Office, Main 2453.  
{ Res. C. L. Hutchinson, Lake 244.  
{ Res. W. H. McGean, Doan 274.  
1408 Rockefeller Bldg. Cleveland.

S. S. LESTER,  
Steamship Agent and Freight Broker.  
Manager Steamer  
ST. LAWRENCE,  
83 Dalhousie St. QUEBEC, QUE.

## VESSEL AND INSURANCE AGENTS.

T. R. MCCARTHY,  
Steamship and Freight Broker.  
Chartering, Forwarding and General Commission Agent; and Broker for the Sale, Purchase and Construction of Steamers and Sailing Vessels.

Cable Address, "Macarthy, Montreal."  
(Watkins', Scott's Liebers and A. B. C. Codes Used.)

Shipping Agent to The Asbestos & Asbestic Co., Ltd., of Danville, Que. The Belgo Canadian Pulp & Paper Co., Ltd., of Shawinigan Falls, Que. Edward Lloyd, Ltd. Paper Manufacturer, of London (Eng.).  
404 Board of Trade Bldg., MONTREAL, CAN.  
Correspondence Invited and Agencies Solicited.

J. Mitchell. J. F. Wedow. A. Mitchell.  
MITCHELL & CO.  
Vessel and Insurance Agents.  
508-10 Perry-Payne Bldg., Cleveland, O.  
Office Tel. M. 767. Res. John Mitchell, Doan 341.  
John F. Wedow, Doan 141-J.  
Alfred Mitchell, Doan 218.

PARKER BROS. CO., LTD.,  
Vessel, Marine Insurance and Wrecking Agents. Marine Surveyors.  
Office Tel. Main 5314. Night: Main 290  
Night: Grand 1723 J.  
15 Atwater St. West, DETROIT, MICH.

Insurance.  
PRINDIVILLE & COMPANY,  
Average Adjusters.  
Insurance Brokers.  
12 Sherman Street, CHICAGO.  
Representing: Johnson & Higgins, New York.

W. C. RICHARDSON,  
Vessel Owner and Broker and  
Marine Insurance Agent.  
420-421 Perry Payne Building,  
CLEVELAND, O.  
Office Tel. 338. Residence Tel. 2938.

D. Sullivan. F. J. Sullivan.  
D. SULLIVAN & CO.  
Vessel Agents.  
Marine Insurance.  
2-4 Sherman St., CHICAGO, ILL.  
Office Tel., Harrison 2847. Res. Ashland 2483.

MARINE INSURANCE,  
by  
WILLIAM GOW.  
Price, \$1.50.  
THE PENTON PUB. CO.,  
Cleveland, O.

NAVAL ARCHITECTURE,  
by  
THOS. H. WATSON.

A manual on laying off iron and steel vessels. Valuable for naval architects as well as beginners in ship yards.

Price, \$5.00.  
Order from  
THE PENTON PUB. CO.,  
Cleveland, O.

## PROCTORS IN ADMIRALTY.

WILLIAM F. CARROLL,  
Lawyer and Proctor in Admiralty  
Twenty years' general practice State and Federal Courts, Minnesota, New York and Illinois.  
613-59 Dearborn St. Chicago, Ill.  
Phone 4232 Central.

ALBERT J. GILCHRIST,  
Proctor in Admiralty.  
604 Perry-Payne Building.  
CLEVELAND, O.

GOULDER, HOLDING & MASTEN,  
Law Offices.  
H. D. Goulder. S. H. Holding. F. S. Masten.  
Perry-Payne Building,  
CLEVELAND, O.

HOYT, DUSTIN & KELLEY,  
Lawyers and Proctors in Admiralty.  
Offices, 702 Western Reserve Bldg.,  
CLEVELAND, O.

JENKINS, RUSSELL  
& EICHELBERGER,  
Attorneys-at-Law  
and Proctors in Admiralty.  
1520 Rockefeller Bldg. CLEVELAND.

C. E. KREMER,  
Counselor at Law and  
Proctor in Admiralty.  
Suite 821-822 New York Life Bldg.  
CHICAGO, ILL.

RAY G. MacDONALD,  
Attorney-at-Law and  
Proctor in Admiralty.  
1018 Hartford Building,  
Telephone, Central 2484 CHICAGO, ILL.

SHAW, WARREN, CADY & OAKES,  
Attorneys-at-Law  
and Proctors in Admiralty.  
Union Trust Bldg., Detroit, Mich.

WHITE, JOHNSON,  
McCASLIN & CANNON,  
Attorneys-at-Law and  
Proctors in Admiralty.  
Williamson Bldg., CLEVELAND, O.

HAND BOOK  
OF  
ADMIRALTY LAW,  
by  
ROBT. M. HUGHES,  
Price \$3.75.  
THE PENTON PUB. CO.,  
Cleveland, O.



## PROFESSIONAL.

## ROBERT W. HUNT &amp; CO.,

*Bureau of Inspection.  
Tests and Consultation.*

1121 The Rookery, CHICAGO.  
Monong. Bank Bldg., PITTSBURG.  
66 Broadway, NEW YORK.

Inspectors of shipbuilding material and machinery. Inspectors of all materials. Duty tests of engines and boilers. Physical and chemical laboratories.

## PROFESSIONAL.

James Nacey. Alexander Hynd.

**NACEY & HYND,**  
*Marine Architects.  
Mechanical Draughtsmen.  
Consulting Engineers.*

Specifications and designs for all descriptions of marine vessels, engines and boilers. Supervision of construction and repairs. Damage and other surveys carefully attended to.

Agents for Marine Specialties.

208-9 Western Reserve Building,  
CLEVELAND, O.  
Phone, Main 3339 J.

## PROFESSIONAL.

## W. J. WOOD,

*Naval Architect, Consulting Engineer.*

Prepares designs or working drawings and specifications for all classes of vessels and superintends construction and repairs. Surveys damaged property and estimates cost of repairs. Arbitrator and court expert.

FIRE BOATS A SPECIALTY.

Complete Plans furnished for Steel, Composite or Wooden Vessels.

921 Postal Telegraph Bldg.  
Tel. Harrison 1020. CHICAGO.

## JOSEPH KIDD,

*Marine Architect and Surveyor.  
Consulting Ship Builder and Engineer*

Over thirty years' experience. Specifications, designs and estimates. Superintendence of construction and repairs. Damage and other surveys carefully attended to. Negotiations for the building, charter or sale of all kinds of vessels and machinery.

610 Board of Trade,  
DULUTH, MINN.

FRED P. BELCHER,  
*Vessel and Insurance Agent,*  
430 Grain Exchange,  
WINNIPEG, MAN.  
P. O. Box 230.

**JUST PUBLISHED  
CLASS BOOK OF  
NAVAL ARCHITECTURE**

BY W. J. LOVETT Price \$2.50  
Illustrated Order from Marine Review, Cleveland.

**NAVAL ARCHITECTS' AND  
ENGINEERS' DATA BOOK,**

By T. H. WATSON.  
Price, \$1.50.  
THE PENTON PUB. CO.,  
Cleveland, O.

## BRITISH ADMIRALTY CHARTS

The latest Editions of Charts, Plans and Sailing Directions published by the British Admiralty. Can be obtained from Admiralty Agent by Appointment.

## J. D. POTTER,

OFFICIAL CATALOGUE  
OF CHARTS (380 pages) 1s.

145 MINORIES  
LONDON, ENGLAND

An abridged Catalogue of Charts of  
Nautical Books (free on application.)

## A NEW MAP

showing in detail the entire

## WATER FRONT OF BUFFALO, N. Y.

Giving Sounds, Principal Buildings, Railroad Connections, Etc. A copy will be forwarded to responsible parties for inspection, on request.

Price, Cloth Backed, \$7.00.

Marine Review,

Cleveland, O.



METALLIC LIFE BOATS AND  
RAFTS, YACHTS AND  
PLEASURE BOATS  
LIFE PRESERVERS

Outfit for Lake Steamers a specialty.

THOMAS DREIN & SON, Builders, Tatnell St. below Railroad  
WILMINGTON, DEL.

John Donnelly, Sr., Pres.  
H. B. Folger, Treas.

John Donnelly, Jr., Vice-Pres.  
Thos. Donnelly, Secy.

**THE  
DONNELLY SALVAGE & WRECKING CO., LTD.**  
KINGSTON, ONT.

DIVERS, STEAM PUMPS, TUGS, ETC.  
SUPPLIED ON SHORTEST NOTICE.

**Quintard  
Iron Works Company**

Office 742 E. 12th St.  
NEW YORK

MANUFACTURERS OF

**MARINE ENGINES,  
BOILERS**

Gas Works Apparatus,  
Sugar, Cement, Mining, Dredging  
and all kinds of Machinery.

N. F. PALMER, President

STEVENSON TAYLOR, Vice Pres.

GEO. Q. PALMER, Treas. and Genl. Mgr.

# GREAT LAKES REGISTER

FOR THE  
CLASSIFICATION OF STEEL AND WOODEN VESSELS.



COMBINED AND ISSUED IN CONNECTION WITH  
**BUREAU VERITAS**  
INTERNATIONAL REGISTER OF SHIPPING.

THE RATINGS OF GREAT LAKES REGISTER GO BEFORE AND ARE ACCEPTED BY THE LEADING UNDERWRITERS OF AMERICA AND EUROPE. VESSELS BUILT UNDER THE SUPERVISION OF ITS SURVEYORS WILL RECEIVE SPECIAL RATING, AND WILL ALSO BE PUBLISHED IN BUREAU VERITAS INTERNATIONAL REGISTER OF SHIPPING.

PLANS AND SPECIFICATIONS FURNISHED.

GREAT LAKES REGISTER SURVEYORS ARE ESTABLISHED AT ALL THE PRINCIPAL PORTS ON THE GREAT LAKES.

F. D. HERRIMAN, SURVEYOR GENERAL,  
320-322 Perry-Payne Building, CLEVELAND, O.

## FORE RIVER SHIPBUILDING CO.

Steel Ship and Marine Engine Builders.

CONTRACTORS FOR

U. S. Torpedo Boat Destroyers Lawrence and Macdonough.  
U. S. Protected Cruiser Des Moines.  
U. S. Battleships New Jersey and Rhode Island.  
U. S. Steam Light-Vessel No. 72.

Office and Works, QUINCY, MASS., U. S. A.

## W. & A. FLETCHER CO.

NORTH RIVER IRON WORKS.

*MARINE ENGINES, BOILERS, Etc.*

Hudson, 12th and 14th Sts., HOBOKEN, N. J.

Take Ferry from foot of West 22nd St., New York.

## The Atlantic Works, EAST BOSTON, Massachusetts.

BUILDERS OF

Steamships, Steam Yachts, Tow Boats, Etc.

Marine Engines, Boilers and Tanks.  
Heavy Machinery and Plate Iron Work.  
THREE MARINE RAILWAYS.

## THE SHIPOWNERS DRY DOCK CO.

CHICAGO, ILL.

Building and Repairing of Steel and Wooden Ships with economy and dispatch.

Yard and Dry Docks: Halstead St. and North Branch.  
Largest Dry Dock: 480 ft. on keel blocks.

Office, 381 No. Halstead St. Phone, North 1658.

CHARLES E. PECK.

WILLIAM A. PRIME.

## CHAS. E. & W. F. PECK,

Insurance Brokers. Average Adjusters.

ESTABLISHED 1870.

NEW YORK, 58 William Street.

BOSTON, 153 Milk St.

BUFFALO, 906 The Fidelity Bldg.

CLEVELAND, 1107-8 Williamson Bldg.

CHICAGO, 1115-16 Royal Insurance Bldg.

REPRESENTED BY

C. T. BOWRING & CO., (Insurance) LTD.,

5 and 6 Billiter Ave., LONDON,

and at "LLOYD'S" LONDON.

**HULLS and CARGOES.**

We place insurances in the most advantageous markets, employing, in the interest of our clients and with equal facility, all Foreign and Home companies, at the best procurable rates and terms.

**We Represent Only the Assured.**

THE "GAYNOR"

## Improved Cork Block Life Preservers

Wired and unwired. The new standard preservers. Best on the market. Unrivalled in reliability, construction, strength, quality and durability of materials. Approved by the Board of Supervising Inspectors of the Steamboat Inspection Service, at its meeting in Washington, D. C. December, 1904.

Manufactured by THE NATIONAL CORK CO.

261 Lorimer St., Brooklyn, N. Y.

Who will send circulars and prices. Or write to  
T. F. GAYNOR, 18 Broadway, N. Y., for particulars.

## GEO. STRATFORD OAKUM CO.

JERSEY CITY, NEW JERSEY.

Established  
1860



Manufacturers  
of all grades of

**Oakum**

Spun  
Cotton

FOR SALE AT SHIP CHANDLERS EVERYWHERE.

## The Martin-Barriss Co.

654 Seneca Street CLEVELAND, OHIO

IMPORTERS AND MANUFACTURERS OF

**MAHOGANY**

**WHITE MAHOGANY**

and all Native Cabinet Woods

High Grades of Kiln Dried Woods for Cabin Work and Inside Trim

**WHITE OAK TIMBERS AND PLANK**

Constantly on Hand and Sawed to Order on Short Notice



# PRACTICAL SHIPBUILDING:

A Treatise on the Structural Design and Building of Modern Steel Vessels. The Work of Construction, from the Making of the Raw Material to the Equipped Vessel, including subsequent Upkeep and Repairs.

By A. CAMPBELL HOLMS,

Member of the Institution of Naval Architects and of the Institution of Engineers and Shipbuilders in Scotland; Surveyor to Lloyd's Register of Shipping. 2 vols. (Vol. I., Text. Medium 8vo. Vol. II., Diagrams and Illustrations. Oblong 4to.)

The plan of the book is briefly as follows: First, attention is given to the fundamental matters which govern the structural design; the various stresses to which the hull is exposed, their straining tendency, and the different structural designs by which the necessary strength to resist them may be secured. Secondly, each important part of the hull is considered by itself, and each one from three points of view viz., its purpose in the structure and the particular stresses and straining effects to which it is liable; the various formations adopted in its design, with the rules governing them as regards scantlings and strength; and a description of the actual work of making it in a shipyard and fitting it to the ship. As a description of the actual work of the shipyard is reading of a special character, it is dealt with separately in the second part of the book, the sequence generally being thus better preserved.

\$16.00, EXPRESSAGE EXTRA.

THE PENTON PUBLISHING COMPANY

::

::

::

::


CLEVELAND.

## ALPHABETICAL INDEX OF ADVERTISERS IN THE MARINE REVIEW.

The star (\*) indicates that the advertisement appears alternate weeks. For addresses see advertisements on pages noted. The dagger (†) indicates that advertisement appears once a month.

Almy Water Tube Boiler Co. .... 49	East End Boiler Works ..... 49	Lake Superior Contracting & Dredging Co. .... 50	Rayner, J. .... 51
American Injector Co. .... 7	Elphicke, C. W., & Co. .... 54	Le Mois Scientifique et Industriel 51	Red Star Line. .... 53
American Line. .... 53	Falls Hollow Staybolt Co. .... 58	Lester, S. S. .... 54	Rice, Henry, and Lovejoy, H. O. .... 55
American Ship Building Co. .... 4	Fitz-Simons & Connell Co. .... 50	Link Belt Machinery Co. .... 13	Richardson, W. C. .... 54
American Ship Windlass Co. .... 2	Fix's, S. Sons .... 58	Lockwood Mfg. Co. .... 58	Ritchie & Sons, E. S. .... 45
Armstrong Cork Co. .... 60	Fleming & Co., E. J. .... 54	Long-Arm System Co. .... 45	Roberts Safety Water-Tube Boiler Co. .... 15
Ashton Valve Co. .... 43	Fletcher, W. & A., Co. .... 56	Lunkenheimer Co. .... 15	Roelker, H. B. .... 58
Atlantic Works .... 56	Fogg, M. W. .... 58	McCarthy, T. R. .... 54	Ross Valve Co. .... 58
Atlantic Works, Inc. .... 14	Fore River Shipbuilding Co. .... 56	McCurdy, Geo. L. .... 43	
Baker, Howard H., & Co. .... 60	Gaynor, T. F. .... 55	McMyler Mfg. Co. .... *	Safety Car Heating & Lighting Co. .... 5
Belcher, Fred P. .... 55	General Electric Co. .... 60	MacDonald, Ray G. .... 54	Safety Fire Extinguisher Co. .... 14
Bird-Archer Co. .... Cover	Gilchrist, Albert J. .... 54	Mallory Line .... 53	Scherzer Rolling Lift Bridge Co. .... 12
Boland, J. J. .... 54	Gilchrist & Co., C. P. .... 54	Marine Iron Co. .... *	Schrader's Son, Inc., A. .... 58
Bonner & Co., Wm. T. .... 11	Goulder, Holding & Masten 54	Marine Iron Works. .... 3	Shaw, Warren, Cady & Oakes. .... 54
Boston & Lockport Block Co. .... 2	Greacen-Derby Engineering Co. 14	Marine Mfg. & Supply Co. .... 56	Shelby Steel Tube Co. .... *
Boston Steamship Co. .... 53	Great Lakes Dredge & Dock Co. 50	Martin-Barriss Co. .... 9	Sheriffs Mfg. Co. .... 52
Bourne-Fuller Co. .... 43	Great Lakes Engineering Works 18	Maryland Steel Co. .... 10	Shipowners' Dry Dock Co. .... 56
Bowers, L. M., & Co. .... 49	Great Lakes Register .... *	Mayo & Bailey. .... 9	Smith Co., L. P. & J. A. .... 51
Braymann & Bros., G. H. .... 50	Great Lakes Towing Co. .... 56	Merchants Montreal Line. .... 52	Smith Coal & Dock Co., Stanley B. 9
Brown Hoisting Machinery Co. Inc. 2	Hall, John B. .... 54	Mietz, Aug. .... 13	Smith, Stanley B., & Co. .... 9
Buffalo Dredging Co. .... 50	Hanna, M. A., & Co. .... 51	Milwaukee Dry Dock Co. .... 5	Smooth-On Mfg. Co. .... 59
Buffalo Dry Dock Co. .... 5	Hawgood & Co., W. A. .... 54	Mitchell & Co. .... 54	Stamford Foundry Co. .... 45
Bunker, E. A. .... 59	Helm & Co., D. T. .... 54	Morse & Son, A. J. .... 58	Standard Oil Co. .... 59
	Hickler Bros. .... 50	Mosher Water-Tube Boiler Co. 49	Starke Dredge & Dock Co., C. H. 51
Carroll, Wm. F. .... 54	Holmes, Samuel. .... 54	Moulton Steering Engine Co. .... 58	Stirling Co. .... 15
Chase Machine Co. .... 15	How, B. V. .... 17	Nacey & Hynd. .... 55	Stratford Oakum Co., Geo. .... 56
Chicago Ship Building Co. .... 4	Hoyt, Dustin & Kelley. .... 54	National Cork Co. .... 55	Sturtevant Co., B. F. .... 60
Cleveland & Buffalo Transit Co. 59	Hubbell Co., H. W. .... 50	Newport News Ship Building & Dry Dock Co. .... 6	Sullivan, M. .... 51
Cleveland City Forge & Iron Co. 54	Hunt, Robert W., & Co. .... 55	New York & Cuba Mail S. S. Co. 53	Sullivan & Co. .... 54
Continental Iron Works. .... 2	Hutchinson & Co. .... 54	New York Shipbuilding Co. .... 16	Superior Ship Building Co. .... 4
Cowing, John P. .... 3	Hyde Windlass Co. .... 11	Nicholson Ship Log Co. .... 52	Sutton Co., C. E. .... 58
Cory, Chas. & Son. .... 58		Northwestern Steam Boiler & Mfg. Co. .... 49	
Craig Ship Building Co. .... 5	International Mercantile Marine Co. 53	Otis Steel Co. .... 3	Taylor Water-Tube Boiler Co. .... 49
Cramp, Wm. & Sons, S. & E. B. Co. 8	Ironville Dock & Coal Co. .... 51	Parker Bros. Co. .... 54	Thropp, J. E., & Sons Co. .... 49
Crandall & Son, H. I. .... 17	Jenkins Brothers. .... 60	Parsons, Ralph M. .... 12	Tietjen & Lang Dry Dock Co. .... 60
Crane Co. .... 14	Jenkins, Russell & Eichelberger. 54	Peck, Chas. E. & W. F. .... 56	Trout, H. G. .... 52
	Kahnweiler's Sons, David .... 59	Pemberthy Injector Co. .... 7	Truscott Boat Mfg. Co. .... 7
Dearborn Drug & Chemical Wks. 9	Katzenstein, L., & Co. .... 59	Pickands, Mather & Co. .... 51	
Dearing Water Tube Boiler Co. 17	Kidd, Joseph .... 55	Pittsburg Coal Co. .... 9	United Fruit Co. .... 53
Delaunay Belleville & Co. .... 43	Kieley & Mueller. .... *	Potter, J. D. .... 55	Upson-Walton Co. .... 60
Delaware River Iron S. B. & E. Works 59	Kingsford Foundry & Machine Works 49	Power Specialty Co. .... 52	
Detroit Ship Building Co. .... 4	Kremer, C. E. .... 54	Prindville & Co. .... 54	Walker, Thomas, & Son. .... 2
Dixon Crucible Co., Joseph .... 52		Quintard Iron Works Co. .... 55	Ward Line. .... 53
Donnelly Salvage & Wrecking Co. 55			Watson-Stillman Co. .... *
Drein, Thos., & Son. .... 55			White, Johnson, McCaslin & Cannon. .... 54
Dunbar & Sullivan Dredging Co. 50			Wood, W. J. .... 55
			Woodhouse Chain Works. .... 7





## Chas. Cory & Son

Manufacturers of

Mechanical and Electrical  
Telegraphs and Indicators.  
Engine Bells and Electric  
Call Bells.

278-279 Division St.  
NEW YORK CITY.



Makers of only the Highest Quality of Staybolt Material, in Hollow and Solid Bars, from the Best Double-Refined Charcoal Iron or Steel. **FALLS HOLLOW STAYBOLT IRON** Is the only Reliable Flexible Staybolt in the World.

The Only Staybolt Iron which responds in service to the expansion and contraction of fire box; which relieves the material in molecular strains; which is self protective from burning; which does not make the side sheets crack; which earns its own cost in oxygen through it to the fire; always sure in giving warning of breakage.

The Staybolt which lasts longest, requires least repairs, gives longest life to the fire box, and the longest service in the engine on the rails. In use by Leading Railways of the United States, Canada, Mexico, Japan and Norway. Also by Marine Engineers and the United States Government. And by the Manufacturers of Mining Drills and by others requiring absolutely reliable material.

## THE ALLEN DENSE-AIR ICE MACHINE

Contains no chemicals, only air. Proven by many years' service in the tropics on United States men-of-war, steam yachts and passenger steamers. A hundred are in daily service on steamers.

H. B. ROELKER, 41 Maiden Lane, NEW YORK.

Consulting and Con-  
structing Engineer.

Designer and Manufacturer  
of Screw Propellers.




Established 1844  
**A. SCHRADER'S SON, Inc.**  
32 Rose Street, NEW YORK  
Manufacturer of

**Submarine Armor and Diving Apparatus**  
We carry a complete stock of Dresses, Hose and  
Repair Sundries.

Improved Bolt Helmet All orders filled day received Write for our prices

## A STEAM STEERER DIRECT AND POSITIVE



**QUICK ACTING**  
Especially  
adapted for  
Steam Yachts  
Ferryboats  
Lake, Ocean  
and Harbor  
Tug Boats.  
Send for Cata-  
logue and  
Particulars.

**MOULTON STEERING ENGINE CO.,** 1691 BROADWAY  
NEW YORK CITY.


## Water Filters, Regulators and Engines.

We make **Pressure Regulating  
Valves** for all purposes, steam or  
water.

Our **Feed-Water Filter** will keep  
oil out of your boiler.

We can interest you if you use a condenser.

**Water Engines for Pumping Organs**



**Water Works  
Regulating Valve**  
Has no peer. Ask for  
list of Water Works  
using our valves.

**THE ROSS VALVE CO.** TROY  
N.Y.

## The Lockwood Manufacturing Co.

EAST BOSTON, MASS.

ENGINEERS AND MACHINISTS.

Builders of Steamships, Tow Boats and Marine Engines.

Repairing of Hulls and Machinery.

## The C. E. Sutton Company

Toledo, Ohio, U. S. A.

Manufacturers of

PUNCHES and SHEARS, FORGING MACHINES, STEEL  
and IRON GREY CASTINGS

**Marine Castings a Specialty**

## M. W. FOGG

**Mattresses  
and Cushions**



202 Front St.

NEW YORK CITY.

ORAM FIX

ESTABLISHED 1860

J. W. FIX

## S. FIX'S SONS

SUCCESSORS TO S. FIX & SON.

## Steam Flue Welding Works

Our work stands government test. Our Welds are perfectly smooth.  
Write us for prices.


COR. LEONARD AND WINTER STS

CLEVELAND, O.



# Vacuum

## No. 1 MARINE ENGINE OIL




for the Lubrication of Steamers' Crank-Pins.

Holds the World's Record.


**STANDARD OIL CO., of New York**

## ROACH'S SHIP YARD.



Ship Building in all its Branches

Builders of  
**STEAMSHIP AND MARINE MACHINERY.**  
Delaware River Iron Ship Building & Engine Works,  
Chester, Pa.



### Katzenstein's Self-Acting Metal Packing

For PISTON RODS, VALVE STEMS, etc. of every description for Steam Engines, Pumps, etc., etc. Adopted and in use by the principal Iron Works and Steamship Companies in this and foreign countries.

**FLEXIBLE TUBULAR METALLIC PACKING**, for slip-joints on Steam Pipes, and for Hydraulic Pressure; also **METAL GASKETS** for all kinds of flanges and joints.

For full particulars and reference, address

**L. KATZENSTEIN & CO.**

GENERAL MACHINISTS, BRASS FINISHERS, ENGINEERS' SUPPLIES.  
358 West street, New York.

## Neversink Cork Jackets and Life Belt

Warranted 24 pounds. Buoyancy and full weight of Cork, as required by U. S. Inspectors.

### Safest Consolidated Cork Life Preservers. Ring Buoys and Fenders. Cheapest

Approved and adopted by U. S. Board of Supervising Inspectors. Also adopted by the principal Ocean, Lake and River Steamer Lines as the only Reliable Life Preserver. Awarded four Medals by World's Columbian Exposition.



**Metallic and Wooden Life Boats.**



**Metallic Life Rafts. Marine Drags.**  
Manufacturers of Woolsey's Patent Life Buoy—the lightest, cheapest and most compact life raft known.

**DAVID KAHNWEILER'S SONS,**  
Fox Building, Cor. Franklin Sq. and Dover Street,  
NEW YORK CITY.



**LIGHT  
STRONG  
DURABLE**

**CLOTH  
THAT'S IN  
DEMAND**

TRADE MARK


**Wilford's Waterproof Cloth** is made of twisted pure flax thread. It is pliable—will not crack, and much stronger than cotton. Impenetrable by salt or fresh water. Suitable for Tarpaulins, sail, hatch or boat covers, etc. A superior waterproof cloth. Test its merits.

**EDWARD A. BUNKER**

Sole Agent for the United States and Canada

P. O. BOX 1579, NEW YORK

## CLEVELAND CITY FORGE & IRON CO.




BEAM STRAP FOR STEAMER "PURITAN"

WOODS FRAME FOR UNITED STATES CRUISER "NEW YORK"

**CLEVELAND, O.**

IRON OR STEEL FORGINGS FINISHED COMPLETE, ROUGH MACHINED OR SMOOTH FORGED ONLY. OF ANY WEIGHT. COUPLING LINKS AND PINS. PRESSED WROUGHT IRON TURNBUCKLES. CAR IRON SPECIALTIES.




**Smooth-On  
Elastic  
Cement**  
will stop leaks

Write for new instruction book

**SMOOTH-ON MFG. CO.**

JERSEY CITY, N. J., U. S. A.

## LIGHTING SETS FOR STEAM YACHTS.




Built to U. S. Navy Dept specifications in a line of sizes from 3 to 100 K. W. Each engine is equipped with forced lubrication watershed partition and oil tight case. The minimum of weight and space is secured for a given output.

**B. F. STURTEVANT CO.**  
BOSTON, MASS.

General Office and Works, Hyde Park, Mass.  
New York Philadelphia Chicago London

Designers and builders of Heating, Ventilating, Drying and Mechanical Draft Apparatus; Fans, Blowers and Exhausters; Steam Engines, Electric Motors and Generating Sets; Fuel Economizers; Forges, Exhaust Heads, Steam Traps, Etc.

**Tight Joints** can only be maintained by the use of high grade flange packing. **Jenkins '96 Packing** is unequalled for durability. It is absolutely guaranteed.



All genuine bears  
**Trade Mark**  
as shown in the cut.

Write for Booklet  
"POINTS ON PACKING"

JENKINS BROS., New York, Boston, Philadelphia, Chicago, London.

## General Electric Company

Original designers  
of marine  
generating sets.

Principal Office: SCHENECTADY, N. Y. Sales offices in all large cities.



See our stock of . . .

## Lanterns and Signal Lights

Orders promptly filled and our guarantee goes with everything we sell.

**The UPSON-WALTON Co.**  
CLEVELAND, O.

## LIFE PRESERVERS—BUOYS

ACME. SOLID CORK. Each Preserver stamped by U. S. Inspector guaranteeing proper buoyancy. Cork Filled Yacht Fenders. Cork Mooring Buoys. Material and Finish Guaranteed. Orders filled promptly.

**ARMSTRONG CORK COMPANY**

Boston New York Philadelphia Pittsburg  
Chicago St. Louis Baltimore

## HOWARD H. BAKER & CO.

SHIP CHANDLERS  
and SAIL MAKERS

18 to 26 Terrace, BUFFALO, N. Y.

## Tietjen & Lang Dry Dock Co.

HOBOKEN, N. J.

**EIGHT DRY DOCKS**

600, 800, 1,000, 1,200, 1,400, 1,800, 2,000, 10,000 TONS.

General Repairs on Wooden and Iron Vessels.

FT. OF 17th STREET

Telephone 700 Hoboken

HOBOKEN, N. J.